## BILL OF MATERIAL

ITEM	UNIT	TOTAL
Epoxy Crack Injection	Foot	40
Structural Repair of Concrete (Depth Greater Than 5 Inches)	Sq. Ft.	10
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	10


indicates Epoxy Crack Injection

- Pier 1 only

indicates Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)

## NOTES:

- The quantities shown are provided as a contingency for estimating purposes only. The area to be repaired shall be determined by the Engineer at the time of construction. Actual repair locations shall be shown on the as-built plans.
- 2. Crack widths are  $\frac{1}{8}$ "  $\pm \frac{1}{16}$ " unless otherwise noted.



**ELEVATION** 

(Looking South)

26′-0′′

TOP PLAN

2

3'-0"

6'-3"

(5)

(4)

END VIEW (Looking East)

**ELEVATION** (Looking North)

END VIEW (Looking West)

DESIGNED -

3'-0"!

(1)

diffed benesch & company Engineers · Surveyors · Planners Cok Borth Michigan Avenue, Suite 2400 Chicago, Illinois 60801 Job No. 3808.02

SHEET NO. S30 RTE. TOTAL SHEET NO. SECTION COUNTY 04-00090-07-BR WILL 57 38 S47 SHEETS CONTRACT NO. 63442 FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

PIER 1 AND 2 REPAIRS

STRUCTURE NO. 099-3298