
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	LASALLE		TOTAL	SHEET NO.
B. B. I. F. A.	(3)BR-1			44	29
FED. ROAD DIST, NO. 7		ILLINOIS	FED. AID PROJECT-		

SHEET NO. 19

OF 23 SHEETS



NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (I) 1"x7"x10" steel 12 to the
fop layer of couplers with 2-5g" \$\phi\$ bolts

screwed to coupler at approximate \$\mathbb{Q}\$ of
each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) 1"x7"x10" steel 1 to the concrete slab or concrete wearing surface with 2-58"\$\phi\$ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \$\mathbb{L}\$ of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier.
The I'' x 7'' x 10'' plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.


SECTIONS THRU SLAB OR DECK BEAM


***Dimension shown is minimum required embedment into concrete.

If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

****If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not







STEEL RETAINER P 1" x 7" x 10"

* Required only with Detail II

TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
US ROUTE 52 AND IL ROUTE 23 OVER
CROOKED LEG CREEK
F.A.P. ROUTE 68 SECTION (3) BR-1
LASALLE COUNTY
STATION 419+80.00
STRUCTURE NUMBER 050-0240

^{**}Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.