CONTRACT NO. 70529

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(102X)BR,BR-3	MCLEAN	42	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

G.N.-781

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

AS A RESULT OF RIGHT OF WAY NEGOTIATIONS, PLEASE BE ADVISED OF THE THE FOLLOWING:

ED AND LINDA DONOVAN HAVE SELECTED 4 OCTOBER GLORY RED MAPLE TREES. MR. AND MRS. DONOVAN HAVE ALSO REQUESTED THAT THE CONTRACTOR CONTACT THEM PRIOR TO CONSTRUCTION. THEY ARE INTERESTED IN ACCOMMODATING THE CONTRACTOR IN REGARDS TO PARKING AND STORING EQUIPMENT ON THEIR PROPERTY. THE DONOVANS CAN BE CONTACTED AT (309) 962-8117 ANY WEEKDAY MORNING.

GARY AND JANET BRENT HAVE REQUESTED THE FOLLOWING TREES AS REPLACEMENTS:

2 RED MAPLES
3 PINK OAKS
3 RED OAKS

THE BRENTS CAN BE REACHED AT (309) 962-9135 FOR REPLACEMENT OF THE TREES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES
F.A.P. ROUTE 315
SECTION (102X)BR,BR-3
MCLEAN COUNTY

DRAWN BY
DATE CHECKED BY

PLOT DATE = 1/28/2014
FILE NAME = c:\pwworking\PWIDOT\SHERER2\d1806598\D570529-sht-gennotes.dgn
PLOT SCALE = 0.0548 m / IN.
USER NAME = sherer_jm