INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS & LIST OF STANDARDS
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	EXISTING TYPICAL CROSS SECTIONS
6-7	SCHEDULE OF QUANTITIES

LIST OF STANDARDS

STANDARD NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
420701-02	PAVEMENT FABRIC
442101-07	CLASS B PATCHES
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5 (15') AWAY
701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701201-03	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 M.P.H.
701901-01	TRAFFIC CONTROL DEVICES

GENERAL NOTES

GENERAL NOTES

G.N. - 100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-440B

THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-442B - PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N. - 442(SPL)

IT IS NOT THE INTENT OF THE DISTRICT TO DISTURB ANY DETECTOR LOOPS WITHIN THE PROPOSED SECTION. IF AN EXISTING DETECTOR LOOP IS IN CONFLICT WITH A PROPOSED PATCH LOCATION, THAT LOCATION SHALL BE DELETED FROM THE PLANS OR MOVED TO NOT INTERFERE WITH THE EXISTING DETECTOR LOOP.

G.N.-1004.0

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

ILE NAME = USER NAME = keysrb		DESIGNED -	REVISED	Γ
::\pw.work\pwidot\keysrb\d0178439\D570824-sht-Gennote.dgn		DRAWN -	REVISED -	
	PLOT SCALE = 40.0000 '/ IN.	CHECKED -	REVISED -	ĺ
	PLOT DATE = 2/3/2010	DATE -	REVISED -	

STATE	: OF	ILLINOIS	
EPARTMENT	0F	TRANSPORTATION	

	INDEX AT AUTOMA LIAN AN ANALYSINA				F.A.S.	SECTION	COUNTY	TOTAL	SHEET	
INDEX OF SHEETS, LIST OF STANDARDS,						RTE. SECTION		000.,,	SHEETS	NO.
AND GENERAL NOTES				•	533	106PT	CHAMPAIGN	7	2	
THE WARRIETS HOLD								CONTRACT	NO. 7	70824
	SHEET NO	. OF	SHEETS	STA.	TO STA.	FED. RO	AD DIST. NO. ILLINOIS FED. AI	D PROJECT		