

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		100% STATE	I000
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
20201000	GRADING AND SHAPING ROADWAY	UNIT	117.0	117.0
25000200	SEEDING, CLASS 2	ACRE	3.5	3.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	315	315
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	315	315
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	315	315
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7	7
25100115	MULCH, METHOD 2	ACRE	3.5	3.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	700	700
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	5,850	5,850
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	3,380	3,380
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	270	270
40300600	SEAL COAT AGGREGATE	TON	1,700	1,700

• LAGRANGE WETLAND BANK
 ** D6 WETLAND MITIGATION 4

FILE NAME =	USER NAME = leughlinr1	DESIGNED -	REVISED -
c:\pw\work\PWIDOT\LAUGHLINRL\dms28174\tsaq.dgn		DRAWN - EJW	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED - JCN	REVISED -
PLOT DATE = Feb-03-2010 04:21:08PM		DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	BROWN	37	3
CONTRACT NO. 72968				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				