

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	BROWN	9	4


STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* LA GRANGE WETLAND BANK
 ** D-6 WETLAND MITIGATION NO. 6

LOCATION	SEEDING SCHEDULE				
	MOWING (ACRE)	HERB. SPRAYING (GALLON)	SEEDING CL 2 SPL (ACRE)	SEEDING CL 4 (MOD) (ACRE)	MAIN. MOWING (ACRE)
FIELD * 12, 13 & 15	20	12.7	20	0	72
SW PART FIELD * 15	22.4	14.3	0	22.4	0
TOTAL =	42.4	29	20	22.4	72


ITEM	TREE PLANTING SCHEDULE	
	LOCATION FIELD #11 & #14 (EACH)	TOTAL (EACH)
TREE, CARYA CORDIFORMIS (BITTERNUT HICKORY), CONTAINER GROWN, 3-GALLON	360	360
TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON	360	360
TREE, CARYA ILINOENSIS (PECAN), CONTAINER GROWN, 3-GALLON	360	360
TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON	360	360

TYPICAL CONTAINER TREE PLANNING PLAN



NOTE:
 PIT size should be the same size as the root ball or slightly larger; this will reduce tipover during flooding.

TYPICAL MAINTENANCE PATTERN



NOTE: VEGETATION SHALL BE MOWED IN A NORTH/SOUTH OR EAST/WEST PATTERN. AREAS SHALL BE MOWED IN "ONE" DIRECTION ONLY AND MOWED PATHS SHALL BE PARALLEL AS DIRECTED BY THE ENGINEER.

CROSS MOWING WILL NOT BE PERMITTED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. / HORIZ. / DATE

DRAWN BY BDK / CHECKED BY