

MODEL: Default
FILE NAME: c:\pwworking\ual\dm20760\180B68-sh1-SQ-Q-01.dgn



USER NAME = dominguez1	DESIGNED - NRH	REVISED -
	DRAWN - NRH	REVISED -
PLOT SCALE = 2.000" / in.	CHECKED - SPF	REVISED -
PLOT DATE = 2/2/2026	DATE - 2/2/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 59 (FROM MCCOY DR TO ARTESIAN RD)

SCALE: SHEET 1 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2025-2023-PP	DUPAGE	69	3
CONTRACT NO. 80B68				
ILLINOIS FED. AID PROJECT				

 REVISED SHEET 4/06/2026

* = SPECIALITY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TYPE CODE		
				ROADWAY	ROADWAY	TRAFFIC SIGNALS
				100% STATE	100% STATE	100% STATE
				0006	0006	0021
				URBAN	URBAN	URBAN
20200100	EARTH EXCAVATION	CU YD	95	95		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,129	1,129		
25200110	SODDING, SALT TOLERANT	SQ YD	1,129	1,129		
25200200	SUPPLEMENTAL WATERING	UNIT	61	61		
28000400	PERIMETER EROSION BARRIER	FOOT	825	825		
28000510	INLET FILTERS	EACH	237	237		
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	6	6		
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	6	6		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	77,751	77,751		
40600370	LONGITUDINAL JOINT SEALANT	FOOT	72,606	72,606		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	218	218		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	514	514		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3,110	3,110		
40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	5,006	5,006		

MODEL: Default
FILE NAME: c:\pwworking\usildms20760\180B68-shl-SQ-03.dgn



USER NAME = dominguez1	DESIGNED - NRH	REVISED -
	DRAWN - NRH	REVISED -
PLOT SCALE = 2.000" / in.	CHECKED - SPF	REVISED -
PLOT DATE = 2/2/2026	DATE - 2/2/2026	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 59 (FROM MCCOY DR TO ARTESIAN RD)

SCALE: SHEET 3 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	2025-2023-PP	DUPAGE	69	5
CONTRACT NO. 80B68				
ILLINOIS FED. AID PROJECT				

REVISED SHEET 4/06/2026

* = SPECIALITY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TYPE CODE		
				ROADWAY	ROADWAY	TRAFFIC SIGNALS
				100% STATE	100% STATE	100% STATE
				0006	0006	0021
				URBAN	URBAN	URBAN
60262700	INLETS TO BE RECONSTRUCTED	EACH	16	16		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10		
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	10		
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5		
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	299	299		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	592	592		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	673	673		
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	221	221		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CUYD	95	95		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3		
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1		
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1		