

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	1
		ILLINOIS	CONTRACT NO. 66N58	

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS, AND HMA TABLE
- 3-9 SUMMARY OF QUANTITIES
- 10 TYPICAL SECTIONS
- 11-13 SCHEDULE OF QUANTITIES
- 14-15 ALIGNMENT, TIES, AND BENCHMARKS
- 16 REMOVAL PLAN
- 17 PLAN AND PROFILE
- 18-22 MAINTENANCE OF TRAFFIC PLAN
- 23 EROSION AND SEDIMENT CONTROL PLAN
- 24 LANDSCAPING PLAN
- 25-44 STRUCTURE PLANS
- 45 TRANSITION DETAIL
- 46-48 DISTRICT 3 DETAILS
- 49-56 CROSS SECTIONS

FOR LIST OF HIGHWAY STANDARDS, SEE SHEET NO. 2

**PROPOSED  
HIGHWAY PLANS**


**FAU ROUTE 392 (US 6)  
SECTION (G-BR)BR-1  
STRUCTURE REHABILITATION  
GRUNDY COUNTY**

C-93-137-25

STRUCTURE REHABILITATION  
(OVER AUX SABLE CREEK)  
STA. 250+74.25  
S.N. 032-0025

BEGIN IMPROVEMENT (US 6)  
STA 246+50


END IMPROVEMENT (US 6)  
STA 256+00



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.  
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION  
1-800-892-0123  
OR 811


LOCATION MAP  
NOT TO SCALE




STATION EQUATION  
253+87.63 BK =  
253+87.11 AH

GROSS LENGTH = 950.00 FT. = 0.180 MILE  
NET LENGTH = 950.00 FT. = 0.180 MILE


PROJECT ENGINEER: JOSEPH KANNEL, PE  
SQUAD LEADER: MOHAMED YOUSIF  
TOWNSHIP(S): AUX SABLE TOWNSHIP  
CONTRACT NO. 66N58



TRAFFIC DATA - US 6  
MINOR ARTERIAL; 2025 ADT = 7550  
P.V. = 85.5% S.U. = 6.6% M.U. = 7.9%



Signed: *Robert Brzezona*  
Date: 2/4/2026  
License Expires: 11/30/2027  
The seal shown above is valid for Sheets 1-24 and 45-56.



Signed: *Alex C. Benz*  
Date: 2/4/2026  
License Expires: 11/30/2026  
The seal shown above is valid for Sheets 25-44.

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUBMITTED February 4, 2026

*Trisha Thompson*  
REGIONAL ENGINEER

March 20, 2026  
*[Signature]*  
ENGINEER OF DESIGN AND ENVIRONMENT

March 20, 2026  
*[Signature]*  
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY  
OF THE STATE OF ILLINOIS

**EFK•Moen**  
Civil Engineering Design

## HIGHWAY STANDARDS

000001-09	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
482011-03	HMA SHOULDER STRIPS/SHOULDERS WITH RS OR WIDENING & RS PROJECTS
515001-04	NAME PLATE FOR BRIDGES
630001-13	STEEL PLATE BEAM GUARDRAIL
630201-07	PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
630301-09	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631031-18	TRAFFIC BARRIER TERMINAL, TYPE 6
667101-02	PERMANENT SURVEY MARKERS
701001-02	OFF-ROAD OPERATIONS 2L, 2W, MORE THAN 15' AWAY
701006-05	OFF-ROAD OPERATIONS 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701201-05	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-04	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701321-19	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING FOR SPEEDS ≥ 45 MPH
701901-11	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER
725001-01	OBJECT AND TERMINAL MARKERS
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
782006-01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS

## GENERAL NOTES

- EXCEPT AS NOTED ON THE PLANS, PAVEMENT GRADES SHOWN ARE AT THE TOP OF PAVEMENT SURFACES.
- THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.
- THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES (100 MILLIMETERS) IN AREAS TO BE SEEDED OR SODDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF FURNISHED EXCAVATION.
- ADDITIONAL CONSTRUCTION PROJECTS MAY BE UNDER CONTRACT WITHIN OR NEAR THE LIMITS OF THIS PROJECT WHEN IT IS IN FORCE. THE CONTRACTOR FOR THIS PROJECT SHALL COOPERATE WITH THE CONTRACTORS ON THE OTHER PROJECTS ACCORDING TO ARTICLE 105.08 OF THE STANDARD SPECIFICATIONS. CONTRACTS ANTICIPATED TO BE IN THE VICINITY OF THIS CONTRACT ARE:  
IDOT CONTRACT 66C06 (IL 47 IN MORRIS TO 0.1 MI E OF NIGAS ROAD IN CHANAHON).
- ALL ELEVATIONS REFERRING TO U.S.G.S. MEAN SEA LEVEL DATUM.
- THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
HMA RESURFACING	112	LBS / SQ YD / IN
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION
- MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:  
AT&T  
COMED  
COMCAST  
NICOR

## COMMITMENT

- THE CONTRACTOR SHALL CONTACT MR. EVAN KILBURN AT EKILBURN@USGS.GOV OR (217) 480-7061 A MINIMUM OF ONE (1) MONTH PRIOR TO THE START OF CONSTRUCTION TO COORDINATE THE RELOCATION OF THE USGS WATER GAUGE.

### HMA MIXTURE REQUIREMENT TABLE

LOCATIONS:	US 6 HMA RESURFACING		US 6 HMA SHOULDERS		US 6 FULL LANE SEALANT WATER PROOFING SYSTEM	US 6 TEMPORARY PAVEMENT	
	HMA SURFACE COURSE	HMA BINDER LFT(S)	HMA SURFACE COURSE	HMA BINDER LFT(S)	HMA SURFACE COURSE	HMA SURFACE COURSE	HMA BINDER LIFT(S)
MIXTURE USE(S):	SBS PG 70-28	PG 64-22	PG 64-22	PG 64-22	SBS PG 70-28	PG 64-22	PG 64-22
BINDER GRADE (PG):	4.0% @ N70	4.0% @ N70	4.0% @ N70	4.0% @ N70	4.0% @ N70	4.0% @ N70	4.0% @ N70
DESIGN AIR VOIDS:	IL-9.5 FG	IL-19.0	IL-9.5 FG	IL-19.0	IL-9.5 FG	IL-9.5	IL-19.0
MIXTURE COMPOSITION: (MIXTURE GRADATION)	MIXTURE D	N/A	MIXTURE D	N/A	MIXTURE D	MIXTURE D	N/A
FRICTION ACCRETE:	112.0 LB/SY/IN	112.0 LB/SY/IN	112.0 LB/SY/IN	112.0 LB/SY/IN	112.0 LB/SY/IN	112.0 LB/SY/IN	112.0 LB/SY/IN
MIXTURE WEIGHT:	QC/QA	QC/QA	QC/QA	QC/QA	QC/QA	QC/QA	QC/QA
QUALITY MANAGEMENT PROGRAM:	N/A	N/A	N/A	N/A	N/A	N/A	N/A
SUBLOT SIZE:	CORES/NUCLEAR	CORES/NUCLEAR	CORES/NUCLEAR	CORES/NUCLEAR	CORES/NUCLEAR	SATISFACTION OF ENGINEER	SATISFACTION OF ENGINEER
DENSITY TEST METHOD:	NO	NO	NO	NO	NO	NO	NO
MATERIAL TRANSFER DEVICE (REQUIRED):							

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE  
AS BUILT INFORMATION

\_\_\_\_\_  
SUPERVISING CONSTRUCTION FIELD ENGINEER

\_\_\_\_\_  
RESIDENT ENGINEER / TECHNICIAN

START & END DATES  
OF CONSTRUCTION:

INSPECTORS:

MODEL: C:\projects\01 (Sheet)  
FILE NAME: C:\2022\23\DOT\CAD\CONNECT\25051\_01\_IDOT\_D3\_PTB\_2144032\_WO\_01\_US\_6\_Over\_Aux\_Sable\_Creek\CADD>Data\CADsheets\0366N58-shi-dgmnote.dgn



USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/30/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
STANDARDS, GENERAL NOTES, COMMITMENTS, & HMA TABLE

SCALE: N/A SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	2
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: SQ001 (Sheet)  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25051.01.IDOT.D3.PTB.214-032.WO.01.US.6.Over.Aux.Sable.Creek\CADD>Data\CADsheets\366N58-sh-SQ0.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013 S.N. 032-0025
20101000	TEMPORARY FENCE	FOOT	695	695
20200100	EARTH EXCAVATION	CU YD	180	180
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10	10
20400800	FURNISHED EXCAVATION	CU YD	30	30
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23
25100630	EROSION CONTROL BLANKET	SQ YD	907	907
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	57	57
28000400	PERIMETER EROSION BARRIER	FOOT	1653	1653
28000500	INLET AND PIPE PROTECTION	EACH	1	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	463	463
28200200	FILTER FABRIC	SQ YD	463	463

\* DENOTES SPECIALTY ITEM



USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 7 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	3
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: S0002 (Sheet)  
 FILE NAME: C:\2022\RD\DOTCAD\CONNECT\25041.01 IDOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\0366N58-ah-SQO.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013 S.N. 032-0025
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	27	27
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	4012	4012
40600370	LONGITUDINAL JOINT SEALANT	FOOT	951	951
40600990	TEMPORARY RAMP	SQ YD	84	84
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	403	403
40604112	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70	TON	334	334
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	161	161
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	2688	2688
44004250	PAVED SHOULDER REMOVAL	SQ YD	36	36
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	113	113
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	56	56
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	492	492
50102400	CONCRETE REMOVAL	CU YD	123.3	123.3
50104650	SLOPE WALL REMOVAL	SQ YD	444	444

\* DENOTES SPECIALTY ITEM



USER NAME = skierpiec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 2 OF 7 SHEETS STA. TO STA.

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66N58	

MODEL: S0003 (Sheet)  
 FILE NAME: C:\2022\DOTCAD\CONNECT\25061\_01\_IDOT\_D3\_PTB\_214-032\_WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\0366N58-ah-S00.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013 S.N. 032-0025
50300100	FLOOR DRAINS	EACH	18	18
50300255	CONCRETE SUPERSTRUCTURE	CU YD	138.9	138.9
50300300	PROTECTIVE COAT	SQ YD	185	185
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	320	320
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39210	39210
50800515	BAR SPLICERS	EACH	26	26
50800530	MECHANICAL SPLICERS	EACH	1018	1018
51500100	NAME PLATES	EACH	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	92	92
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12
52100520	ANCHOR BOLTS, 1"	EACH	24	24
53016000	DECK SLAB REPAIR (PARTIAL)	SQ YD	7	7
53016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	50	50
53212754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	36	36

\* DENOTES SPECIALTY ITEM



USER NAME = skierpiec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/16/2026	DATE = 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 3 OF 7 SHEETS STA. TO STA.

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66N58	

MODEL: S0004 (Sheet)  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25051.01.IDOT.D3.PTB.214-032.WO.01.US.6.Over.Aux.Sable.Creek\CADD>Data\CADsheets\366N58-sh-SQO.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013 S.N. 032-0025
58100210	FULL LANE SEALANT WATERPROOFING SYSTEM	SQ YD	738	738
59000200	EPOXY CRACK INJECTION	FOOT	80	80
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	250	250
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	610	610
63500105	DELINEATORS	EACH	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5

\* DENOTES SPECIALTY ITEM



USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 4 OF 7 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	6
			CONTRACT NO. 66N58	
		ILLINOIS	FED. AID PROJECT	

MODEL: S0005 (Sheet)  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25051.01.IDOT.D3.PTB.214-032.WO.01.US.6.Over.Aux.Sable.Creek\CADD>Data\CADsheets\366N58-sh-S00.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013
				S.N. 032-0025
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70300100	SHORT TERM PAVEMENT MARKING	FOOT	816	816
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2264	2264
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	5686	5686
70307210	TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE	FOOT	48	48
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450.0	450.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5	387.5
70600251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
70600352	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	3804	3804
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	480	480
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12

\* DENOTES SPECIALTY ITEM



USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 5 OF 7 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	7
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: S0006 (Sheet)  
 FILE NAME: C:\2025\DOTCAD\CONNECT\2501\_01\_IDOT\_D3\_PTB\_214-032\_WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-ah-S00.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0013 S.N. 032-0025
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	16	16
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	12	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	754	754
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	8	8
Z0003615	REMOVAL OF EXISTING CONCRETE I-BEAM	EACH	6	6
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0015500	DEBRIS REMOVAL	L SUM	1	1
Z0043800	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIR	SQ FT	73	73
Z0053700	RESETTING SURVEY MONUMENTS	EACH	1	1
Z0062456	TEMPORARY PAVEMENT	SQ YD	141	141
X0325748	ACRYLIC COATING	SQ YD	26	26
X0325749	FIBER WRAP	SQ FT	232	232
X4062952	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	306	306

\* DENOTES SPECIALTY ITEM



USER NAME = skierpiec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE = 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION


US 6 OVER AUX SABLE CREEK  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET 6 OF 7 SHEETS STA. TO STA.

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	8
			CONTRACT NO. 66N58	
ILLINOIS FED. AID PROJECT				




MODEL: TYPICAL (Sheet) FILE NAME: C:\2022\23\DOT\CAD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_214-032\_WO 01\_US 6 over Aux Sable Creek\CADD Data\CADsheets\366N56-sh1-Typicals.dgn



**EXISTING ROADWAY TYPICAL SECTION**


STA. 246+50.00 TO STA. 249+93.83  
 STA. 249+93.83 TO STA. 251+54.67 (BRIDGE OMISSION)  
 STA. 251+54.67 TO STA. 256+00.00




**PROPOSED ROADWAY TYPICAL SECTION**

STA. 246+50.00 TO STA. 249+93.83  
 STA. 249+93.83 TO STA. 251+54.67 (BRIDGE OMISSION)  
 STA. 251+54.67 TO STA. 256+00.00


\*HOT-MIX ASPHALT BINDER COURSE THICKNESS VARIES:  
 -SEE TRANSITION DETAIL  
 -FROM STA. 248+82.71 TO STA. 249+72.71  
 -FROM STA. 251+75.79 TO STA. 252+65.79




STA. 246+50.00 TO STA. 247+12.43 (RT)  
 STA. 246+50.00 TO STA. 247+87.37 (LT)  
 STA. 254+08.39 TO STA. 256+00.00 (RT)  
 STA. 253+96.77 TO STA. 256+00.00 (LT)



STA. 246+50.00 TO STA. 247+12.43 (RT)  
 STA. 246+50.00 TO STA. 247+87.37 (LT)  
 STA. 254+08.39 TO STA. 256+00.00 (RT)  
 STA. 253+96.77 TO STA. 256+00.00 (LT)



STA. 247+12.43 TO STA. 247+40.81 (RT)  
 STA. 247+87.37 TO STA. 248+14.71 (LT)



STA. 253+23.19 TO STA. 254+08.39 (RT)  
 STA. 252+95.19 TO STA. 253+96.77 (LT)

**EXISTING**

- (A) HMA OVERLAY, ± 5"
- (B) PCC PAVEMENT, 9"
- (C) PCC BASE COURSE WIDENING, 9"
- (D) HMA SHOULDER, 8"
- (E) AGG. SHOULDER, 8"
- (F) GUARDRAIL

HMA SURFACE REMOVAL, 3.75"

**PROPOSED**

- (1) POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70, 1.5"
- (2) POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2.25"
- (3) HOT-MIX ASPHALT SHOULDERS, 8"
- (4) STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS
- (5) AGGREGATE WEDGE SHOULDER, TYPE B

- (6) AGGREGATE SHOULDERS, TYPE B, 6"
- (7) LONGITUDINAL JOINT SEALANT (SEE NOTE 1)
- (8) HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARDRAIL

**NOTES**

1. THE LONGITUDINAL JOINT SEALANT SHALL BE PLACED UNDER THE SURFACE LIFT.

USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - JDH	REVISED -
PLOT DATE = 1/19/2026	DATE = 1/23/2026	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	10
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: Sched01 (Sheet)  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25051.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-sh-Schedule.dgn

EARTHWORK SCHEDULE									
1				2	3	4	5	6	
LOCATION				EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTH BALANCE WASTE (+) OR SHORTAGE (-)	
				CU YD	CU YD	CU YD	CU YD	CU YD	
US 6	246+50.00	TO	247+00.00	RT	1.5	0.1	1.0	0.0	1.0
US 6	247+00.00	TO	247+50.00	RT	3.9	0.2	2.7	5.3	-2.6
US 6	247+50.00	TO	248+00.00	RT	8.0	0.5	5.6	15.0	-9.4
US 6	248+00.00	TO	248+50.00	RT	12.0	0.7	8.4	23.3	-14.9
US 6	248+50.00	TO	249+00.00	RT	14.4	0.8	10.1	16.5	-6.4
US 6	249+00.00	TO	249+50.00	RT	13.2	0.7	9.3	13.4	-4.1
US 6	249+50.00	TO	249+80.00	RT	6.9	0.4	4.8	40.3	-35.5
<b>SN 032-0025</b>	<b>249+80.00</b>	<b>TO</b>	<b>251+68.00</b>	<b>RT</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>
US 6	251+68.00	TO	252+00.00	RT	8.2	0.5	5.8	30.8	-25.0
US 6	252+00.00	TO	252+50.00	RT	16.8	0.9	11.9	4.7	7.2
US 6	252+50.00	TO	253+00.00	RT	37.8	1.9	26.9	0.9	26.0
US 6	253+00.00	TO	253+50.00	RT	35.5	1.8	25.2	0.0	25.2
US 6	253+50.00	TO	254+00.00	RT	10.1	0.6	7.0	0.0	7.0
US 6	254+00.00	TO	254+50.00	RT	4.1	0.3	2.8	0.0	2.8
US 6	254+50.00	TO	255+00.00	RT	1.7	0.1	1.2	0.0	1.2
US 6	255+00.00	TO	255+50.00	RT	1.6	0.1	1.1	0.0	1.1
US 6	255+50.00	TO	256+00.00	RT	1.6	0.1	1.1	0.0	1.1
TOTAL					180	10	125	155	-30

COLUMN 1: LOCATION FROM PLANS.  
 COLUMN 2: CUT QUANTITIES. DOES NOT INCLUDE UNSUITABLE MATERIAL.  
 COLUMN 3: CUT MATERIAL THAT IS DETERMINED TO BE EITHER UNSTABLE OR UNSUITABLE FOR USE IN EMBANKMENT. NOMINAL QUANTITY OF 5% OF EARTH EXCAVATION (COLUMN 2) PROVIDED.  
 COLUMN 4: QUANTITIES OF EARTH EXCAVATION ADJUSTED FOR A SHRINKAGE FACTOR OF 25%.  
 COLUMN 5: QUANTITIES OF EMBANKMENT (FILL).  
 COLUMN 6: EARTHWORK BALANCE (COLUMN 4 - COLUMN 5).  
 (+) = QUANTITY OF EXTRA EXCAVATION TO BE WASTED.  
 (-) = QUANTITY OF FURNISHED EXCAVATION NEEDED.



USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/22/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	11
			CONTRACT NO. 66N58	
		ILLINOIS FED. AID PROJECT		

GUARDRAIL REMOVAL SCHEDULE				
FROM STATION	OFFSET	TO STATION	OFFSET	GUARDRAIL REMOVAL FOOT
247+59.63	RT	249+87.14	RT	227.6
248+34.05	LT	249+86.55	LT	152.6
251+61.57	LT	252+76.56	LT	115.0
251+61.67	RT	252+76.15	RT	114.6
TOTAL				610

ROADWAY REMOVAL SCHEDULE					
FROM STATION	TO STATION	OFFSET	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	PAVED SHOULDER REMOVAL
			SQ YD	SQ YD	SQ YD
246+50.00	249+93.96	CL	78.1	1157.2	
251+54.37	256+00.00	CL	82.6	1530.1	
252+71.66	253+48.92	RT			35.2
TOTAL			161	2688	36

PROPOSED PAVEMENT SCHEDULE											
FROM STATION	TO STATION	LT/RT	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (TACK COAT)	LONGITUDINAL JOINT SEALANT	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70	AGGREGATE SHOULDERS, TYPE B 6"	AGGREGATE WEDGE SHOULDER, TYPE B	HOT-MIX ASPHALT SHOULDERS, 8"	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL
			TON	POUND	FOOT	TON	TON	SQ YD	TON	SQ YD	SQ YD
246+50.00	249+93.83	RT		236.8				21.0	4.8	143.6	106.4
246+50.00	249+93.83	LT		173.7				22.6	13.1	110.3	73.5
246+50.00	256+00.00	LT/RT		3255.4	950.5	402.3	240.0				
251+54.67	256+00.00	RT	26.9	188.9				30.3	17.4	130.0	68.8
251+54.67	256+00.00	LT		156.8				38.4	20.2	107.8	56.4
TOTAL			27	4012	951	403	241	113	56	492	306

NOTES:

- SEE STRUCTURAL PLANS FOR ADDITIONAL POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE QUANTITY.

PROPOSED GUARDRAIL SCHEDULE											
FROM STATION	TO STATION	OFFSET	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	DELINEATORS	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL REFLECTORS, TYPE A	BARRIER WALL REFLECTORS, TYPE C	LINEAR DELINEATOR PANELS, 4 INCH	LINEAR DELINEATOR PANELS, 6 INCH
			FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
247+58.80	249+80.08	RT	137.5	1	1	1	1	4		2	
248+33.80	249+80.08	LT	62.5	1	1	1	1	4		2	
249+00.00	251+60.42	LT							6		3
249+80.08	251+68.42	RT							6		3
251+68.42	252+77.20	LT	25.0	1	1	1	1	4		2	
251+68.42	252+77.20	RT	25.0	1	1	1	1	4		2	
TOTAL			250.0	4	4	4	4	16	12	8	6

EROSION CONTROL SCHEDULE						
FROM STATION	TO STATION	OFFSET	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
			SQ YD	POUND	FOOT	EACH
246+50.00	249+80.42	RT	317.7	19.7	355.1	
246+50.00	249+81.34	LT	292.5	18.1	395.3	
251+57.25	256+00.00	LT	171.3	10.6	469.1	
251+57.73	252+85.00	RT	99.2	6.2	151.8	
253+20.00	256+00.00	RT	26.5	1.6	280.8	1
TOTAL			907	57	1653	1

LANDSCAPING SCHEDULE							
FROM STATION	TO STATION	OFFSET	AREA	SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
			SQ FT	ACRE	POUND	POUND	POUND
246+50.00	249+80.42	RT	2858.9	0.07	5.9	5.9	5.9
246+50.00	249+81.34	LT	2632.3	0.06	5.4	5.4	5.4
251+57.25	256+00.00	LT	1542.1	0.04	3.2	3.2	3.2
251+57.73	252+85.00	RT	893.2	0.02	1.8	1.8	1.8
253+20.00	256+00.00	RT	238.6	0.01	0.5	0.5	0.5
TOTAL				0.19	16.9	16.9	16.9
ROUNDED TOTAL				0.25	23	23	23

MODEL: Schem02 (Sheet)  
FILE NAME: O:\2022R3\DOTCAD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_2144032\_WO 01\_US 6 over Aux\_Sable\_Creek\CADD Data\CADsheets\366N58-sh-Schedule.dgn



USER NAME = zbackes	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	12
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MAINTENANCE OF TRAFFIC SCHEDULE											
STAGE	LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	TEMPORARY RUMBLE STRIPS	TEMPORARY BRIDGE TRAFFIC SIGNALS
						FOOT	FOOT	EACH	EACH	EACH	EACH
STAGE 1	US 6	248+49.09	3.27' RT	249+36.29	4.00' LT	87.5		1			
	US 6	249+36.29	4.00' LT	251+86.29	4.00' LT	250.0					
	US 6	251+86.29	4.00' LT	252+36.29	0.17' RT	50.0		1			
	US 6					STAGE 1 SUBTOTAL	387.5	0	2	0	6
STAGE 2	US 6	248+49.09	3.27' LT	249+36.29	4.00' RT		87.5		1		
	US 6	249+36.29	4.00' RT	252+11.29	4.00' RT		275.0				
	US 6	252+11.29	4.00' RT	252+98.49	3.27' LT	62.5	25.0		1		
	US 6					STAGE 2 SUBTOTAL	62.5	387.5	0	2	0
TOTAL						450.0	387.5	2	2	6	1

MAINTENANCE OF TRAFFIC PAVEMENT MARKING SCHEDULE								
STAGE	FROM STATION	TO STATION	OFFSET	SHORT TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE	SHORT TERM PAVEMENT MARKING REMOVAL SQ FT
				WHITE (ABBREVIATED)	YELLOW (ABBREVIATED)	SOLID WHITE	SOLID WHITE	
				FOOT	FOOT	FOOT	FOOT	
STAGE 1	246+55.21		RT				24.0	48.0
STAGE 1	246+71.21	254+95.77	RT			1653.6		551.2
STAGE 1	248+14.71	253+96.27	LT			1164.9		388.3
STAGE 1	255+61.77		LT				24.0	48.0
STAGE 2	247+15.21	255+51.77	LT			1677.6		559.2
STAGE 2	248+14.71	254+08.27	RT			1189.4		396.5
STAGE 3	246+50.00	256+00.00	CTR	240.0	576.0			272.0
TOTAL					816	5686	48	2264

PAVEMENT MARKING SCHEDULE							
START STATION	END STATION	OFFSET	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL - WATER BLASTING
			SOLID WHITE	YELLOW 10' DASH - 30' SKIP			
			FOOT	FOOT	EACH	EACH	SQ FT
246+50.00	256+00.00	LT	1902				317.0
246+50.00	256+00.00	CTR		480	12	12	120.0
246+50.00	256+00.00	RT	1902				317.0
TOTAL			3804	480	12	12	754

NOTES:  
1. PAVEMENT MARKINGS SHALL BE APPLIED IN TWO APPLICATIONS.

MODEL: Schedule3 (Sheet)  
FILE NAME: C:\2022R3\DOTCAD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_2144032\_WO 01\_US 6 OVER AUX SABLE CREEK\CADD Data\CADsheets\366N58-sh-Schedule.dgn



USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 3 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	13
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: ATB1  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_214-032\_WO 01\_US 6 over Aux\_Sable\_Creek\CADD Data\CADsheets\366N58-sh1-ATB.dgn



### PERMANENT SURVEY MARKER SCHEDULE

MONUMENT NUMBER	DESCRIPTION	APPROXIMATE LOCATION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
006399	NW CORNER SECTION 20, T34N, R8E, 3RD PM POSSIBLE LOCATON	WEST END OF BRIDGE	MAG NAIL	TYPE 1	YES	1
A006399	NW CORNER SECTION 20, T34N, R8E, 3RD PM POSSIBLE LOCATION	WEST END OF BRIDGE	NONE, PER TIES	SEE NOTE		
NOTE: TWO LOCATIONS ARE BEING USED AS THE SECTION CORNER. THE BURIED CAST IRON MONUMENT WILL BE LOCATED BY PLATS AND PLANS AT THE TIME OF 66N58 CONSTRUCTION, OR PRIOR TO THAT DURING THE DAY LABOR RESURFACING OF ROUTE 6 AT THAT LOCATION. ONE MONUMENT WILL BE SET.						

ONLY THE ORIGINAL SCOPE OF THIS JOB HAS BEEN SEARCHED FOR MONUMENTS. R.E. MUST INFORM PLATS AND PLANS TO SEARCH FOR ADDITIONAL MONUMENTS PRIOR TO MILLING IF ADDENDUMS HAVE BEEN ADDED TO THIS JOB.

**R.E. WILL INFORM PLATS AND PLANS WHEN THE WEST BOUND LANE IS TO BE CLOSED.**

UNKNOWN MONUMENTS MAY EXIST. IF AN UNLISTED MONUMENT IS FOUND, R.E. IS REQUIRED TO PROTECT THE MONUMENT FROM DAMAGE UNTIL A PLATS AND PLANS LAND SURVEYOR CAN DOCUMENT THE MONUMENT. PLATS AND PLANS WILL RESET SUCH MONUMENTS IN KIND FOLLOWING CONSTRUCTION.

NOTE: FOR BIDDING PURPOSES NO CONTRACTED LAND SURVEYING SERVICES WILL BE REQUIRED.						
PLATS AND PLANS WILL PREPARE AND RECORD ANY REQUIRED MONUMENT RECORDS.						
TRAFFIC CONTROL SHALL BE PROVIDED BY THE CONTRACTOR FOR THE ENGINEER TO INSTALL ALL MONUMENT TYPES.						
<b>RESPONSIBILITY:</b>						
1) RESIDENT TO COORDINATE WITH PLATS AND PLANS STAFF TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED ACCORDING TO THE SPECIAL PROVISION "FURNISH PERMANENT SURVEY MARKER")						
2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT						




USER NAME = pgillespie	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/21/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 ALIGNMENT, TIES, AND BENCHMARKS


SCALE: 1"=100' SHEET 1 OF 2 SHEETS STA. 213+09.62 TO STA. 275+00.00

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 14
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				




PI STA 246+00.00 (US 6)

MAG NAIL  
N: 1730161.7580  
E: 979794.7397




PI STA 250+74.25 (US 6)

CUT "X" IN DECK  
N: 1730168.9618  
E: 980268.9350



PI STA 253+87.63 BK =  
STA 253+87.11 AH (US 6)

MAG NAIL  
N: 1730173.7219  
E: 980582.2745



CONTROL POINT #11  
STA 252+79.68, 23.44' LT (US 6)

80D SPIKE IN ABANDONED FIELD ENTRANCE  
N: 1730195.5240  
E: 980473.9870  
EL: 532.401

ALIGNMENT COORDINATES - C US 6			
POINT	STA	NORTHING	EASTING
POT	213+09.62	1730111.7779	976504.7393
PI	246+00.00	1730161.7580	979794.7397
PI	250+74.25	1730168.9618	980268.9350
PI	253+87.63 BK = 253+87.11 AH	1730173.7219	980582.2745
POT	275+00.00	1730222.9853	982694.5865

MODEL: ATB2  
FILE NAME: C:\2022R3\DOTCAD\CONNECT\250651.01\DOT D3 PTB 2144032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADD sheets\366N58-sh1-ATB.dgn

**EFK Moen**  
Civil Engineering Design

USER NAME = sklerplec  
PLOT DATE = 1/19/2026



DESIGNED - JDB  
DRAWN - PJG  
CHECKED - RBB  
DATE - 1/23/2026

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
ALIGNMENT, TIES, AND BENCHMARKS**  
SCALE: N/A SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	15
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				



MODEL: Rem1  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\250651.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-shr-Removals.dgn

**EFK Moen**  
Civil Engineering Design



USER NAME = pgillespie	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/22/2026	DATE - 1/23/2026	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
REMOVAL PLAN**


SCALE: 1"=50'    SHEET 1 OF 1 SHEETS    STA. 243+00.00 TO STA. A 257+99.48

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 16
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				



**LEGEND**

- ① HMA SHOULDERS, 8"
  - ② AGGREGATE WEDGE SHOULDER, TYPE B, 3.75" & VARIES
  - ③ STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS
  - ④ TRAFFIC BARRIER TERMINAL, TYPE 6
  - ⑤ TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT
  - ⑥ AGGREGATE SHOULDERS, TYPE B 6"
  - ⑦ HMA STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL
- POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70, 1.5"
  - POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2.25"
  - POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70, 1.5"
  - POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, VARIES 2.25" TO 4.5" (SEE TRANSITION DETAIL)
  - POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, MIX "D", N70, 1.5"
  - FULL LANE SEALANT WATERPROOFING SYSTEM, 0.75"
  - AGGREGATE SURFACE COURSE, TYPE B, 8"
  - LIMITS OF CONSTRUCTION



MODEL: P:\P\01 FILE NAME: C:\2022R3\DOTCADD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_214-032\_WO 01\_US 6 over Aux\_Sable\_Creek\CADD Data\CADsheets\366N58-sh-P\PrP.dgn

**EFK Moen**  
Civil Engineering Design

USER NAME = zbackes	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/20/2026	DATE - 1/23/2026	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK**  
**PLAN AND PROFILE**

SCALE: 1"=50' SHEET 1 OF 1 SHEETS STA. 243+00.00 TO STA. A 257+99.48

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 17
CONTRACT NO. 66N58			ILLINOIS FED. AID PROJECT	

**STAGING GENERAL NOTES**

1. THE STAGING PLANS SHALL SERVE AS A GUIDE FOR THE SAFE DIVERSION OF TRAFFIC DURING EXECUTION OF THE CONTRACT. THE CONTRACTOR MAY MODIFY THE STAGING PLANS TO MEET CONSTRUCTION NEEDS, BUT NOT AT THE EXPENSE OF PUBLIC SAFETY OR CONVENIENCE. ANY CHANGES TO THE TRAFFIC CONTROL SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL.
2. ALL THE EXISTING AND TEMPORARY PAVEMENT MARKINGS FROM PRIOR STAGES THAT ARE IN CONFLICT SHALL BE REMOVED.
3. ANY RAISED REFLECTIVE PAVEMENT MARKERS THAT CONFLICT WITH THE TEMPORARY TRAFFIC LANES MUST HAVE THE REFLECTIVE LENSES REMOVED AS DIRECTED BY THE ENGINEER.
4. SIGNS DESIGNATED AS (O) SHALL HAVE FLUORESCENT ORANGE SHEETING MATERIAL WITH BLACK LETTERING.
5. THE CONTRACTOR SHALL REMOVE OR COVER ALL EXISTING SIGNS THAT CONFLICT WITH OR DO NOT APPLY TO THE REVISED TRAFFIC PATTERNS AND SHALL RESTORE THE SIGNS AT THE END OF CONSTRUCTION AS DIRECTED BY THE ENGINEER. DO NOT PLACE TAPE OR DRILL INTO THE FACE OF THE SIGN WHEN COVERING.
6. CONTRACTOR SHALL NOTIFY THE OPERATION SIGNAL SECTION PRIOR TO ACTIVATING THE TEMPORARY SIGNAL AND SHALL OBTAIN THE TEMPORARY BRIDGE SIGNAL ACTIVATION FORM.

**STAGING SEQUENCE OF CONSTRUCTION**

PRE-STAGE

TRAFFIC:

1. UTILIZE STANDARD 701326 TO CLOSE WB LANE.

CONSTRUCTION:

1. REMOVE 3' OF EXISTING WB AGGREGATE SHOULDER.
2. CONSTRUCT TEMPORARY PAVEMENT.

STAGE 1

TRAFFIC:

1. UTILIZE STANDARD 701321 AND THE STAGING PLANS TO INSTALL TEMPORARY SIGNALS ALONG US 6 AND AT THE PRIVATE RD AT STA 253+02, TEMPORARY CONCRETE BARRIERS AND OTHER TRAFFIC CONTROL DEVICES.
2. MAINTAIN ONE 12' LANE WITH 1' SHOULDERS ON EACH SIDE ON EX WB PAVEMENT, HMA SHOULDER, AND TEMPORARY PAVEMENT.
3. UTILIZE FLAGGERS AS NEEDED TO CONTROL TRAFFIC AT THE PRIVATE RD AT STA 253+02.

CONSTRUCTION:

1. PERFORM BRIDGE IMPROVEMENTS AS ALLOWED BY THE WORK ZONE. SEE STRUCTURAL PLANS.
2. REMOVE EXISTING GUARDRAIL ALONG EB PAVEMENT.
3. MILL APPROACH SLABS ALONG EB PAVEMENT.
4. PLACE PROPOSED OVERLAY FROM STA 249+72.71 TO STA 251+75.79 ALONG EB PAVEMENT AND CONSTRUCT TEMPORARY RAMPS.
5. CONSTRUCT PROPOSED GUARDRAIL AND GRADING ALONG EB PAVEMENT.
6. CONSTRUCT PROPOSED SHOULDER ALONG EB PAVEMENT FROM STA 247+12.43 TO STA 254+08.39.

STAGE 2

TRAFFIC:

1. UTILIZE STANDARD 701321 AND THE STAGING PLANS TO RELOCATE AND INSTALL TEMPORARY CONCRETE BARRIERS AND OTHER TRAFFIC CONTROL DEVICES.
2. MAINTAIN ONE 12' LANE WITH 1' SHOULDERS ON EACH SIDE ON EB PAVEMENT AND PR SHOULDERS.

CONSTRUCTION:

1. PERFORM BRIDGE IMPROVEMENTS AS ALLOWED BY THE WORK ZONE. SEE STRUCTURAL PLANS.
2. REMOVE EXISTING GUARDRAIL ALONG WB PAVEMENT.
3. REMOVE TEMPORARY PAVEMENT.
4. MILL APPROACH SLABS ALONG WB PAVEMENT.
5. PLACE PROPOSED OVERLAY FROM STA 249+72.71 TO STA 251+75.79 ALONG WB PAVEMENT AND CONSTRUCT TEMPORARY RAMPS.
6. CONSTRUCT PROPOSED GUARDRAIL AND GRADING ALONG WB PAVEMENT.
7. CONSTRUCT PROPOSED SHOULDER ALONG WB PAVEMENT FROM STA 247+87.37 TO STA 253+96.77.

STAGE 3

TRAFFIC:

1. UTILIZE STANDARD 701306 AND 701311 TO ALTERNATE CLOSURES OF THE WB AND EB LANES.

CONSTRUCTION:

1. MILL AND RESURFACE EX PAVEMENT FROM STA 246+50.00 TO STA 249+72.71 AND FROM STA 251+75.79 TO STA 256+00.00.
2. CONSTRUCT AGGREGATE WEDGE SHOULDERS AND GRADING.
3. PLACE FINAL PAVEMENT MARKINGS.

MODEL: Gennote01 (Sheet)  
FILE NAME: O:\2022R3\DOTCAD CONNECT\250651.01 IDOT D3 PTB 2144032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-sh-Staging-Gennote.dgn



USER NAME = zbackes	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
MAINTENANCE OF TRAFFIC - GENERAL NOTES**


SCALE: N/A      SHEET 1 OF 5 SHEETS      STA.      TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	18
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: TYP025 (Sheet)  
 FILE NAME: C:\2022\23\DOT\CAD\CONNECT\250651.01.IDOT.D3.PTB.214-032.WO.01.US.6.over.Aux.Sable.Creek\CADD>Data\CADsheets\366N56-sh-Staging-Typicals.dgn







**US 6 TYPICAL SECTION STAGE 1**  
 STA. 249+62.21 TO STA. 251+86.29



**US 6 TYPICAL SECTION STAGE 2**  
 STA. 249+62.21 TO STA. 251+86.29

**LEGEND**

-  WORK ZONE
-  TEMPORARY PAVEMENT (SEE NOTE 1)
-  WORK COMPLETED IN PREVIOUS STAGES
-  TEMPORARY PAVEMENT MARKING - TAPE TYPE IV - LINE 4" (SOLID WHITE)



**NOTES**

1. SEE HMA MIX CHART. TEMPORARY PAVEMENT CONSISTS OF:
  - HMA SURFACE COURSE, IL-9.5, MIX "D", N70, 2"
  - HMA BINDER COURSE, IL-19.0, N70, 6"
  - SUBBASE GRANULAR MATERIAL, TYPE B, 4"

**EFK Moen**  
 Civil Engineering Design

USER NAME =	pgillespie	DESIGNED -	JDB	REVISED -	
		DRAWN -	PJG	REVISED -	
		CHECKED -	RBB	REVISED -	
PLOT DATE =	1/21/2026	DATE -	1/23/2026	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**




**US 6 OVER AUX SABLE CREEK**  
**MAINTENANCE OF TRAFFIC - TYPICAL SECTIONS**

SCALE: NONE SHEET 2 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	19
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

**ADVANCED SIGNING DETAIL - US 6 (EB)**

PER HIGHWAY STANDARD 701321




**LEGEND**

- SIGN
- DIRECTION OF TRAFFIC
- TYPE II BARRICADES, DRUMS, OR VERTICAL PANELS SPACED AT 25' C-C WITHIN LANE TAPER LIMITS, 50' C-C WITHIN TANGENTS
- TYPE III BARRICADE WITH FLASHING LIGHTS
- TEMPORARY TRAFFIC SIGNAL WITH BACKPLATE
- MICROWAVE DETECTOR
- TEMPORARY RUMBLE STRIPS
- TEMPORARY CONCRETE BARRIER
- IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3
- WORK ZONE
- WORK COMPLETED IN PREVIOUS STAGE
- ① TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE (SOLID WHITE)
- ② TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE (SOLID WHITE)
- Ⓔ EXISTING PAVEMENT MARKING
- Ⓟ PAVEMENT MARKING PLACED IN PREVIOUS STAGE

**ADVANCED SIGNING DETAIL - US 6 (WB)**

PER HIGHWAY STANDARD 701321



MODEL: STG1  
FILE NAME: O:\2022\23\DOTCAD\CONNECT\25051.01\DOT D3 PTB 2144032.WO 01 US 6 over Aux Sable Creek\Creek\CADD Data\CADsheets\366N58-sh-Staging-1.dgn



USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/23/2026	DATE - 1/23/2026	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**




**US 6 OVER AUX SABLE CREEK  
MAINTENANCE OF TRAFFIC - STAGE 1**

SCALE: 1"=50'    SHEET 3 OF 5 SHEETS    STA. 243+00.00 TO STA. A 257+99.48

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 20
CONTRACT NO. 66N58				ILLINOIS FED. AID PROJECT

**ADVANCED SIGNING DETAIL - US 6 (EB)**

PER HIGHWAY STANDARD 701321




**LEGEND**

- SIGN
- DIRECTION OF TRAFFIC
- TYPE II BARRICADES, DRUMS, OR VERTICAL PANELS SPACED AT 25' C-C WITHIN LANE TAPER LIMITS, 50' C-C WITHIN TANGENTS
- TYPE III BARRICADE WITH FLASHING LIGHTS
- TEMPORARY TRAFFIC SIGNAL WITH BACKPLATE
- MICROWAVE DETECTOR
- TEMPORARY RUMBLE STRIPS
- TEMPORARY CONCRETE BARRIER
- IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3
- WORK ZONE
- WORK COMPLETED IN PREVIOUS STAGE
- ① TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE (SOLID WHITE)
- ② TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE (SOLID WHITE)
- ⓔ EXISTING PAVEMENT MARKING
- Ⓟ PAVEMENT MARKING PLACED IN PREVIOUS STAGE

**ADVANCED SIGNING DETAIL - US 6 (WB)**

PER HIGHWAY STANDARD 701321



MODEL: STG2  
FILE NAME: O:\2022R3\DOTCAD\CONNECT\25051.01\DOT D3 PTB 2144032.WO 01 US 6 over Aux Sable Creek\CADD Data\CAD\sheet\366N5B-sh-Staging-2.dgn



USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/19/2026	DATE - 1/23/2026	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
MAINTENANCE OF TRAFFIC - STAGE 2**


SCALE: 1"=50'    SHEET 4 OF 5 SHEETS    STA. 243+00.00 TO STA. A 257+99.48

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 21
CONTRACT NO. 66N58				ILLINOIS FED. AID PROJECT


ADVANCE WIDTH RESTRICTION SIGNING  
FOR EB US 6 AT IL 47




ADVANCE WIDTH RESTRICTION SIGNING  
FOR WB US 6 AT I-55



ADVANCE WIDTH RESTRICTION SIGNING  
FOR EB US 6 AT COUNTY RD 3000 E (BRISBIN RD)



ADVANCE WIDTH RESTRICTION SIGNING  
FOR WB US 6 AT RIDGE RD



NOTES

- SIGNS DESIGNATED AS (O) SHALL HAVE FLUORESCENT ORANGE SHEETING MATERIAL WITH BLACK LETTERING.

MODEL: C:\projects\01\_Sheet1  
FILE NAME: O:\2022\23\DOTCAD\CONNECT\250651.01\_IDOT\_D3\_PTB\_214-032\_WO 01\_US 6 over Aux\_Sable\_Creek\CADD Data\CADsheets\0366N58-sh-Staging-Detail.dgn

**EFK Moen**  
Civil Engineering Design



USER NAME =	pgillespie	DESIGNED -	JDB	REVISED -	
		DRAWN -	PJG	REVISED -	
		CHECKED -	RBB	REVISED -	
PLOT DATE =	1/15/2026	DATE -	1/23/2026	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
MAINTENANCE OF TRAFFIC - ADVANCE WIDTH RESTRICTION SIGNING

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	22
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

SCALE: N/A SHEET 5 OF 5 SHEETS STA. TO STA.



**EROSION CONTROL LEGEND**

- LIMITS OF CONSTRUCTION
- PERIMETER EROSION BARRIER
- WETLAND "NO INTRUSION" FENCE PAID FOR AS TEMPORARY FENCE
- WETLAND
- ▨ TEMPORARY EROSION CONTROL SEEDING EROSION CONTROL BLANKET
- ◆ INLET AND PIPE PROTECTION

MODEL: Eros1  
 FILE NAME: C:\2022\23\DOTCAD CONNECT\25061.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\0366N58-sh1-Eros.dgn





USER NAME = sklerplec	DESIGNED - JDB	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/20/2026	DATE - 1/23/2026	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**


**US 6 OVER AUX SABLE CREEK**  
**EROSION AND SEDIMENT CONTROL PLAN**

SCALE: 1"=50'    SHEET 1 OF 1 SHEETS    STA. 243+00.00 TO STA. A 257+99.48

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 23
CONTRACT NO. 66N58			ILLINOIS FED. AID PROJECT	



**LANDSCAPING LEGEND**

- LIMITS OF CONSTRUCTION
- TOPSOIL EXC & PLAC; 6" EXC & 4" PLAC
- SEEDING, CL 2A
-  EROSION CONTROL BLANKET
- NITROGEN FERT NUTR
- PHOSPHOROUS FERT NUTR
- POTASSIUM FERT NUTR

MODEL: L:\ndscp01 FILE NAME: C:\2022\23\DOTCAD\CONNECT\25051.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CAD sheets\366N58-sh1-Landscp.dgn

**EFK Moen**  
Civil Engineering Design

USER NAME =	pgillespie	DESIGNED -	JDB	REVISED -	
		DRAWN -	ZJW	REVISED -	
		CHECKED -	RBB	REVISED -	
PLOT DATE =	1/22/2026	DATE -	1/23/2026	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
LANDSCAPING PLAN**

SCALE: 1"=50'      SHEET 1      OF 1      SHEETS      STA. 243+00.00      TO STA. A 257+99.48

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	24
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				



**GENERAL NOTES**


1. Reinforcement bars designated (E) shall be epoxy coated.
2. Protective coat shall not be applied to surfaces to which Waterproofing Membrane System is applied for the joints and top and front face of parapets.
3. Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.
4. Plan dimensions and details relative to the existing structure have been taken from existing plans and are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
5. All structural steel shall conform to AASHTO Classification M-270 Gr. 36, unless otherwise noted.
6. The deck surface shall have its final finish tined according to Article 420.09(e)(1) of the Standard Specifications. Cost to be included with Concrete Superstructure.
7. Joint opening shall be adjusted according to Article 520.04 of the Standard Specifications when the the deck is poured at an ambient temperature other than 50° F.

**INDEX OF SHEETS**

1. General Plan and Elevation
2. General Data
3. Stage Construction Details
4. Temporary Concrete Barrier
5. Deck Repairs
6. Superstructure
7. Superstructure Details
8. Diaphragm Details
9. Expansion Joint Removal and Replacement
10. Preformed Joint Strip Seal
11. 42" PPC I-Beam
12. 42" PPC I-Beam Details
13. Bearing Details
14. Beam Repairs
15. Abutment Repairs
16. Pier 1 Repairs
17. Pier 2 Repairs
18. Wingwall Reconfiguration
19. Concrete Parapet Slipforming Option
20. Bar Splicer Assembly and Mechanical Splicer Details

**TOTAL BILL OF MATERIAL**

ITEM	UNIT	SUPER	SUB	TOTAL
Stone Riprap, Class A4	Sq. Yd.		463	463
Filter Fabric	Sq. Yd.		463	463
Polymerized Hot-Mix Asphalt Surface Course, IL-9.5FG, Mix "D", N70	Ton	93		93
Concrete Removal	Cu. Yd.	123.3		123.3
Slope Wall Removal	Sq. Yd.		444	444
Floor Drains	Each	18		18
Concrete Superstructure	Cu. Yd.	138.9		138.9
Protective Coat	Sq. Yd.	185		185
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 42 in.	Foot	320		320
Reinforcement Bars, Epoxy Coated	Pound	38,920	290	39,210
Bar Splicers	Each	26		26
Mechanical Splicers	Each	1,018		1,018
Name Plates	Each	1		1
Preformed Joint Strip Seal	Foot	92		92
Elastomeric Bearing Assembly, Type II	Each	12		12
Anchor Bolts, 1"	Each	24		24
Full Lane Sealant Waterproofing System	Sq. Yd.	738		738
Epoxy Crack Injection	Foot		80	80
Acrylic Coating	Sq. Yd.	26		26
Fiber Wrap	Sq. Ft.	232		232
Jack and Remove Existing Bearings	Each	8		8
Removal of Existing Concrete I-Beam	Each	6		6
Debris Removal	L Sum		1	1
Structural Repair of Concrete (Depth Equal to or Less Than 5 in.)	Sq. Ft.		36	36
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	50		50
Deck Slab Repair (Partial)	Sq. Yd.	7		7
Precast Prestressed Concrete I-Beam Repair	Sq. Ft.	73		73



**SECTION A-A**


\*Depth can be reduced to top of rock, if encountered.

STA. 250+74.25  
RE-BUILT 20 BY  
STATE OF ILLINOIS  
RTE. 392 SEC. (G-BR)BR-1  
LOADING HS20-44  
STR. NO. 032-0025

**NAME PLATE**

See Std. 515001


Existing Name Plate shall be cleaned and relocated next to new Name Plate. Cost included with Name Plates.




**SECTION THRU PILE SUPPORTED STUB ABUTMENT**

MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\250511.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-002-General Data.dgn  
3/6/2026 12:40:40 PM


	USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -	<p align="center"><b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b></p>	<p align="center"><b>GENERAL DATA STRUCTURE NUMBER 032-0025</b></p>	F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 26
	PLOT SCALE =	DRAWN - KRH	REVISED -			CONTRACT NO. 66N58		ILLINOIS FED. AID PROJECT		
	PLOT DATE = 3/6/2026	CHECKED - ACB	REVISED -	SHEET 2 OF 20 SHEETS						




**STAGE 1 REMOVAL**  
(Looking East at Abutment Joint)




**STAGE 1 CONSTRUCTION**  
(Looking East at Abutment Joint)



**STAGE 2 REMOVAL**  
(Looking East at Abutment Joint)




**STAGE 2 CONSTRUCTION**  
(Looking East at Abutment Joint)



Diaphragm Removal

**FASCIA BEAM REMOVAL**  
Interior diaphragm removal shown.  
Pier diaphragm removal similar.



**WATERPROOFING STAGING**

Full Lane Sealant Waterproofing System consists of an initial tack coat to promote bonding, Layer 1 of Full Lane Sealant, a Protection Layer and Layer 2 of Full Lane Sealant.

Notes:  
Hatched area indicates Concrete Removal for expansion joint replacement and fascia beam replacement. See Sheet 6 and 8 of 20 for additional dimensions.  
Cross hatched area indicates Removal of Existing I-Beam.  
For quantity of temporary concrete barrier, see roadway plans.  
For details of HMA Overlay with FLS, see Sheet 6 of 20.

MODEL: Default  
FILE NAME: 012022R3\DOTCAD CONNECT\250511.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-003-Stage\_Construction.dgn  
3/6/2026 12:40:42 PM

**EFK Moen**  
Civil Engineering Design

USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
	CHECKED - ACB	REVISED -
PLOT SCALE =	DRAWN - KRH	REVISED -
PLOT DATE = 3/6/2026	CHECKED - ACB	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**STAGE CONSTRUCTION DETAILS**  
**STRUCTURE NUMBER 032-0025**

SHEET 3 OF 20 SHEETS


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	27
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-004-Temporary Barrier.dgn





When "A" is 3'-1" or less, the temporary concrete barrier shall be restrained to the new slab according to Detail I, II or III. No restraint is required when "A" is greater than 3'-1".


**NEW SLAB OR NEW DECK BEAM**




**EXISTING SLAB**  
**EXISTING DECK BEAM**  
**SECTIONS THRU SLAB OR DECK BEAM**




**DETAIL I**




**DETAIL II**




**DETAIL III**



**BAR SPLICER FOR #4 BAR - DETAIL III**



**STEEL RETAINER 1" x 8" x "W"**  
(Detail I and II)



**STEEL RETAINER 1" x "H" x 10"**  
(Detail III)

**Notes:**  
Cost of retainer assembly is included with Temporary Concrete Barrier.  
A retainer assembly shall be located at the approximate center of each temporary concrete barrier.  
The retainer plate shall not be removed until the concrete on the adjacent stage is ready to be poured. For Detail III applications the retainer plate shall not be removed until just prior to placing the adjacent beam.  
When the 'A' dimension is less than 1 1/2", the wood block shall be omitted and the retainer shall be placed in direct contact with the steel retainer plate.  
For deck beam applications the minimum required 'A' distance is 6" to accommodate the shear key clamping device.

**Detail I - Installation for a new bridge deck or bridge slab.**

**Detail II - Installation for a new deck beam with an initial concrete wearing surface.** Additional bar splicers shall be provided at 6'-0" centers and paired with the bar splicers of the concrete wearing surface reinforcement to accommodate the installation of the retainer assemblies. The cost of the additional bar splicers is included with the concrete wearing surface.

**Detail III - Installation for a new deck beam with no initial wearing surface or with an initial hot-mix asphalt (HMA) wearing surface present.** The deck beam directly beneath the temporary concrete barrier shall be fabricated with bar splicer inserts in the side of the beam, as detailed, to accommodate the installation of the retainer assemblies. A pair of bar splicers, 6" apart, shall be placed at 6'-0" centers along the length of the beam. The cost of the bar splicers is included with the deck beam.

**RAILING CRITERIA**

NCHRP 350 Test Level	3
Railing Weight (plf)	440

R-27 5-15-2023

**EFK Moen**  
Civil Engineering Design

USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
PLOT SCALE =	CHECKED - ACB	REVISED -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISED -
	CHECKED - ACB	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**TEMPORARY CONCRETE BARRIER**  
**STRUCTURE NUMBER 032-0025**


SHEET 4 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	28
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-005-Deck Repairs.dgn



TOP OF DECK PLAN



Notes:  
 Areas of deck repairs shown are estimated. The Engineer shall show actual location and size of deck repairs on As-built Plans.

LEGEND

- Deck Slab Repair (Partial)
- Deck Slab Repair (Full Depth, Type I)

BILL OF MATERIAL

Item	Unit	Total
Deck Slab Repair (Partial)	Sq. Yd.	7
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	50



USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
PLOT SCALE =	CHECKED - ACB	REVISED -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISED -
	CHECKED - ACB	REVISED -


STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

DECK REPAIRS  
 STRUCTURE NUMBER 032-0025

SHEET 5 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	29
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				


MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-006-Superstructure.dgn  
 3/6/2026 12:40:46 PM



**MINIMUM BAR LAP**  
 #5 bar = 3'-10"

**DECK PLAN**


**Notes:**  
 See sheet 8 of 22 for superstructure details and Bill of Material.  
 Bars indicated thus 20 x 3-#5 etc. indicates 20 lines of bars with 3 lengths per line.  
 Existing reinforcement bars extending into the removal area shall be cleaned, straightened, and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system at the Contractor's expense.




**CROSS SECTION**  
 (Looking East)

USER NAME = \$USER\$	DESIGNED - KRH	REVISED -
PLOT SCALE =	CHECKED - ACB	REVISED -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISED -
	CHECKED - ACB	REVISED -

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 30
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66N58	




INSIDE ELEVATION OF PARAPET




SECTION THRU PARAPET


**MINIMUM BAR LAP**  
#4 bar = 2'-2"




PARAPET JOINT DETAILS



DEAD LOAD DEFLECTION DIAGRAM  
(Includes weight of concrete, excluding beams for fillet adjustment.)



BAR s(E) & s1(E)




BAR a2(E)

**Notes:**  
Fiberglass pipe shall conform to ASTM D2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.  
The exterior surfaces of the fiberglass floor drains shall be pigmented by the manufacturer with a color that matches the concrete.  
The top portion of aluminum floor drains shall be coated with 5 mils of either bitumen paint or epoxy paint to minimize reaction with wet concrete.  
The clamping device and inserts shall be galvanized according to AASHTO M 232. Cost of clamping device included with Floor Drains.  
The 3/16" minimum aluminum sheet shall be ASTM B 209 alloy 3003-H14 and coated with 5 mils of either bitumen paint or epoxy paint to minimize reaction with wet concrete. Cost included with Concrete Superstructure.  
The Polyurethane Sealant shall be according to Article 1050.04 of the Std. Spec. and the color shall be gray.  
Bar terminators, paid for separately. See Total Bill of Material.  
See Sheet 9 of 20 for expansion joint replacement details.






**SUPERSTRUCTURE**  
**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
a(E)	334	#5	7'-4"	—
a1(E)	666	#5	7'-0"	—
a2(E)	666	#5	8'-4"	—
a3(E)	332	#5	7'-8"	—
b(E)	100	#5	33'-8"	—
b1(E)	24	#7	33'-9"	—
b2(E)	120	#5	28'-8"	—
d(E)	484	#5	6'-5"	—
d1(E)	460	#5	8'-4"	—
e(E)	72	#4	15'-4"	—
e1(E)	32	#4	24'-5"	—
e2(E)	80	#4	6'-4"	—
e3(E)	36	#4	13'-1"	—
e4(E)	16	#4	21'-1"	—
m(E)	8	#6	3'-9"	—
m1(E)	16	#4	4'-5"	—
m2(E)	24	#4	3'-9"	—
s(E)	20	#4	10'-0"	U
s1(E)	30	#4	7'-10"	U
Reinforcement Bars, Epoxy Coated Concrete Superstructure			Lbs.	34,430
Concrete Superstructure			Cu. Yds.	113.1



Bars indicated thus 1 x 2-#4 etc. indicates 1 line of bars with 2 lengths per line.



SECTION THRU PARAPET AT ENDS




SECTION A-A  
\*Dimension as required by pipe clamp




BAR d(E)

BAR d1(E)


MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01\_IDOT.D3\_PTB 214-032.WO 01 US 6 over Aux\_Sable\_Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-007-Superstructure.dgn  
3/6/2026 12:40:48 PM



**DIAPHRAGM AT PIER 1**  
(2 locations)




**DIAPHRAGM AT PIER 2**  
(2 locations)




**SECTION A-A**


\* Minimum length to remain:  
#4 bars = 1'-7"




**PLAN AT PIER 1**  
(Showing bearing pads and P.J.F. details)



**PLAN AT PIER 2**  
(Showing bearing pads and P.J.F. details)




**SIDE RETAINER**  
(2 required each side of pier).  
Equivalent rolled angle with stiffeners  
will be allowed in lieu of welded plates.




**ELASTOMERIC BEARING DETAIL**


**Notes:**  
See sheet 6 of 20 for superstructure details and Bill of Material.  
Anchor bolts and side retainers shall be installed in drilled holes according to Article 521.06 of the Standard Specifications. Side retainers shall be hot dip galvanized.  
Anchor bolts and side retainers shall be installed as each exterior beam is erected unless an equivalent temporary means of lateral restraint is used. Cost of side retainers, anchor bolts, and elastomeric and fabric bearing pads shall be included with Furnishing and Erecting 42" PPC I-Beams.  
Existing reinforcement bars extending into the removal area shall be cleaned, straightened, and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system at the Contractor's expense.



**INTERIOR DIAPHRAGM**  
(6 locations)







**SECTION B-B**




**DETAIL 'A'**

MODEL: Default  
FILE NAME: 012022R31DOTCAD CONNECT\2505101 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-008-Diaphragm.dgn  
3/6/2026 12:40:50 PM

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-009-Expansion Joint.dgn




**Notes:**  
 Hatched areas indicate limits of Concrete Removal.  
 For details of parapets at expansion joints, see Sheet 10 of 20.  
 Parapet quantities not included with Concrete Removal or Concrete Superstructure quantities on this sheet.



**BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
a10(E)	36	#7	22'-8"	—
a11(E)	40	#6	7'-2"	—
a12(E)	20	#6	3'-5"	—
d1(E)	24	#5	8'-4"	⌒
h10(E)	16	#6	21'-8"	—
u10(E)	140	#6	7'-5"	⌒
Concrete Removal			Cu. Yd.	26.6
Reinforcement Bars, Epoxy Coated			Pound	4,490
Concrete Superstructure			Cu. Yd.	24.5



FOR SKEWS ≤ 30°


**PLAN AT PARAPET**

FOR SKEWS > 30°




**SECTION B-B**

(3/4" Ø countersunk bolts extending into concrete shall have hex nuts tack welded to the back of the embedded plates with end caps provided.)




**SECTION AT PARAPET**

(Skews > 30° shown. Skews ≤ 30° similar except as shown in plan view.)




**TRIMETRIC VIEW**

(Showing embedded plates only)



**DETAIL A**

(Kick-up at parapet locations shown. See sheet 5 of 20 for kick-up at curb locations.)




**SHOWING ROLLED RAIL JOINT**

\* 5/8" Ø x 6" studs @ 6" cts. (alternate angled/bent studs with horizontal studs)


3/8" Ø threaded rods in 7/16" Ø holes at 4'-0" ± cts. for holding the proper joint opening based on the temperature during the deck pour. Place to miss studs. All rods shall be burned, or sawed off flush with the plates after concrete is set.

**SECTION A-A**

\* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.




**SHOWING WELDED RAIL JOINT**



**LOCKING EDGE RAILS**

\*\* Back gouge not required if complete joint penetration is verified by mock-up.



**LOCKING EDGE RAIL SPLICE**

The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

**BILL OF MATERIAL**

Item	Unit	Total
Preformed Joint Strip Seal	Foot	92

MODEL: Default FILE NAME: 012022R31DOTCAD CONNECT25051,01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-010-Expansion Join.dgn

EJ-SS

4-4-2025

**EFK•Moen**  
Civil Engineering Design

USER NAME =	SUSERS\$
PLOT SCALE =	
PLOT DATE =	3/6/2026


DESIGNED -	KRH	REVISED -	
CHECKED -	ACB	REVISED -	
DRAWN -	KRH	REVISED -	
CHECKED -	ACB	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**


**PREFORMED JOINT STRIP SEAL**  
**STRUCTURE NUMBER 032-0025**

SHEET 10 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	34
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				




**ELEVATION OF BEAM**  
(Showing reinforcement & dimensions)




**SECTION A-A**  
\*\* Only tighten sufficiently to compress lock washers

**SECTION B-B**



**ELEVATION OF BEAM**  
(Showing prestressing steel)




**SECTION C-C**  
(20-3/2" Ø 270 ksi strands)

**BAR LIST**  
**ONE BEAM ONLY**  
(For information only)


Bar	No.	Size	Length	Shape
G1(E)	104	#4	8'-7"	⌈ L
G2(E)	10	#4	6'-8"	⌈
G3(E)	8	#6	30'-6"	⌈
G4(E)	38	#3	4'-11"	⌈
G5(E)	53	#3	2'-6"	⌈

Notes:  
See sheet 11 of 20 for additional details and Bill of Material.


MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-011-42 PPC I-Beams.dgn  
3/6/2026 12:40:55 PM




**LIFTING LOOP DETAIL**




**BAR G1(E)**




**BAR G2(E)**




**BAR G4(E)**




**BAR G5(E)**



**TOP PLATE**



**BOTTOM PLATE (Showing threaded rods)**



**BOTTOM PLATE (Showing studs)**

See bearing details for pintle hole locations when required.

**NOTES**

Inserts for 3/4" Ø threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in. The beams shall have a final concrete compressive strength, f'c, of 6,000 psi and a release concrete compressive strength, f'ci, of 5,000 psi. A minimum 2 1/2" Ø lifting pin shall be used to engage the lifting loops during handling. Tilt G6(E) bars when necessary to maintain 1 1/2" clearance. The top and bottom plates shall be AASHTO M270 Grade 50. The top and bottom plates shall be galvanized according to AASHTO M111. The threaded rods, nuts and washers shall be galvanized according to AASHTO M232. Threaded rods shall be ASTM F 1554 Grade 55. The G6(E) bar assembly shall develop, in tension, at least 125 percent of the yield strength of a grade 60 reinforcement bar times the nominal cross-sectional area of a #8 bar. The assembly shall allow completion of the splice without turning of the hook bar. The hook bar shall be threaded such that the entire coupler can be threaded onto the hook bar.

**BILL OF MATERIAL**

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 42"	Ft.	320

MODEL: Default FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-012-42 PPC I-Beam Details.dgn 3/6/2026 12:40:56 PM




USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
PLOT SCALE =	CHECKED - ACB	REVISED -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISED -
	CHECKED - ACB	REVISED -

**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION**

**42" PPC I-BEAM DETAILS  
STRUCTURE NUMBER 032-0025**

SHEET 12 OF 20 SHEETS


F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 36
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66N58	




**ELEVATION AT ABUT.**

**SECTION A-A**



**TYPE II ELASTOMERIC EXP. BRG.**




**TOP BEARING ASSEMBLY**



**PINTLE**





**BOTTOM BEARING ASSEMBLY**



**SIDE RETAINER**

Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.




BELOW 50°F.

ABOVE 50°F.

$D = 1/8"$  per each 100' of expansion for every 15° temp. change from the normal temp. of 50°F.

**EXPANSION BEARING ORIENTATION**

The above diagrams are for informational purposes only to show the amount of expected offset "D" for the current temperature in the field.



**EXISTING BEARING REMOVAL DETAIL**

Cost included with Jack and Remove Existing Bearings.

**BEAM REACTIONS**

$R_{DL}$	(K)	32.5
$R_{LL}$	(K)	57.8
Imp.	(K)	15.0
$R$ (Total)	(K)	105.3

**Notes:**



- Min. jack capacity = 100 Tons.
- Side retainers and leveling pads shall be included in the cost of Elastomeric Bearing Assembly, Type II.
- The 1/8" PTFE sheet shall be bonded directly to the top steel plate with a two-component, medium viscosity epoxy resin, conforming to the requirements of the Federal Specification MMM-A-134, Type I. The bond agent shall be applied on the full area of the contact surfaces.
- Bonding of 1/8" PTFE sheet during vulcanizing process will be permitted provided the process and method of adjusting assembly height is approved by the Engineer. See sheet 11 of 20 for additional details of embedded plate.
- Anchor bolts and side retainers at all supports shall be installed as each member is erected unless an equivalent temporary means of lateral restraint is used.
- All exposed bearing plates and side retainers shall be hot dipped galvanized according to AASHTO M111.

**BILL OF MATERIAL**


Item	Unit	Total
Elastomeric Bearing Assembly, Type II	Each	12
Anchor Bolts, 1"	Each	24

MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-013-Bearing Details.dgn  
3/6/2026 12:40:57 PM


MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-014-Beam Repairs.dgn  
 3/6/2026 12:40:59 PM



**TYPICAL DAMAGE AT BEAM ENDS**  
 (8 Beam End Locations)  
 9.1 sq. ft. per location, 73 sq. ft. Total  
 (4 existing beams on each abutment end)



\* Horizontal Anchorage Strips and Bottom Flange Strip to extend 6" beyond end of beam and wrap onto beam end.



**FRP TREATMENT AT END OF BEAM**

**NOTES**

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The Contractor shall use extreme care during concrete removal to avoid damage to the PPC I-Beams.

The existing concrete surface shall be cleaned and prepared in accordance with the Special Provisions.

See Special Provisions for "FRP Strengthening for PPC I-Beam Repairs".  
 See Special Provisions for "Precast Prestressed Concrete I-Beam Repair".  
 Acrylic coating shall be placed over Fiber Wrap repairs. Two coats shall be applied.

**LEGEND**

- P.P.C. I-Beam Repair
- Fiber Wrap Repair (Layer 1)
- Fiber Wrap Repair (Layer 2)


**BILL OF MATERIAL**

Item	Unit	Total
Fiber Wrap	Sq. Ft.	232
Acrylic Coating	Sq. Yd.	26
Precast Prestressed Concrete I-Beam Repair	Sq. Ft.	73


USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
PLOT SCALE =	CHECKED - ACB	REVISED -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISED -
	CHECKED - ACB	REVISED -

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 38
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-015-Abutment Repairs.dgn



**WEST ABUTMENT ELEVATION**  
 (Looking West)



**EAST ABUTMENT ELEVATION**  
 (Looking East)

**LEGEND**

- Structural Repair of Concrete (Depth Equal to or Less Than 5")
- Epoxy Crack Injection

**BILL OF MATERIAL**

Item	Unit	Total
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.	14.0
Epoxy Crack Injection	Foot	16



USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
	CHECKED - ACB	REVISED -
PLOT SCALE =	DRAWN - KRH	REVISED -
PLOT DATE = 3/6/2026	CHECKED - ACB	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ABUTMENT REPAIRS**  
**STRUCTURE NUMBER 032-0025**


SHEET 15 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	39
			CONTRACT NO. 66N58	
		ILLINOIS	FED. AID PROJECT	

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-016-Pier\_1 Repairs.dgn



**PIER 1 ELEVATION**  
 (Looking East)



**PIER 1 ELEVATION**  
 (Looking West)

**LEGEND**

- Structural Repair of Concrete (Depth Equal to or Less Than 5")
- Epoxy Crack Injection

**BILL OF MATERIAL**

Item	Unit	Total
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.	12.0
Epoxy Crack Injection	Foot	32



USER NAME =	SUSERS\$	DESIGNED -	KRH	REVISED -	
		CHECKED -	ACB	REVISED -	
PLOT SCALE =		DRAWN -	KRH	REVISED -	
PLOT DATE =	3/6/2026	CHECKED -	ACB	REVISED -	


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**PIER 1 REPAIRS  
 STRUCTURE NUMBER 032-0025**


SHEET 16 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	40
			CONTRACT NO. 66N58	
		ILLINOIS	FED. AID PROJECT	

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-017-Pier 2 Repairs.dgn



**PIER 2 ELEVATION**  
 (Looking East)



**PIER 2 ELEVATION**  
 (Looking West)

**LEGEND**

- Structural Repair of Concrete (Depth Equal to or Less Than 5")
- Epoxy Crack Injection





**BILL OF MATERIAL**

Item	Unit	Total
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.	10.0
Epoxy Crack Injection	Foot	32


USER NAME = \$USERS\$	DESIGNED - KRH	REVISED -
	CHECKED - ACB	REVISED -
PLOT SCALE =	DRAWN - KRH	REVISED -
PLOT DATE = 3/6/2026	CHECKED - ACB	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	41
CONTRACT NO. 66N58				
ILLINOIS		FED. AID PROJECT		


MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-018-Wingwall Recon\_g.dgn



\*Epoxy grout h(E), v(E) and v1(E) bars in 9" min. holes according to Article 584 of the Standard Specifications. Cost included with Reinforcement Bars, Epoxy Coated.



BAR s2(E)




BAR v(E) & v1(E)

**WINGWALL  
 BILL OF MATERIAL  
 (4 WINGS)**


Bar	No.	Size	Length	Shape	
h(E)	32	#4	3'-7"	—	
h1(E)	16	#4	8'-5"	—	
h2(E)	16	#4	3'-11"	—	
s2(E)	12	#4	3'-4"	□	
v(E)	20	#4	1'-9"	U	
v1(E)	20	#4	2'-5"	U	
Reinforcement Bars, Epoxy Coated				Lbs.	290
Concrete Superstructure				Cu. Yds.	1.3

MODEL: Default  
 FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N5B-019-Slipforming.dgn  
 3/6/2026 12:41:05 PM




**39" CONSTANT-SLOPE  
PARAPET SECTION**  
(Showing dimensions, d(E), and 1/2" Ø GFRP rebar)


**STEEL SUPERSTRUCTURES**  
\*See Superstructure Details.




**44" CONSTANT-SLOPE  
PARAPET SECTION**  
(Showing dimensions, d(E), and 1/2" Ø GFRP rebar)



**39" CONSTANT-SLOPE  
PARAPET SECTION**  
(Showing dimensions, d(E), and 1/2" Ø GFRP rebar)



**SF(E) BAR**



**DETAIL - GFRP REBAR STIFFENING ELEVATION**  
(Place as shown in parapet section at each parapet joint location.)

**Notes:**  
 All dimensions shall remain the same as shown on superstructure details, except dimension "A" which is to be revised as shown.  
 Additional concrete needed to revise dimension "A" (39" and 44" parapets):  
 Steel Superstructures: 0.00348 cu. yds./ft.  
 Slab Bridge Superstructures: cu. yds./ft.  
 Place full depth aluminum sheets as shown on superstructure details.  
 Replace all cork joint filler locations with a full thickness saw cut.  
 Steel and slab superstructures shown. Other superstructure types similar.

SFP 39-44

10/27/2023

**EFK Moen**  
Civil Engineering Design

USER NAME = \$USER\$	DESIGNED - KRH	REVISIONS -
PLOT SCALE =	CHECKED - ACB	REVISIONS -
PLOT DATE = 3/6/2026	DRAWN - KRH	REVISIONS -
	CHECKED - ACB	REVISIONS -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**CONCRETE PARAPET SLIPFORMING OPTION  
STRUCTURE NUMBER 032-0025**

SHEET 19 OF 20 SHEETS

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 43
CONTRACT NO. 66N58				

ILLINOIS FED. AID PROJECT




**STANDARD BAR SPLICER ASSEMBLY PLAN**

Only bar splicer assemblies as presented on the approved QPL list may be used.

Threaded splicer bar length = min. lap length + 1 1/2" + thread length

\* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Minimum lap length
Expansion Joint	#6	8	3'-1"
Expansion Joint	#7	18	3'-5"




**INSTALLATION AND SETTING METHODS**

"A" : Set bar splicer assembly by means of a template bolt.


"B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E) : Indicates epoxy coating.



**STANDARD MECHANICAL SPLICER**

Location	Bar size	No. assemblies required
Top of Deck	#5	334
Bottom of Deck	#5	666
Expansion Joint	#6	10
Diaphragms	#6	8



**THREADING OF ASSEMBLIES**

The threaded length "X" shall be no more than L/2. The bar should be tightened until 0-1 thread(s) is/are exposed.

**Notes:**

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.

See approved list of bar splicer assemblies and mechanical splicers for alternatives.

MODEL: Default  
FILE NAME: O:\2022R3\DOTCAD CONNECT\25051.01 IDOT D3 PTB 214-032 WO 01 US 6 over Aux Sable Creek\CADD Data\Structures\Plotsheets\0320025-66N58-020-Bar\_Splicer.dgn

BSD-1

4-4-2025

**EFK Moen**  
Civil Engineering Design

USER NAME = \$USER\$	DESIGNED - KRH	REVISER -
	CHECKED - ACB	REVISIONS -
PLOT SCALE =	DRAWN - KRH	REVISIONS -
PLOT DATE = 3/6/2026	CHECKED - ACB	REVISIONS -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS  
STRUCTURE NUMBER 032-0025

SHEET 20 OF 20 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	44
CONTRACT NO. 66N58				

ILLINOIS FED. AID PROJECT

MODEL: C:\projects\01 (Sheet)  
 FILE NAME: C:\2022\23\DOT\CAD\CONNECT\250651.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CAD Sheets\366N58-sh-Detail.dgn



STA 248+82.71 TO STA 249+72.71  
 STA 251+75.79 TO STA 252+65.79

**EFK Moen**  
 Civil Engineering Design


USER NAME = sklerplec	DESIGNED - SNK	REVISED -
	DRAWN - PJG	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/20/2026	DATE - 1/23/2026	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 TRANSITION DETAIL

SCALE: NONE SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.U. RTE. 392	SECTION (G-BR)BR-1	COUNTY GRUNDY	TOTAL SHEETS 56	SHEET NO. 45
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				




## TYPICAL BENCHING DETAIL FOR EMBANKMENT

### NOTES:


- ① CONSTRUCT SUCCEEDING BENCH CUTS AND EMBANKMENT PLACEMENT AND COMPACTION FROM BOTTOM TO TOP IN STAIRSTEP FASHION.
- ② EXISTING FORESLOPE PREPARED IN ACCORDANCE WITH ARTICLE 205.03 OF THE STANDARD SPECIFICATIONS.
- ③ BENCH CUT EXISTING SLOPE TYPICAL FOR EACH STEP.
- ④ TRIM TO FINAL SLOPE.
- ⑤ EQUAL 8-INCH LIFTS OF EMBANKMENT COMPACTED IN ACCORDANCE WITH ARTICLE 205.05 OF THE STANDARD SPECIFICATIONS.
- ⑥ EXCAVATION OF BENCH CUTS WITHIN EXISTING EMBANKMENT WILL BE INCLUDED IN THE COST OF FURNISHED EXCAVATION.
- ⑦ SLOPES SHALL BE BENCHED ACCORDING TO THIS DETAIL WHEN THE SLOPE IS STEEPER THAN 1V:4H AND THE HEIGHT IS GREATER THAN 5'.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SHOWN.

205-4



### SECTION A-A



### SECTION B-B

## FIELD ENTRANCE DETAIL

\* USE 1V:6H SLOPE OR MATCH EXIST FORESLOPE (USE FLATTER OF TWO.)

MODEL: C:\Users\skierplec\OneDrive\Desktop\CAD\CADD Data\CADD sheets\366N58-sh1-Detail.dgn

**EFK Moen**  
Civil Engineering Design

USER NAME = skierplec	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 1/19/2026	DATE -	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
DISTRICT 3 STANDARD DETAILS**

SCALE: NONE    SHEET 2 OF 4 SHEETS    STA.    TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	46
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				


402-1



TO BE POST MOUNTED AS SHOWN ELSEWHERE IN THE PLANS.

COST OF SUPPLYING, INSTALLING, MAINTAINING AND REMOVING WIDTH RESTRICTION SIGNS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION PAY ITEMS.

## WIDTH RESTRICTION SIGNING DETAILS 701-6



## TEMPORARY INFORMATION SIGNING

### NOTES:

- USE 6" D BLACK LETTERING ON FLUORESCENT ORANGE BACKGROUND.
- ERECT SIGNS AT LOCATIONS IN ADVANCE OF THE "ROAD CONSTRUCTION AHEAD" SIGNS AS DIRECTED BY THE ENGINEER.
- ERECT SIGN ① WITH INSTALLED PANEL ② A MINIMUM OF ONE WEEK PRIOR TO THE START OF THE LANE CLOSURE.
- REMOVE PANEL ② ON THAT DATE.
- SEE SPECIAL PROVISION "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- WILL BE PAID FOR PER SQ FT AS "TEMPORARY INFORMATION SIGNING". EACH SIGN = 21 SQ FT AND THE DATE PANEL ② WILL NOT BE MEASURED SEPARATELY FOR PAYMENT.

720-8

MODEL: C:\projects\03 (Sheet)  
FILE NAME: C:\2022\23\DOT\CADD\CONNECT\250651.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CAD Sheets\366N58-sh-Details.dgn

**EFK Moen**  
Civil Engineering Design


USER NAME = pgillespie	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 1/21/2026	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
DISTRICT 3 STANDARD DETAILS


SCALE: NONE SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	47
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				




782-4

**BARRIER WALL MARKER**



**PAVEMENT MARKING**

780-8




**LINEAR DELINEATOR APPLICATION TO STANDARD GALVANIZED GUARDRAIL**

LINEATOR DELINEATOR SHALL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS

**4" BRACKET**

782-5

AMBER TYPE "C" PRISMATIC BARRIER WALL REFLECTORS AT 25' CTS.



**LINEAR DELINEATOR PANELS FOR TEMPORARY CONCRETE BARRIER**

782-6

MODEL: C:\projects\5 (Sheet)  
FILE NAME: C:\2022\23\IDOCAD\CONNECT\25051.01.IDOT.D3.PTB.2144032.WO.01.US.6.Over.Aux.Sable.Creek\CADD>Data\CAD\Drawings\366N58-sh-Details.dgn

**EFK Moen**  
Civil Engineering Design

USER NAME = skierplec	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 1/20/2026	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


US 6 OVER AUX SABLE CREEK  
DISTRICT 3 STANDARD DETAILS

SCALE: NONE SHEET 4 OF 4 SHEETS STA. TO STA.


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	48
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				



MODEL: XSC02  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25061\_01\_IDOT\_D3\_PTB\_214432\_WO\_01\_US\_6\_Over\_Aux\_Sable\_Creek\CADD>Data\CAD\Sheets\366N58-Ex-RW-Crossht.dgn



**STA 248+00.00**



**STA 247+50.00**

**EFK Moen**  
 Civil Engineering Design

USER NAME = pgillespie	DESIGNED - JDB	REVISED -
	DRAWN - ZJW	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/22/2026	DATE - 1/23/2026	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK**  
**CROSS SECTIONS**


SCALE: 1"=10'    SHEET 2 OF 8 SHEETS    STA.    TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	50
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: XSC03  
 FILE NAME: C:\2022\23\DOT\CADD\CONNECT\250651\_01\_IDOT\_D3\_PTB\_2144032\_WO\_01\_US\_6\_Over\_Aux\_Sable\_Creek\CADD Data\CAD\Sheets\366N58-sh-xssht.dgn




STA 249+00.00




STA 248+50.00

**BRIDGE OMISSION**  
**STA 249+93.83 TO STA. 251+54.67**



**STA 249+80.08**



**STA 249+50.00**

MODEL: XSC04  
 FILE NAME: C:\2022\23\DOTCAD\CONNECT\250651.D1\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-sh-xssht.dgn

**EFK Moen**  
 Civil Engineering Design

USER NAME =	pgillespie	DESIGNED -	JDB	REVISED -	
		DRAWN -	ZJW	REVISED -	
		CHECKED -	RBB	REVISED -	
PLOT DATE =	1/23/2026	DATE -	1/23/2026	REVISED -	


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK**  
**CROSS SECTIONS**


SCALE: 1" = 10'      SHEET 4      OF 8      SHEETS      STA.      TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	52
CONTRACT NO. 66N58			ILLINOIS FED. AID PROJECT	

MODEL: XSC05  
 FILE NAME: C:\2022R3\DOT\CAD\CONNECT\25051\_01\_IDOT\_D3\_PTB\_2144032\_WO 01 US 6 over Aux Sable Creek\CADD Data\CAD\Sheets\366N58-sh-xssht.dgn



**STA 252+00.00**



**STA 251+68.42**



USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - ZJW	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/22/2026	DATE - 1/23/2026	REVISED -




**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
 CROSS SECTIONS**

SCALE: 1" = 10'    SHEET 5    OF 8    SHEETS    STA.    TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	53
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				

MODEL: XSC06  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25061.01\DOT D3 PTB 214-032.WO 01 US 6 over Aux Sable Creek\CADD Data\CADsheets\366N58-sh-xssht.dgn



<b>EFK Moen</b> Civil Engineering Design	USER NAME = sklerplec	DESIGNED - JDB	REVISED -
		DRAWN - ZJW	REVISED -
		CHECKED - RBB	REVISED -
	PLOT DATE = 1/20/2026	DATE - 1/23/2026	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**US 6 OVER AUX SABLE CREEK  
 CROSS SECTIONS**


SCALE: 1"=10'    SHEET 6 OF 8 SHEETS    STA.    TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	54
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				


MODEL: YSC07  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25051\_01\_IDOT\_D3\_PTB\_2144032\_WO 01\_US 6 over Aux\_Sable\_Creek\CADD Data\CADsheets\366N58-sh-ssht.dgn



STA 254+50.00



STA 254+00.00



STA 253+50.00



USER NAME = skierplec	DESIGNED - JDB	REVISED -
	DRAWN - ZJW	REVISED -
	CHECKED - RBB	REVISED -
PLOT DATE = 1/20/2026	DATE - 1/23/2026	REVISED -


STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 CROSS SECTIONS


SCALE: 1"=10' SHEET 7 OF 8 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	55
CONTRACT NO. 66N58				
ILLINOIS FED. AID PROJECT				


MODEL: XSC08  
 FILE NAME: C:\2022R3\DOTCAD\CONNECT\25061\_01\_IDOT\_D3\_PTB\_2144032\_WO 01 US 6 over Aux Sable Creek\CADD Data\CAD\Sheets\366N58-sh-ssht.dgn



STA 256+00.00



STA 255+50.00



STA 255+00.00



USER NAME =	pgillespie	DESIGNED -	JDB	REVISED -	
		DRAWN -	ZJW	REVISED -	
		CHECKED -	RBB	REVISED -	
PLOT DATE =	1/22/2026	DATE -	1/23/2026	REVISED -	

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

US 6 OVER AUX SABLE CREEK  
 CROSS SECTIONS

SCALE: 1"=10' SHEET 8 OF 8 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
392	(G-BR)BR-1	GRUNDY	56	56
CONTRACT NO. 66N58			ILLINOIS FED. AID PROJECT	