



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 6, 2026

SUBJECT: FAU 9250 & FAS 1881 (East Park Street Road)
Section 22-00152-00-RS
Perry County
Contract No. 99768
Item 208
April 24, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Fold-up Plan Pages 3 & 5

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Summary Of Quantities			
Item No.	Pay Item	Unit	Quantity
40600290	BITUMINOUS MATERIALS (TACK COAT)	PD	13,817
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SY	222
40604052	HMA SURFACE COURSE, IL-9.5, MIX "C", N70	TN	5,200
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SY	4,322
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TN	445
58100200	WATERPROOFING MEMBRANE SYSTEM	SY	307
67100100	MOBILIZATION	LS	1
70300100	SHORT TERM PAVEMENT MARKING	FT	2,704
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FT	71,061
* LR400520	HOT IN-PLACE RECYCLING-SURFACE RECYCLING	SY	61,088
* LR400510	REJUVENTATING AGENT	GA	6,108
X4401198	HMA SURFACE REMOVAL, VARIABLE DEPTH	SY	788
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LS	1
Z0013798	CONSTRUCTION LAYOUT	LS	1

* SPECIALTY ITEM

Estimating Factors		
Item	Rate	Units
Aggregate	2.05	TN/CY
Tack Coat on Existing Pavement	0.05	PD/SF
Tack Coat on HIR	0.025	PD/SF
HMA	112	PD/SY/IN

Surfacing									
Location	Length FT	Width FT	Area SY	HOT IN-PLACE RECYCLING LR400520	REJUVE- NATING AGENT LR400510	TACK COAT 40600290	HMA SURFACE 1.5" 40604052		AGGRE- GATE WEDGE 48102100
				SY	GA	PD	Main Line TN	Sideroads Driveways TN	TN
0 to 13+25	1,325	26.0	3,828	3,828	383	861	322	0	0
13+25 to 54+11	4,086	23.5	10,669	10,669	1,067	2,401	896	31	78
54+11 to 180+00	12,589	21.0	29,374	29,374	2,937	6,609	2,467	19	239
180+00 to 246+89	6,689	23.0	17,094	17,094	1,709	3,846	1,436	10	127
250+96 to 251+44	48	23.0	123	123	12	28	10	0	1
Old DuQuoin Rd	15	96.0	160	0	0	72	0	9	0
Column Totals				61,088	6,108	13,817	5,131	69	445
Project Totals				61,088	6,108	13,817	5,200		445

WATERPROOFING MEMBRANE SYSTEM			
Location	Length FT	Width FT	Area SY
Station to Station	FT	FT	SY
103+01 to 103+33	32	26.0	92
204+18 to 204+61	43	23.5	112
223+49 to 223+93	44	21.0	103
Project Totals			307

Mixture Requirements	
Locations:	E. Parkt Street Rd
Mixtures Uses:	HMA SURFACE COURSE, IL-9.5, MIX "C", N70
AC/PG:	PG 64-22
RAP % (Max):	10%
Design Air Voids:	4% Ndes 70
Mixture Composition (Gradation Composition):	IL 9.5
Friction Aggregate:	Mixture C
Mixture Weights:	112 pd / sy / inch thickness