

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL.	608	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
* (26, 26HB-1&114) R-2		CONTRACT NO. 60363		

SUMMARY OF QUANTITIES

90% FED. / 10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	WILL COUNTY											TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	90% FED. / 10% STATE			
				ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS		CITY OF JOLIET 100% JOLIET	RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS	
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E		Y031-1F	J000-2A	Y007	J000-2A
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7,375	240	7,135														
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	12,249	210	10,864	1,020		155											
* 72000100	SIGN PANEL - TYPE 1	SQ FT	569									558			11				
* 72000200	SIGN PANEL - TYPE 2	SQ FT	131									131							
* 72000300	SIGN PANEL - TYPE 3	SQ FT	1,221									1,221							
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	112									112							
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	9									9							
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	570									570							
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	145									145							
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	640									640							
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	19									19							
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	105									105							
* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	20									20							
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1132									1132							
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	76									76							
* 73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	90									90							
* 73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	20									20							
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24									24							
* 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	4									4							
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	73				218											
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47,727	1,556	25,762			3,809	16,600										
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	872	322				550											
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,595		1,909	932	1,754												
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,141		1,141														
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	182	42				140											
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	8,227		8,227														
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	13,914		13,914														
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	4,187		4,187														
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	3,476		3,476														
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	619	546		73													
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	26,587	14,158		5,575	4,706			640	1,508								

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59
 SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 9

SCALE: DATE: 03/14/08

DRAWN BY: JB
 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
 ENGINEERS ARCHITECTS PLANNERS
 280 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE 312.642.6000

S:\SUDOPRS5.DGN, ... S:\SUDOPRS5.DGN, ... T\FBGRN.DGN
 3-24-2008, 10:31:47
 I:\DOCUMENT\9327930\CIVIL\DWG\SUDOPRS5.DGN
 2-3-2008 11:12:13 AM 15:18:19 202122324252827282930313233343536373839404142434445464748495051525354555657585960616263

Rev.