

LOCATION STATION TO STATION	TOPSOIL EXCAVATION (CU YD)				EARTH EXCAVATION (ALL SUITABLE) (CU YD)				EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)				EMBANKMENT (CU YD)				EARTHWORK BALANCE (CU YD)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)				
	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	
8000+00.00	8001+00.00	0.0	0.0	205.1	0.0	0.0	137.3	0.0	0.0	0.0	116.7	0.0	0.0	0.0	252.2	0.0	0.0	0.0	0.0	-135.5	0.0	0.0	0.0	172.3	0.0
8001+00.00	8002+00.00	0.0	0.0	213.1	0.0	0.0	177.6	0.0	0.0	0.0	151.0	0.0	0.0	0.0	236.0	0.0	0.0	0.0	0.0	-85.0	0.0	0.0	0.0	178.5	0.0
8002+00.00	8003+00.00	0.0	0.0	211.6	0.0	0.0	208.9	0.0	0.0	0.0	177.6	0.0	0.0	0.0	198.7	0.0	0.0	0.0	0.0	-21.2	0.0	0.0	0.0	179.1	0.0
8003+00.00	8004+00.00	0.0	0.0	208.9	0.0	0.0	250.4	0.0	0.0	0.0	212.8	0.0	0.0	0.0	141.3	0.0	0.0	0.0	0.0	71.5	0.0	0.0	0.0	179.3	0.0
8004+00.00	8005+00.00	0.0	0.0	187.5	0.0	0.0	233.5	0.0	0.0	0.0	198.5	0.0	0.0	0.0	114.7	0.0	0.0	0.0	0.0	83.8	0.0	0.0	0.0	160.4	0.0
8005+00.00	8006+00.00	0.0	0.0	160.0	0.0	0.0	201.9	0.0	0.0	0.0	171.6	0.0	0.0	0.0	102.6	0.0	0.0	0.0	0.0	69.0	0.0	0.0	0.0	134.3	0.0
8006+00.00	8007+00.00	0.0	0.0	156.1	0.0	0.0	127.8	0.0	0.0	0.0	108.6	0.0	0.0	0.0	87.4	0.0	0.0	0.0	0.0	21.2	0.0	0.0	0.0	130.6	0.0
8007+00.00	8008+00.00	0.0	0.0	215.1	0.0	0.0	40.4	0.0	0.0	0.0	34.4	0.0	0.0	0.0	424.8	0.0	0.0	0.0	0.0	-390.4	0.0	0.0	0.0	180.3	0.0
8008+00.00	8009+00.00	0.0	0.0	298.6	0.0	0.0	19.7	0.0	0.0	0.0	16.8	0.0	0.0	0.0	930.3	0.0	0.0	0.0	0.0	-913.5	0.0	0.0	0.0	254.8	0.0
8009+00.00	8010+00.00	183.2	0.0	163.6	0.0	0.2	0.0	0.0	0.2	0.0	0.0	0.0	0.0	722.5	0.0	576.2	0.0	-722.3	0.0	-576.2	0.0	154.9	0.0	141.6	0.0
8010+00.00	8011+00.00	394.7	0.0	0.0	0.0	0.2	0.0	0.0	0.2	0.0	0.0	0.0	0.0	1671.4	0.0	49.4	0.0	-1671.2	0.0	-49.4	0.0	330.9	0.0	0.0	0.0
8011+00.00	8012+00.00	461.7	0.0	0.0	0.0	0.5	0.0	0.0	0.0	0.4	0.0	0.0	0.0	2198.8	0.0	50.1	0.0	-2198.3	0.0	-50.1	0.0	380.1	0.0	0.0	0.0
8012+00.00	8013+00.00	549.1	0.0	0.0	0.0	11.8	0.0	0.0	10.0	0.0	0.0	0.0	0.0	2911.9	0.0	51.3	0.0	-2901.8	0.0	-51.3	0.0	444.0	0.0	0.0	0.0
8013+00.00	8014+00.00	644.3	0.0	0.0	0.0	40.1	0.0	0.0	34.1	0.0	0.0	0.0	0.0	3806.6	0.0	51.7	0.0	-3772.5	0.0	-51.7	0.0	513.8	0.0	0.0	0.0
8014+00.00	8015+00.00	692.1	0.0	0.0	0.0	43.4	0.0	0.0	36.9	0.0	0.0	0.0	0.0	4930.0	0.0	51.7	0.0	-4893.1	0.0	-51.7	0.0	548.9	0.0	0.0	0.0
8015+00.00	8016+00.00	724.9	0.0	0.0	0.0	17.7	0.0	0.0	15.1	0.0	0.0	0.0	0.0	6418.4	0.0	51.7	0.0	-6403.4	0.0	-51.7	0.0	572.9	0.0	0.0	0.0
8016+00.00	8017+00.00	810.6	0.0	0.0	0.0	4.6	0.0	0.0	3.9	0.0	0.0	0.0	0.0	8159.6	0.0	51.6	0.0	-8155.7	0.0	-51.6	0.0	635.8	0.0	0.0	0.0
8017+00.00	8018+00.00	827.3	0.0	0.0	0.0	2.1	0.0	0.0	1.8	0.0	0.0	0.0	0.0	9925.6	0.0	50.5	0.0	-9923.9	0.0	-50.5	0.0	635.9	0.0	0.0	0.0
8018+00.00	8019+00.00	624.6	0.0	0.0	0.0	3.1	0.0	0.0	2.6	0.0	0.0	0.0	0.0	9523.8	0.0	42.4	0.0	-9521.2	0.0	-42.4	0.0	472.1	0.0	0.0	0.0
8019+00.00	8020+00.00	229.8	0.0	0.0	0.0	2.4	0.0	0.0	2.0	0.0	0.0	0.0	0.0	4124.7	0.0	17.6	0.0	-4122.7	0.0	-17.6	0.0	174.1	0.0	0.0	0.0
8020+00.00	8021+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8021+00.00	8022+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8022+00.00	8023+00.00	176.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3806.6	0.0	17.6	0.0	-3806.6	0.0	-17.6	0.0	132.1	0.0	0.0	0.0
8023+00.00	8024+00.00	466.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7959.7	0.0	35.2	0.0	-7959.7	0.0	-35.2	0.0	360.7	0.0	0.0	0.0
8024+00.00	8025+00.00	721.6	0.0	0.0	0.0	9.3	0.0	0.0	7.9	0.0	0.0	0.0	0.0	8808.7	0.0	41.6	0.0	-8800.9	0.0	-41.6	0.0	566.1	0.0	0.0	0.0
8025+00.00	8026+00.00	837.0	0.0	0.0	0.0	24.5	0.0	0.0	20.8	0.0	0.0	0.0	0.0	8591.3	0.0	49.8	0.0	-8570.4	0.0	-49.8	0.0	655.2	0.0	0.0	0.0
8026+00.00	8027+00.00	788.2	0.0	0.0	0.0	37.5	0.0	0.0	31.9	0.0	0.0	0.0	0.0	7281.4	0.0	51.7	0.0	-7249.5	0.0	-51.7	0.0	619.3	0.0	0.0	0.0
8027+00.00	8028+00.00	738.5	0.0	0.0	0.0	60.0	0.0	0.0	51.0	0.0	0.0	0.0	0.0	6023.1	0.0	51.7	0.0	-5972.1	0.0	-51.7	0.0	582.8	0.0	0.0	0.0
8028+00.00	8029+00.00	355.3	0.0	0.0	0.0	37.7	0.0	0.0	32.0	0.0	0.0	0.0	0.0	2677.3	0.0	25.9	0.0	-2645.3	0.0	-25.9	0.0	281.2	0.0	0.0	0.0
8029+00.00	8030+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8030+00.00	8031+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8031+00.00	8032+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8032+00.00	8033+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8033+00.00	8034+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8034+00.00	8035+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8035+00.00	8036+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
8036+00.00	END	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TOTALS		10225.8	0.0	2019.8	0.0	295.1	0.0	1397.6	0.0	250.8	0.0	1188.0	0.0	99541.4	0.0	3805.5	0.0	-99290.6	0.0	-2617.5	0.0	8061.0	0.0	1711.1	0.0

S:\00002_V.DGN - ATTORNEY\0327\03\01\CIVIL\08\AN_S\000021\08.DGN
 3-14-2008, 13:28:50
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59
 SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 3

SCALE: DRAWN BY: JB
 DATE: 03/14/08 CHECKED BY: ACL

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312-587-0900