F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	30
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

LOCATION STATION TO STATION		TOPSOIL EXCAVATION (CU YD)				EARTH EXCAVATION (ALL SUITABLE) (CU YD)				EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)				EMBANKMENT (CU YD)				EARTHWORK BALANCE (CU YD)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)			
IL ROUTE 59		PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3
7475+75.00	7476+50.00	0.0	787.3	0.0	0.0	0.0	26.5	0.0	0.0	0.0	22.5	0.0	0.0	10331.5	98.7	0.0	0.0	-10331.5	-76.2	0.0	0.0	0.0	663.0	0.0	0.0
7476+50.00	7477+00.00	0.0	468.1	0.0	0.0	0.0	16.2	0.0	0.0	0.0	13.7	0.0	0.0	6742.3	123.2	0.0	0.0	-6742.3	-109.5	0.0	0.0	0.0	359.7	0.0	0.0
7477+00.00	7477+50.00	0.0	505.6	0.0	0.0	0.0	6.4	0.0	0.0	0.0	5.4	0.0	0.0	6236.4	126.9	0.0	0.0	-6236.4	-121.5	0.0	0.0	0.0	406.4	0.0	0.0
7477+50.00	7478+00.00	0.0	501.8	0.0	0.0	0.0	25.5	0.0	0.0	0.0	21.7	0.0	0.0	5875.1	126.9	0.0	0.0	-5875.1	-105.2	0.0	0.0	0.0	401.3	0.0	0.0
7478+00.00	7478+50.00	0.0	481.6	0.0	0.0	0.0	20.1	0.0	0.0	0.0	17.1	0.0	0.0	5432.6	126.9	0.0	0.0	-5432.6	-109.8	0.0	0.0	0.0	390.3	0.0	0.0
7478+50.00	7479+00.00	0.0	457.5	0.0	0.0	0.0	12.5	0.0	0.0	0.0	10.7	0.0	0.0	4827.3	126.8	0.0	0.0	-4827.3	-116.2	0.0	0.0	0.0	374.1	0.0	0.0
7479+00.00	7479+50.00	0.0	439.8	0.0	0.0	0.0	24.7	0.0	0.0	0.0	21.0	0.0	0.0	4159.3	126.8	0.0	0.0	-4159.3	-105.8	0.0	0.0	0.0	360.1	0.0	0.0
7479+50.00	7480+00.00	0.0	415.2	0.0	0.0	0.0	28.4	0.0	0.0	0.0	24.1	0.0	0.0	3458.0	123.4	0.0	0.0	-3458.0	-99.3	0.0	0.0	0.0	342.9	0.0	0.0
7480+00.00	7480+50.00	0.0	389.1	0.0	0.0	0.0	34.2	0.0	0.0	0.0	29.1	0.0	0.0	2800.0	114.8	0.0	0.0	-2800.0	-85.7	0.0	0.0	0.0	324.0	0.0	0.0
7480+50.00	7481+00.00	0.0	361.1	0.0	0.0	0.0	32.8	0.0	0.0	0.0	27.8	0.0	0.0	2282.6	105.1	0.0	0.0	-2282.6	-77.2	0.0	0.0	0.0	303.2	0.0	0.0
7481+00.00	7481+50.00	0.0	172.0	0.0	135.7	0.0	13.8	0.0	13.8	0.0	11.7	0.0	11.7	1027.5	50.2	0.0	835.0	-1027.5	-38.5	0.0	-823.3	0.0	145.1	0.0	110.0
7481+50.00	7482+00.00	0.0	0.0	0.0	222.4	0.0	0.0	0.0	58.5	0.0	0.0	0.0	49.7	0.0	0.0	0.0	1436.6	0.0	0.0	0.0	-1386.9	0.0	0.0	0.0	173.1
7482+00.00	7482+50.00	0.0	0.0	0.0	141.9	0.0	0.0	0.0	110.1	0.0	0.0	0.0	93.5	0.0	0.0	0.0	991.5	0.0	0.0	0.0	-897.9	0.0	0.0	0.0	97.1
7482+50.00	7483+00.00	0.0	0.0	0.0	83.1	0.0	0.0	0.0	130.4	0.0	0.0	0.0	110.8	0.0	0.0	0.0	589.7	0.0	0.0	0.0	-478.9	0.0	0.0	0.0	42.7
7483+00.00	7483+50.00	0.0	0.0	0.0	80.2	0.0	0.0	0.0	127.7	0.0	0.0	0.0	108.5	0.0	0.0	0.0	427.6	0.0	0.0	0.0	-319.1	0.0	0.0	0.0	44.4
7483+50.00	7484+00.00	0.0	0.0	0.0	103.4	0.0	0.0	0.0	114.4	0.0	0.0	0.0	97.2	0.0	0.0	0.0	310.0	0.0	0.0	0.0	-212.7	0.0	0.0	0.0	76.3
7484+00.00	7484+50.00	0.0	0.0	0.0	104.8	0.0	0.0	0.0	103.0	0.0	0.0	0.0	87.5	0.0	0.0	0.0	180.4	0.0	0.0	0.0	-92.9	0.0	0.0	0.0	78.6
7484+50.00	7485+00.00	0.0	0.0	0.0	121.2	0.0	0.0	0.0	86.3	0.0	0.0	0.0	73.4	0.0	0.0	0.0	229.9	0.0	0.0	0.0	-156.5	0.0	0.0	0.0	90.6
7485+00.00	7485+50.00	0.0	0.0	0.0	141.8	0.0	0.0	0.0	55.9	0.0	0.0	0.0	47.5	0.0	0.0	0.0	283.9	0.0	0.0	0.0	-236.4	0.0	0.0	0.0	114.0
7485+50.00	7486+00.00	0.0	0.0	0.0	148.7	0.0	0.0	0.0	38.9	0.0	0.0	0.0	33.1	0.0	0.0	0.0	299.9	0.0	0.0	0.0	-266.8	0.0	0.0	0.0	122.6
7486+00.00	7486+50.00	0.0	0.0	0.0	140.1	0.0	4.5	0.0	39.4	0.0	3.8	0.0	33.5	0.0	0.0	0.0	251.4	0.0	3.8	0.0	-217.9	0.0	0.0	0.0	113.9
7486+50.00	7487+00.00	0.0	9.1	0.0	133.5	0.0	8.4	0.0	50.8	0.0	7.2	0.0	43.1	0.0	17.2	0.0	190.0	0.0	-10.0	0.0	-146.9	0.0	9.1	0.0	108.5
7487+00.00	7487+50.00	0.0	19.3	0.0	130.3	0.0	8.4	0.0	65.3	0.0	7.2	0.0	55.5	0.0	31.4	0.0	145.4	0.0	-24.3	0.0	-89.9	0.0	19.3	0.0	106.9
7487+50.00	7488+00.00	0.0	18.9	59.9	62.4	0.0	8.5	41.7	35.8	0.0	7.2	35.5	30.4	0.0	24.3	48.2	59.1	0.0	-17.1	-12.7	-28.7	0.0	18.9	49.9	51.1
7488+00.00	7488+50.00	0.0	13.5	126.1	0.0	0.0	8.3	88.0	0.0	0.0	7.1	74.8	0.0	0.0	15.1	96.9	0.0	0.0	-8.0	-22.1	0.0	0.0	13.5	104.8	0.0
7488+50.00	7489+00.00	0.0	4.9	132.1	0.0	0.0	7.7	97.2	0.0	0.0	6.6	82.7	0.0	0.0	5.2	83.3	0.0	0.0	1.4	-0.7	0.0	0.0	4.9	111.6	0.0
7489+00.00	7489+50.00	0.0	0.0	119.3	0.0	0.0	3.4	114.8	0.0	0.0	2.9	97.6	0.0	0.0	0.1	46.8	0.0	0.0	2.8	50.9	0.0	0.0	0.0	102.1	0.0
7489+50.00	7490+00.00	0.0	0.0	120.5	0.0	0.0	5.2	114.6	0.0	0.0	4.4	97.4	0.0	0.0	0.0	40.5	0.0	0.0	4.4	56.9	0.0	0.0	0.0	102.1	0.0
7490+00.00	7490+50.00	0.0	0.0	152.6	0.0	0.0	9.1	113.4	0.0	0.0	7.7	96.4	0.0	0.0	0.1	69.0	0.0	0.0	7.6	27.4	0.0	0.0	0.0	126.4	0.0
7490+50.00	7491+00.00	0.0	0.0	172.3	0.0	0.0	8.6	124.3	0.0	0.0	7.3	105.7	0.0	0.0	0.1	88.0	0.0	0.0	7.2	17.6	0.0	0.0	0.0	140.1	0.0
7491+00.00	7491+50.00	0.0	0.0	167.1	0.0	0.0	9.2	113.9	0.0	0.0	7.8	96.8	0.0	0.0	0.1	94.8	0.0	0.0	7.7	2.0	0.0	0.0	0.0	136.5	0.0
7491+50.00	7492+00.00	0.0	0.0	150.3	0.0	0.0	4.6	94.8	0.0	0.0	3.9	80.6	0.0	0.0	0.1	104.4	0.0	0.0	3.8	-23.9	0.0	0.0	0.0	124.7	0.0
7492+00.00	7492+50.00	0.0	0.0	112.9	0.0	0.0	0.0	93.3	0.0	0.0	0.0	79.3	0.0	0.0	0.0	82.2	0.0	0.0	0.0	-2.9	0.0	0.0	0.0	96.7	0.0
7492+50.00	7493+00.00	0.0	0.0	112.3	0.0	0.0	0.0	97.1	0.0	0.0	0.0	82.5	0.0	0.0	0.0	66.2	0.0	0.0	0.0	16.3	0.0	0.0	0.0	95.8	0.0
7493+00.00	7493+50.00	0.0	0.0	147.7	0.0	0.0	0.0	175.4	0.0	0.0	0.0	149.1	0.0	0.0	0.0	109.1	0.0	0.0	0.0	40.0	0.0	0.0	0.0	114.0	0.0
7493+50.00	7494+00.00	0.0	0.0	142.2	0.0	0.0	3.1	405.1	0.0	0.0	2.6	344.4	0.0	0.0	0.4	94.4	0.0	0.0	2.3	250.0	0.0	0.0	0.0	100.4	0.0
7494+00.00	7494+50.00	0.0	0.0	79.4	34.7	0.0	7.8	303.2	196.6	0.0	6.6	257.7	167.1	0.0	0.4	41.2	0.0	0.0	6.3	216.5	167.1	0.0	0.0	56.5	21.5
7494+50.00	7495+00.00	0.0	0.0	30.4	60.4	0.0	9.2	54.9	316.5	0.0	7.8	46.6	269.0	0.0	0.1	27.0	0.3	0.0	7.7	19.7	268.7	0.0	0.0	24.0	36.3
7495+00.00	7495+50.00	0.0	0.0	28.3	26.8	0.0	4.5	54.7	175.6	0.0	3.8	46.5	149.3	0.0	0.1	26.3	7.5	0.0	3.7	20.2	141.8	0.0	0.0	22.2	6.9
7495+50.00	7496+00.00	0.0	32.0	28.8	11.1	0.0	6.6	54.9	90.6	0.0	5.6	46.7	77.0	0.0	29.6	26.0	17.8	0.0	-24.0	20.7	59.3	0.0	32.0	22.3	-7.9
7496+00.00	7496+50.00	0.0	64.4	31.6	32.5	0.0	13.2	61.7	67.8	0.0	11.2	52.4	57.6	0.0	69.1	23.9	21.8	0.0	-57.9	28.5	35.8	0.0	64.4	24.3	11.0
7496+50.00	7497+00.00	0.0	32.4	23.9	46.0	0.0	6.6	68.2	74.9	0.0	5.6	58.0	63.7	0.0	39.5	24.4	24.7	0.0	-33.9	33.6	39.0	0.0	32.4	19.0	23.4
7497+00.00	7497+50.00	0.0	34.8	14.3	45.6	0.0	3.3	70.5	78.6	0.0	2.8	60.0	66.8	0.0	59.4	22.8	27.2	0.0	-56.6	37.2	39.6	0.0	34.8	11.7	23.4
7497+50.00	7498+00.00	0.0	67.3	18.1	53.0	0.0	6.7	71.2	94.3	0.0	5.7	60.5	80.2	0.0	125.9	27.7	24.8	0.0	-120.2	32.8	55.4	0.0	67.3	14.8	29.3
7498+00.00	7498+50.00	0.0	32.5	24.8	30.9	0.0	6.8	68.9	84.7	0.0	5.8	58.6	72.0	0.0	66.8	39.4	13.4	0.0	-61.0	19.2	58.6	0.0	32.5	20.4	18.3
7498+50.00	7499+00.00	0.0	0.0	29.4	0.0	0.0	7.3	67.3	58.0	0.0	6.2	57.2	49.3	0.0	0.4	49.8	6.2	0.0	5.8	7.5	43.1	0.0	0.0	24.0	0.0
7499+00.00	7499+50.00	0.0	38.8	31.8	28.5	0.0	8.2	68.5	105.7	0.0	7.0	58.2	89.9	0.0	84.5	61.9	11.0	0.0	-77.4	-3.7	78.9	0.0	38.8	25.1	18.3
7499+50.00	7500+00.00	0.0	45.7	25.3	28.5	0.0	8.0	69.9	95.7	0.0	6.8	59.4	81.3	0.0	93.0	60.2	19.3	0.0	-86.2	-0.8	62.0	0.0	45.7	18.8	18.3

CONTINUED ON
FOLLOWING SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 5

SCALE: DRAWN BY: JB
DATE: 03/14/08 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
325 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-616-0000

...\SCQ002_ILDOT_...\TTBOORR.DGN
3-14-2008,13:28:49 I:\DOCUMENT\d32790\DWG\DAN\SCQ002TUA.DGN
BONDHUJO
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63