| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 55 | * | WILL | 608 | 46 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

66400105 — TOTAL 10,712 FOOT

CHAIN LINK FENCE, 4'

| LOCATION | STA. | STA. | OFFSET LT / RT | LENGTH | SUBTOTALS FOOT |
|---|---|---|---|---|---|
| IL59 | 7477+00.00 | 7480+06.37 | LT | 308.41 | 308 |
| SEIL RD | 4012+72.68 | 4017+00.00 | LT | 463.69 | 464 |
| SEIL RD | 4017+00.00 | 4017+69.58 | LT | 76.86 | 77 |
| SEIL RD | 4012+49.07 | 4015+50.76 | RT | 303.99 | 304 |
| SB RAMP | 7001+36.25 | 7004+03.99 | RT | 273.15 | 273 |
| SB RAMP | 7003+79.14 | 7004+03.99 | RT | 96.88 | 97 |
| SB RAMP | 7003+79.14 | 7011+00.00 | RT | 722.11 | 722 |
| SB RAMP | 7011+00.00 | 7011+00.00 | RT | 20.02 | 20 |
| SB RAMP | 7011+00.00 | 7014+00.00 | RT | 312.22 | 312 |
| SB RAMP | 7014+00.00 | 7018+34.92 | RT | 451.24 | 451 |
| SB RAMP | 7018+34.92 | 7019+22.16 | RT | 91.99 | 92 |
| SB RAMP | 7019+22.16 | 7022+00.00 | RT | 270.21 | 270 |
| SB RAMP | 7022+00.00 | 7024+21.78 | RT | 209.95 | 210 |
| I-55 | 87+08.76 | 98+00.00 | RT | 1,091.24 | 1,091 |
| NB RAMP | 8003+24.96 | 8005+15.11 | RT | 190.15 | 190 |
| NB RAMP | 8005+15.11 | 8017+00.00 | RT | 1,392.27 | 1,392 |
| NB RAMP | 8017+00.00 | 8020+46.40 | RT | 367.75 | 368 |
| I-55 | 114+87.90 | 118+44.43 | RT | 363.22 | 363 |
| I-55 | 118+44.43 | 126+00.00 | RT | 743.78 | 744 |
| I-55 | 126+00.00 | 139+00.00 | RT | 1,279.16 | 1,279 |
| I-55 | 139+00.00 | 144+00.00 | RT | 492.06 | 492 |
| I-55 | 132+32.74 | 139+00.00 | LT | 718.81 | 719 |
| I-55 | 139+00.00 | 143+60.41 | LT | 472.77 | 473 |

66502300 — TOTAL 7,090 FOOT

WOVEN WIRE FENCE REMOVAL

| STATION | STATION | OFFSET | LENGTH | SUBTOTALS FOOT |
|---|---|---|---|---|
| 87+08.58 | 98+00.00 | RT | 1,091.42 | 1,091 |
| 98+00.00 | 111+00.00 | RT | 1,300.00 | 1,300 |
| 106+35.37 | 111+00.00 | LT | 529.50 | 530 |
| 111+00.00 | 126+00.00 | LT | 1,500.00 | 1,500 |
| 111+00.00 | 121+89.52 | RT | 1,089.52 | 1,090 |
| 126+00.00 | 130+00.00 | LT | 400.00 | 400 |
| 131+78.34 | 139+00.00 | LT | 741.61 | 742 |
| 139+00.00 | 143+63.78 | LT | 437.64 | 438 |

66600105 — TOTAL 37 EACH

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

| LOCATION | STATION | OFFSET | | SUBTOTALS EACH |
|---|---|---|---|---|
| EFR | 6502+52.83 | RT | 1 | 1 |
| EFR | 6505+18.92 | RT | 1 | 1 |
| EFR | 6509+51.46 | RT | 1 | 1 |
| EFR | 6510+91.56 | RT | 1 | 1 |
| EFR | 6518+59.87 | RT | 1 | 1 |
| EFR | 6523+21.29 | RT | 1 | 1 |
| EFR | 6526+30.23 | RT | 1 | 1 |
| WFR | 5508+18.75 | LT | 1 | 1 |
| WFR | 5516+18.94 | LT | 1 | 1 |
| WFR | 5519+20.83 | LT | 1 | 1 |
| WFR | 5523+19.50 | LT | 1 | 1 |
| WFR | 5529+70.84 | LT | 1 | 1 |
| WFR | 5529+70.84 | LT | 1 | 1 |
| WFR | 5530+50.84 | LT | 1 | 1 |
| WFR | 5537+79.73 | LT | 1 | 1 |
| WFR | 5539+54.73 | LT | 1 | 1 |
| WFR | 5539+54.73 | LT | 1 | 1 |
| WFR | 5544+21.18 | LT | 1 | 1 |
| SEIL | 4009+99.06 | RT | 1 | 1 |
| SEIL | 4009+09.23 | RT | 1 | 1 |
| WFR | 5525+05.90 | RT | 1 | 1 |
| WFR | 5530+40.83 | RT | 1 | 1 |
| WFR | 5532+96.89 | RT | 1 | 1 |
| WFR | 5532+96.89 | RT | 1 | 1 |
| WFR | 5536+27.47 | RT | 1 | 1 |
| WFR | 5536+27.47 | RT | 1 | 1 |
| WFR | 5537+79.73 | RT | 1 | 1 |
| WFR | 5544+19.73 | RT | 1 | 1 |
| SEIL | 4010+93.34 | RT | 1 | 1 |
| SEIL | 4011+81.70 | RT | 1 | 1 |
| SBRP | 7011+01.72 | RT | 1 | 1 |
| SBRP | 7011+00.00 | RT | 1 | 1 |
| SBRP | 7008+00.00 | RT | 1 | 1 |
| SBRP | 7005+00.00 | RT | 1 | 1 |
| SBRP | 7003+79.01 | RT | 1 | 1 |
| SEIL | 4015+59.21 | RT | 1 | 1 |
| SEIL | 4015+50.75 | RT | 1 | 1 |

70300210 — TOTAL 88 SQ FT

TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

| DIRECTION | LOCATION | STATION | ARROW SQ FT | TOTAL EACH | ONLY SQ FT | TOTAL EACH | TOTAL AREA SQ FT | MOT STAGE | SUBTOTALS SQ FT |
|---|---|---|---|---|---|---|---|---|---|
| NB | IL 59 | 7484+86 | 6 | 2 | 20.8 | 2 | 53.6 | WINTER | 53.6 |
| NB | IL 59 | 7491+18 | 6 | 1 | 20.8 | 1 | 26.8 | WINTER | 26.8 |
| | | | | PAVEMENT PARKING WEAR AND TEAR 10% | | | | | 8 |

70300220 — TOTAL 6,155 FOOT

TEMPORARY PAVEMENT MARKING - LINE 4"

| DIRECTION | LOCATION | STA. | STA. | CALC LENGTH FT | # OF LINES | COLOR | MOT STAGE | % OF TOTAL LENGTH | SUBTOTALS FOOT |
|---|---|---|---|---|---|---|---|---|---|
| NB | IL 59 | 2983+82.00 | 2987+00.00 | 318.00 | | WHITE | WINTER | | 318 |
| NB | IL 59 | 7487+00.00 | 7500+45.00 | 1,345.00 | | WHITE | WINTER | | 1,345 |
| NB | IL 59 | 7495+60.00 | 7497+54.00 | 194.00 | | WHITE | WINTER | | 194 |
| NB | IL 59 | 2983+82.00 | 2984+50.00 | 68.00 | 2.00 | YELLOW | WINTER | | 136 |
| NB | IL 59 | 2984+50.00 | 2987+00.00 | 250.00 | 2.00 | YELLOW | WINTER | | 500 |
| NB | IL 59 | 7487+00.00 | 7490+77.00 | 377.00 | 2.00 | YELLOW | WINTER | | 754 |
| SB | IL 59 | 2984+50.00 | 2987+00.00 | 250.00 | 2.00 | YELLOW | WINTER | | 500 |
| SB | IL 59 | 7487+00.00 | 7492+23.00 | 523.00 | 2.00 | YELLOW | WINTER | | 1,046 |
| SB | IL 59 | 7487+00.00 | 7492+23.00 | 523.00 | | WHITE | WINTER | 25% | 131 |
| SB | IL 59 | 7482+50.00 | 7487+00.00 | 555 | | WHITE | WINTER | | 555 |
| SB | IL 59 | 7482+83.00 | 7483+85.00 | 116.36 | | WHITE | WINTER | | 116 |
| | | | PAVEMENT MARKING WEAR AND TEAR 10% | | | | | | 560 |

70300240 — TOTAL 484 FOOT

TEMPORARY PAVEMENT MARKING - LINE 6"

| DIRECTION | LOCATION | STA. | STA. | CALC LENGTH | LINE TYPE | # OF LINES | COLOR | MOT STAGE | SUBTOTALS FOOT |
|---|---|---|---|---|---|---|---|---|---|
| SB | IL 59 | 2983+83 | 2987+00 | 317 | SOLID | 1 | WHITE | WINTER | 317 |
| SB | IL 59 | 7491+00 | 7492+23 | 123 | SOLID | 1 | WHITE | WINTER | 123 |
| | | | PAVEMENT MARKING WEAR AND TEAR 10% | | | | | | 44 |

70300260 — TOTAL 384 FOOT

TEMPORARY PAVEMENT MARKING - LINE 12"

| DIRECTION | LOCATION | STA. | STA. | MEASURED LENGTH | # OF LINES | COLOR | MOT STAGE | SUBTOTALS FOOT |
|---|---|---|---|---|---|---|---|---|
| NB | IL 59 | 748500 | 749000 | 99.5 | 9 | WHITE | WINTER | 99.5 |
| NB | IL 59 | 748700 | 749700 | 249.7 | 15 | WHITE | WINTER | 249.7 |
| | | | PAVEMENT MARKING WEAR AND TEAR 10% | | | | | 35.0 |

70300280 — TOTAL 13 FOOT

TEMPORARY PAVEMENT MARKING - LINE 24"

| LOCATION | STATION | MEASURED LENGTH FT | MOT STAGE | SUBTOTALS FOOT |
|---|---|---|---|---|
| IL 59 | 2983+83 | 13 | WINTER | 13 |

X0325842 — TOTAL 318 SQ FT

WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS

| LOCATION | STATION | ARROW SQ FT | TOTAL EACH | ONLY SQ FT | TOTAL EACH | TOTAL AREA SQ FT | MOT STAGE | SUBTOTALS SQ FT |
|---|---|---|---|---|---|---|---|---|
| IL 59 | 7528+00 | 6 | 3 | 20.8 | 3 | 80 | PRESTAGE A | 80.4 |
| IL 59 | 7530+68 | 6 | 1 | 20.8 | 1 | 27 | PRESTAGE A | 26.8 |
| IL 59 | 7527+06 | 6 | 1 | 20.8 | 1 | 27 | STAGE 2A | 26.8 |
| IL 59 | 7528+35 | 6 | 1 | 20.8 | 1 | 27 | STAGE 2A | 26.8 |
| IL 59 | 7484+96 | 6 | 2 | 20.8 | 2 | 54 | STAGE 2B | 53.6 |
| IL 59 | 7476+66 | 6 | 1 | 20.8 | 1 | 27 | STAGE 3B | 26.8 |
| IL 59 | 4016+67 | 6 | 1 | 20.8 | 2 | 48 | STAGE 3B | 47.6 |
| | PAVEMENT MARKING WEAR AND TEAR 10% | | | | | | | 29.0 |

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 21

SCALE:
DRAWN BY: JB
DATE: 03/14/08
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS•ARCHITECTS•PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0300

..\SC0001V7E.DGN ..\TTBOORN.DGN
4-14-2008,10:48:16 T:\DOCUMENT\1932790\CIVIL\DGN\SC0001V7S.DGN
LEEAC
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63