

PROPOSED SIGN SCHEDULE

SIGN NO.	ROAD	STATION	OFFSET	SIGN DESCRIPTION	SIGN TYPE/I.D.	PANEL TYPE	PANEL SIZE (SF)	HEIGHT	WIDTH	TELESCOPING STEEL SIGN SUPPORT (FT)	BASE TEL STL SIN SUPP	SHEET NO.	REMARKS
S-1A	I-55 NB	33+80	RT	EXIT 251, IL 59, SHOREWOOD, PLAINFIELD, 1 MILE	ID # 1S099I055R249.90LT	3	188.50	14.50	13.00	N/A	N/A	271	X
S-2	I-55 NB	53+45	RT	INTERSTATE 55, NORTH, CHICAGO	ID #1B099I055R250.28LT	3	92.00	8.00	11.50	N/A	N/A	271	
S-3	I-55 NB	63+00	RT	EXIT 251, IL 59, SHOREWOOD, PLAINFIELD, 1/2 MILE	ID # 1C099I055R250.46	3	188.50	14.50	13.00	N/A	N/A	271	
S-4	IL 59 NB	7498+00	RT	CENTER LANE LEFT TURN ONLY	R3-9b	1	6.00	3.00	2.00	15.00	1	276	
S-5	IL 59 NB	7518+75	LT	CENTER LANE LEFT TURN ONLY	R3-9b	1	6.00	3.00	2.00	15.00	1	277	
S-6	NOT USED												
S-7	I-55 NB	79+00	RT	EXIT 251, IL 59, SHOREWOOD, PLAINFIELD, RIGHT LANE	ID # 1C099I055R250.76	3	188.50	14.50	13.00	N/A	N/A	272	
S-11	I-55 SB	91+95	LT	SPEED LIMIT 65, MINIMUM 45	R2-4g	3	32.00	8.00	4.00	20.00	1	272	
S-12	I-55 SB	93+96	LT	SOUTH	M3-3	1	3.13	1.25	2.50	N/A	N/A	272	
S-13	I-55 SB	93+96	LT	INTERSTATE 55	M1-1	1	9.00	3.00	3.00	15.00	1	272	
S-14	I-55 SB	88+00	LT	EXIT 250B, WEST IOWA, RIGHT LANE	ID # 1C099I055L250.93	3	132.00	12.00	11.00	N/A	N/A	272	
S-15	EAST FRONT. RD	6500+50	RT	RIGHT CURVE	W1-2	1	6.25	2.50	2.50	14.50	1	272	
S-16	EAST FRONT. RD	6508+00	RT	LEFT CURVE	W1-2	1	6.25	2.50	2.50	14.50	1	273	
S-17	IL 59 NB EXIT RAMP	8011+00	RT	LEFT CURVE	W1-2	1	9.00	3.00	3.00	15.00	1	273	
S-18	EAST FRONT. RD	6520+50	RT	RIGHT CURVE	W1-2	1	6.25	2.50	2.50	14.50	1	274	
S-24	I-55 NB	92+32	RT	EXIT 251, IL 59, SHOREWOOD, PLAINFIELD	ID # 1S099I055R251.02RT	3	224.75	14.50	15.50	N/A	N/A	272	
S-25	I-55 NB	92+32	RT	RAMP, 40 M.P.H.	W13-3	2	20.00	5.00	4.00	N/A	N/A	272	
S-26	NOT USED												
S-28	I-55 NB	100+00	RT	EXIT 251 ARROW TO THE RIGHT	E5-1a	3	37.50	5.00	7.50	34.00	2	273	
S-32	I-55 SB	105+18	LT	ADDED LANE	W4-3	2	16.00	4.00	4.00	16.00	1	273	
S-36	IL 59 SB	7498+00	RT	CENTER LANE LEFT TURN ONLY ENDS	CUSTOM	1	6.00	3.00	2.00	15.00	1	276	
S-46	NOT USED						0.00			12.00	1	279	
S-47	NB IL 59 EXIT RAMP	8034+84	RT	WRONG WAY	R5-1a	1	6.00	2.00	3.00	14.00	1	275	
S-48	SB IL 59 ENTR. RAMP	7002+40	RT	LANE ENDS	W4-2	1	9.00	3.00	3.00	15.00	1	275	
S-49	NOT USED												
S-52	IL 59 EXIT RAMP	8034+84	RT	DIRECTIONAL ARROW	M6-3	1	2.19	1.25	1.75	N/A	N/A	275	
S-53	IL 59 EXIT RAMP	8034+84	RT	ILLINOIS 59	M1-5	1	9.00	3.00	3.00	N/A	N/A	275	
S-54	IL 59 EXIT RAMP	8034+84	RT	NORTH	M3-1	1	3.13	1.25	2.50	N/A	N/A	275	
S-55	IL 59 MEDIAN	7475+35	RT	LEFT ONLY	M3-5	1	2.00	1.00	2.00	13.00	1	275	
S-56	IL 59 EXIT RAMP	8032+00	RT	FRONTAGE ROAD ENTRANCE	CUSTOM	1	7.50	3.00	2.50	15.00	1	279	
S-58	IL 59 NB	7476+19	RT	TWO DIRECTIONS ARROW	W1-7	1	8.00	2.00	4.00	14.00	1	275	
S-60	IL 59 NB	7517+38	RT	CENTER LANE LEFT TURN ONLY ENDS	CUSTOM	1	6.00	2.00	3.00	14.00	1	277	
S-61	IL 59 MEDIAN	7475+45	LT	KEEP RIGHT SYMBOL	R4-7	1	5.00	2.50	2.00	14.50	1	275	
S-62	IL 59 MEDIAN	7476+35	LT	KEEP RIGHT SYMBOL	R4-7	1	5.00	2.50	2.00	14.50	1	275	
S-64	IL 59 NB	7477+11	RT	ILLINOIS 59	M1-5	1	9.00	3.00	3.00	15.00	1	275	
S-65	IL 59 NB	7477+11	RT	NORTH	M3-1	1	2.00	1.00	2.00	N/A	N/A	275	
S-66	IL 59 NB	7478+41	RT	SPEED LIMIT 45	R2-1	1	5.00	2.50	2.00	14.50	1	275	
S-67	IL 59 SB	7477+75	RT	SOUTH	M3-3	1	2.00	1.00	2.00	N/A	N/A	275	
S-68	IL 59 SB	7477+75	RT	INTERSTATE 55	M1-1	1	9.00	3.00	3.00	15.00	1	275	
S-69	IL 59 SB	7477+75	RT	DIRECTIONAL ARROW	M6-3	1	2.19	1.25	1.75	N/A	N/A	275	
S-70	IL 59 SB	7477+75	RT	FRONTAGE ROAD ENTRANCE	CUSTOM	1	7.50	3.00	2.50	15.00	1	275	
S-80	IL 59 MEDIAN	7483+44	LT	LEFT ONLY	R3-5	1	7.50	3.00	2.50	15.00	1	275	
S-81	IL 59 MEDIAN	7483+56	LT	KEEP RIGHT SYMBOL	R4-7	1	5.00	2.50	2.00	14.50	1	275	
S-82A	IL 59 SB	AT STOP BAR	LT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	275	
S-84	IL 59 MEDIAN	7484+42	LT	KEEP RIGHT SYMBOL	R4-7	1	5.00	2.50	2.00	14.50	1	275	
S-86	IL 59 EXIT RAMP	8019+37	LT	TERMINAL MARKER	W5-52L	1	3.00	3.00	1.00	15.00	1	274	
S-88	IL 59 EXIT RAMP	8019+46	RT	TERMINAL MARKER	W5-52R	1	3.00	3.00	1.00	15.00	1	274	
S-89A	IL 59 SB	AT STOP BAR	RT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	276	
S-90	IL 59 MEDIAN	7486+10	LT	KEEP RIGHT SYMBOL	R4-7	1	5.00	2.50	2.00	14.50	1	276	
S-91A	IL 59 SB	2988+87	LT	JUNCTION MARKER	M2-1	1	2.19	1.25	1.75	N/A	N/A	276	
S-92A	IL 59 SB	2988+87	LT	SOUTH	M3-3	1	2.00	1.00	2.00	N/A	N/A	276	
S-93A	IL 59 SB	2988+87	LT	INTERSTATE 55	M1-1	1	9.00	3.00	3.00	15.00	1	276	
S-95A	IL 59 SB	2991+27	LT	SPEED LIMIT 45	R2-1	1	5.00	2.50	2.00	14.50	1	276	
S-96A	AMENDODGE DR.	AT STOP BAR	LT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	276	
S-111A	IL 59 SB	2999+52	LT	SPEED LIMIT 45	R2-1	1	5.00	2.50	2.00	14.50	1	277	
S-112A	OAKWOOD DR.	AT STOP BAR	LT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	277	
S-114A	SHOREWOOD LN.	AT STOP BAR	LT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	277	
S-115	IL 59 SB	7512+77	LT	SPEED LIMIT 35	R2-1	1	5.00	2.50	2.00	14.50	1	277	
S-116A	MYERS ST.	AT STOP BAR	LT	STOP SIGN	R1-1	1	6.25	2.50	2.50	14.50	1	277	


\S:\COO\20\DOCN...ATTBDRK\DOCN...SC0002\ZJDRG
 3-12-2008 16:59:05 T:\DOCUMENT\632750\CVL\DOCN\SC0002\ZJDRG
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59
 SECTION: (26, 26HB-1&114) R-2

SIGN INVENTORY 4

SCALE: DRAWN BY: JB
 DATE: 03/14/08 CHECKED BY: ACL



TENG & ASSOCIATES, INC.
 ENGINEERS ARCHITECTS PLANNERS
 565 N. MICHIGAN AVE. CHICAGO, IL 60611
 TEL: 312.467.8900 FAX: 312.467.8901