

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2943	2005-078 RS	COOK	31	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38				
40600300	AGGREGATE (PRIME COAT)	TON	190	190				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	29	29				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1210	1210				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	361	361				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7984	7984				
42001300	PROTECTIVE COAT	SQ YD	588	588				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	95045	95045				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1765	1765				
44002223	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 3/4"	SQ YD	1120	1120				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1080	1080				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	40	40				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	40	40				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	153	153				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	106	106				
60404940	FRAMES AND GRATES, TYPE 23	EACH	10	10				
60404950	FRAMES AND GRATES, TYPE 24	EACH	35	35				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	20	20				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	20	20				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
<del>70100450</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701201</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11	11				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18762	18762				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	692	692				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45530	45530				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2534	2534				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1680	1680				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	681	681				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	692	692				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45530	45530				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2534	2534				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1680	1680				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	681	681				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1408	1408				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1138	1138				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2747	2747				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3742	3742				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
* 20076600	TRAINERS	HOOR	3000	3000				

3/21/2008 2:00 PM C:\PROJECTS\60A87\60A87.DWG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
Rev.

© Y080  
\*SPECIALTY ITEMS