

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT			ROADWAY 1000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	375		375
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	80		80
40600300	AGGREGATE (PRIME COAT)	TON	380		380
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100		100
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10		10
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	250		250
40600990	TEMPORARY RAMP	SQ YD	540		540
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	900		900
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,020		8,020
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	92,600		92,600
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300		300
44002212	HOT-MIX ASPHALT SURFACE REMOVAL OVER PATCHES, 3"	SQ YD	5,200		5,200
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	630		630
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	230		230
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	3,660		3,660
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,900		1,900
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10		10
64200105	SHOULDER RUMBLE STRIP	FOOT	1,110		1,110
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,000		5,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,530		1,530
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	282,000		282,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,300		6,300
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	570		570
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	15,300		15,300
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	720		720
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	38,600		38,600
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510		510
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	94,000		94,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,100		2,100
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	190		190
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	5,100		5,100

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT			ROADWAY 1000-2A
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	240		240
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	570		570
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	530		530
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52		52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,760		3,760

@ 20076600 TRAINEES

Hour 1500 1500

FILE NAME = N:\PROJ\3329\3329\_34\Design\ProposedPlan\3329\_34-03-Quantities.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mbelog	DESIGNED - WBL	REVISED -
	DRAWN - WBL	REVISED -
PLOT SCALE = 1.0000' / IN.	CHECKED - MJL	REVISED -
PLOT DATE = 4/8/2008	DATE - 4/7/2008	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 72 FRENCH ROAD TO US ROUTE 20 SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 557	SECTION Y-RS-2	COUNTY KANE	TOTAL SHEETS 23	SHEET NO. 3
CONTRACT NO. 60E43				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				