

80% FED 20% STATE
Y03HF

CONTRACT NO. 64C89				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	24TS	JO DAVIESS	11	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Summary of Quantities for US 20 @ IL 78			
PAY CODE	ITEM	UNIT	TOTAL
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
* 72000100	SIGN PANEL TYPE I	50 FT	30
78300100	PAVEMENT MARKING REMOVAL	50 FT	1628
80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/2" NO. 10	FOOT	802
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2
82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1293
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	623
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	49
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT	EACH	1
87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT	EACH	1
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	27.5
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	31.25
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7
88040150	SIGNAL HEAD, POLYCARBONATE, LED 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	9
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	370
X0324887	CONDUIT INSTALLED, 2 1/2" ^{DIA.} NON-METALLIC	FOOT	54
X0324888	CONDUIT INSTALLED, 4" ^{DIA.} NON-METALLIC	FOOT	235
X0325335	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	43
* X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	50 FT	171
* X7800510	POLYUREA PAVEMENT MARKING SPECIAL- LINE 4"	FOOT	1230
* X7800540	POLYUREA PAVEMENT MARKING SPECIAL- LINE 8"	FOOT	857
* X7800550	POLYUREA PAVEMENT MARKING SPECIAL- LINE 12"	FOOT	248
* X7800580	POLYUREA PAVEMENT MARKING SPECIAL- LINE 24"	FOOT	116
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1
XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	1

* SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____

PLOT DATE: 11/12/08 10:29:36 AM
 FILE NAME: \\s010001\proj\64C89 US 20 IL 78 SIGNALS\64C89 US 20 IL 78 SIGNALS.dgn
 PLOT SCALE: 1/4" = 1'-0"
 USER NAME: JHJ