

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(1R-B)I-3	KANKAKEE	20	3

SUMMARY OF QUANTITIES

CONSTRUCTION CODE SFTY-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE	
				SN 046-0039 (EB) PPS# 0-00859-3003	SN 046-0040 (WB) PPS# 0-00859-3004
50102400	CONCRETE REMOVAL	CU YD	17	8.5	8.5
50157300	PROTECTIVE SHIELD	SQ YD	1334	667	667
50300225	CONCRETE STRUCTURES	CU YD	7.4	3.7	3.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.6	4.8	4.8
50300260	BRIDGE DECK GROOVING	SQ YD	2080	1040	1040
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3200	1600	1600
50800515	BAR SPLICERS	EACH	64	32	32
52000110	PREFORMED JOINT STRIP SEAL	FOOT	148	74	74
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	9	4.5	4.5
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	2	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	15	15

Mar 27, 2008 - 07:40:00 AM
 c:\pco\lect\5\ema\1\09\cm303\der\c11s.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP 330 (IL 17) SECTION (1R-B)I-3
 KANKAKEE COUNTY
 STA. 228+10.95
 SN 046-0039 (EB) & SN 046-0040 (WB)