

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(1R-B)I-3	KANKAKEE	20	6

SCHEDULE				
LOCATION	BRIDGE DECK HYDRO SCARIFICATION	BRIDGE DECK LATEX CONCRETE OVERLAY	BRIDGE DECK GROOVING	PROTECTIVE SHIELD
	SQ YD	SQ YD	SQ YD	SQ YD
SN 046-0039 (EB)				
STAGE I	594	557	520	400
STAGE II	520	557	520	267
SUBTOTAL	1114	1114	1040	667
SN 046-0040 (WB)				
STAGE I	594	557	520	400
STAGE II	520	557	520	267
SUBTOTAL	1114	1114	1040	667
TOTAL	2228	2228	2080	1334

SCHEDULE				
LOCATION	CONCRETE REMOVAL	CONCRETE SUPERSTRUCTURE	CONCRETE STRUCTURE	PREFORMED JOINT STRIP SEAL,
	CU YD	CU YD	CU YD	FEET
SN 046-0039 (EB)				
STAGE I	4.5	2.4	1.8	37
STAGE II	4.0	2.4	1.8	37
SUBTOTAL	8.5	4.8	3.7	74
SN 046-0040 (WB)				
STAGE I	4.5	2.4	1.8	37
STAGE II	4.0	2.4	1.8	37
SUBTOTAL	8.5	4.8	3.7	74
TOTAL	17.0	9.6	7.4	148

SCHEDULE	
LOCATION	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THEN 5")
	SQ FT
SN 046-0039 (EB)	
EAST ABUT.	48
WEST ABUT.	46
N. CURB	251
S. CURB	251
SUBTOTAL	596
SN 046-0040 (WB)	
EAST ABUT.	39
WEST ABUT.	39
N. CURB	251
S. CURB	251
SUBTOTAL	580
TOTAL	1176

SCHEDULE						
LOCATION	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE 1 4"	POLYUREA PAVEMENT MARKING TYPE 1 6"	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
	SQ FT	FEET	SQ FT	FEET	FEET	EACH
SN 046-0039 (EB)						
STAGE I	529	2026	669	1328.0		
STAGE II	529	2026	669	1328	518	8
SUBTOTAL	1058	4052	1338	2656	518	8
SN 046-0040 (WB)						
STAGE I	529	2026	669	1328		
STAGE II	529	2026	669	1328	518	8
SUBTOTAL	1058	4052	1338	2656	518	8
TOTAL	2116	8104	2676	5312	1036	16

SCHEDULE		
LOCATION	CONTROLLED LOW-STRENGTH MATERIAL	JOINT SEALER
	CU YD	FOOT
WEST ABUTMENT	5	260
EAST ABUTMENT	4	210
TOTAL	9	470

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
 FAP 330 (IL 17) SECTION (1R-B)I-3
 KANKAKEE COUNTY
 STA. 228+10.95
 SN 046-0039 (EB) & SN 046-0040 (WB)

Mar 05, 2008 - 08:38:17 AM
 c:\p\proj\sect\sl\cma\in09\cm303\def\all.s.dgn