

90% FED. 10% ST.  
SFTY-2A

SUMMARY OF QUANTITIES					
Code No.	Item	Unit	Total	LASALLE	KENDALL
20200500	EARTH EXCAVATION (WIDENING)	CU YD	7981	2542	5439
25000210	SEEDING, CLASS 2A	ACRE	10.4	2.7	7.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	936	243	693
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	936	243	693
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	936	243	693
25100115	MULCH, METHOD 2	ACRE	10.4	2.7	7.7
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	694	694	0
40600300	AGGREGATE (PRIME COAT)	TON	18	18	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	728	728	0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8668	8668	0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	73875	21770	52105
64200105	SHOULDER RUMBLE STRIP	FOOT	143288	39277	104011
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	2
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	5	10
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	0	156
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	186990	50722	136268
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	23535	9938	13597
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	1300	0	1300
# 20076600	TRAINEES	HOWE	1,000	1,000	

SPECIALTY ITEMS  
#Y080