

LASALLE COUNTY EARTHWORK						
STA	TO	STA	EARTH EX	EARTH EX	EMBANK	EARTHWORK BAL
			(WIDENING)	ADJ FOR SHRINKAGE		WASTE (+) OR SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
668+58	TO	675+00	79	59	9	50
675+00	TO	680+00	65	49	8	41
680+00	TO	685+00	68	51	7	44
685+00	TO	690+00	58	44	8	36
690+00	TO	695+00	58	44	6	38
695+00	TO	700+00	54	41	7	34
700+00	TO	705+00	60	45	7	38
705+00	TO	710+00	69	52	3	49
710+00	TO	715+00	63	47	6	41
715+00	TO	720+00	70	53	5	48
720+00	TO	725+00	70	53	4	49
725+00	TO	730+00	57	43	8	35
730+00	TO	735+00	52	39	9	30
735+00	TO	740+00	51	38	10	28
740+00	TO	745+00	60	45	9	36
745+00	TO	750+00	67	50	5	45
750+00	TO	755+00	69	52	7	45
755+00	TO	760+00	73	55	9	46
760+00	TO	765+00	73	55	6	49
765+00	TO	770+00	67	50	3	47
770+00	TO	775+00	67	50	4	46
775+00	TO	780+00	63	47	4	43
780+00	TO	785+00	55	41	8	33
785+00	TO	790+00	51	38	11	27
790+00	TO	795+00	57	43	9	34
795+00	TO	800+00	68	51	5	46
800+00	TO	805+00	69	52	3	49
805+00	TO	810+00	70	53	1	52
810+00	TO	815+00	75	56	1	55
815+00	TO	820+00	71	53	2	51
820+00	TO	825+00	62	47	5	42
825+00	TO	830+00	61	46	8	38
830+00	TO	835+00	66	50	7	43
835+00	TO	840+00	66	50	5	45
840+00	TO	845+00	63	47	5	42
845+00	TO	850+00	72	54	5	49
850+00	TO	855+00	72	54	5	49
855+00	TO	860+00	67	50	3	47
860+00	TO	865+00	63	47	5	42
865+00	TO	867+29	21	16	7	9
TOTAL			2542	1910	239	1671

25% SHRINKAGE FACTOR USED.

KENDALL COUNTY EARTHWORK						
STA	TO	STA	EARTH EX	EARTH EX	EMBANK	EARTHWORK BAL
			(WIDENING)	ADJ FOR SHRINKAGE		WASTE (+) OR SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
867+29	TO	870+00	26	20	8	12
870+00	TO	875+00	61	46	12	34
875+00	TO	880+00	68	51	0	51
880+00	TO	885+00	59	44	1	43
885+00	TO	890+00	55	41	12	29
890+00	TO	895+00	46	35	17	18
895+00	TO	900+00	45	34	16	18
900+00	TO	905+00	48	36	18	18
905+00	TO	910+00	60	45	10	35
910+00	TO	915+00	65	49	8	41
915+00	TO	920+00	54	41	25	16
920+00	TO	925+00	55	41	30	11
925+00	TO	930+00	65	49	11	38
930+00	TO	935+00	63	47	6	41
935+00	TO	940+00	62	47	6	41
940+00	TO	945+00	50	38	18	20
945+00	TO	950+00	42	32	25	7
950+00	TO	955+00	46	35	34	1
955+00	TO	960+00	47	35	31	4
960+00	TO	965+00	45	34	22	12
965+00	TO	970+00	42	32	30	2
970+00	TO	975+00	41	31	32	-1
975+00	TO	980+00	45	34	22	12
980+00	TO	985+00	45	34	21	13
985+00	TO	990+00	40	30	30	0
990+00	TO	995+00	39	29	32	-3
995+00	TO	1000+00	40	30	32	-2
1000+00	TO	1005+00	46	35	23	12
1005+00	TO	1010+00	42	32	25	7
1010+00	TO	1015+00	45	34	23	11
1015+00	TO	1020+00	54	41	14	27
1020+00	TO	1025+00	50	38	19	19
1025+00	TO	1030+00	51	38	20	18
1030+00	TO	1035+00	53	40	20	20
1035+00	TO	1040+00	51	38	21	17
1040+00	TO	1045+00	51	38	15	23
1045+00	TO	1050+00	54	41	13	28
1050+00	TO	1055+00	51	38	15	23
1055+00	TO	1060+00	50	38	14	24
1060+00	TO	1065+00	48	36	14	22
1065+00	TO	1070+00	44	33	16	17
1070+00	TO	1075+00	46	35	17	18
1075+00	TO	1080+00	49	37	16	21
1080+00	TO	1085+00	51	38	18	20
1085+00	TO	1090+00	50	38	19	19
1090+00	TO	1095+00	51	38	16	22
1095+00	TO	1100+00	54	41	13	28
1100+00	TO	1105+00	50	38	16	22
1105+00	TO	1110+00	22	17	11	6
1110+00	TO	1115+00	23	17	13	4
1115+00	TO	1120+00	49	37	22	15
1120+00	TO	1125+00	53	40	17	23
1125+00	TO	1130+00	55	41	16	25
1130+00	TO	1135+00	56	42	17	25
1135+00	TO	1140+00	53	40	22	18
1140+00	TO	1145+00	53	40	23	17
1145+00	TO	1150+00	46	35	23	12
1150+00	TO	1155+00	47	35	24	11
1155+00	TO	1160+00	58	44	13	31
1160+00	TO	1165+00	56	42	16	26
1165+00	TO	1170+00	52	39	19	20
1170+00	TO	1175+00	50	38	17	21
1175+00	TO	1180+00	50	38	14	24
1180+00	TO	1185+00	55	41	18	23
1185+00	TO	1190+00	48	36	30	6
1190+00	TO	1195+00	42	32	27	5
1195+00	TO	1200+00	50	38	14	24

KENDALL COUNTY EARTHWORK (CONT.)						
STA	TO	STA	EARTH EX	EARTH EX	EMBANK	EARTHWORK BAL
			(WIDENING)	ADJ FOR SHRINKAGE		WASTE (+) OR SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
1200+00	TO	1205+00	61	46	5	41
1205+00	TO	1210+00	64	48	7	41
1210+00	TO	1215+00	54	41	18	23
1215+00	TO	1220+00	42	32	27	5
1220+00	TO	1225+00	40	30	35	-5
1225+00	TO	1230+00	46	35	35	0
1230+00	TO	1235+00	48	36	20	16
1235+00	TO	1240+00	43	32	21	11
1240+00	TO	1245+00	43	32	27	5
1245+00	TO	1250+00	42	32	26	6
1250+00	TO	1255+00	37	28	35	-7
1255+00	TO	1260+00	39	29	36	-7
1260+00	TO	1265+00	44	33	20	13
1265+00	TO	1270+00	46	35	14	21
1270+00	TO	1275+00	44	33	28	5
1275+00	TO	1280+00	36	27	44	-17
1280+00	TO	1285+00	44	33	34	-1
1285+00	TO	1290+00	53	40	17	23
1290+00	TO	1295+00	47	35	24	11
1295+00	TO	1300+00	52	39	16	23
1300+00	TO	1305+00	56	42	11	31
1305+00	TO	1310+00	47	35	24	11
1310+00	TO	1315+00	52	39	23	16
1315+00	TO	1320+00	47	35	31	4
1320+00	TO	1325+00	40	30	30	0
1325+00	TO	1330+00	22	17	8	9
1330+00	TO	1335+00	19	14	17	-3
1335+00	TO	1340+00	60	45	17	28
1340+00	TO	1345+00	58	44	19	25
1345+00	TO	1350+00	39	29	19	10
1350+00	TO	1355+00	34	26	24	2
1355+00	TO	1360+00	35	26	36	-10
1360+00	TO	1365+00	48	36	22	14
1365+00	TO	1370+00	54	41	26	15
1370+00	TO	1375+00	57	43	21	22
1375+00	TO	1380+00	72	54	11	43
1380+00	TO	1385+00	74	56	17	39
1385+00	TO	1390+00	69	52	13	39
1390+00	TO	1395+00	71	53	4	49
1395+00	TO	1400+00	71	53	5	48
1400+00	TO	1405+00	68	51	14	37
1405+00	TO	1410+00	70	53	13	40
1410+00	TO	1412+52	38	29	4	25
TOTAL			5439	4096	2130	1966