

PATCHING SCHEDULE - WESTBOUND LANES

| LOCATION M.P. | PASSING LANE | | | | | | | DRIVING LANE | | | | | | |
|----------------------|--------------------------------|-------------------|------------------|---------------|-------------|----------------|-------------|------------------|-------------------|------------------|---------------|-------------|----------------|-------------|
| | CLASS B PATCHING | | | DOWEL BARS | SAW CUTS | PVMT FABRIC | TIE BARS | CLASS B PATCHING | | | DOWEL BARS | SAW CUTS | PVMT FABRIC | TIE BARS |
| | TYPE II SQ YD | TYPE III SQ YD | TYPE IV SQ YD | | | | | TYPE II SQ YD | TYPE III SQ YD | TYPE IV SQ YD | | | | |
| 70.15 | IL ROUTE 89 | | | | | | | | | | | | | |
| 70.05 | 8 | | | 20 | 48 | 8 | | | | | | | | |
| 69.95 | 11 | | | 20 | 52 | 11 | | 11 | | | 20 | 52 | 11 | |
| 69.65 | 13 | | | 20 | 56 | 13 | | | | | | | | |
| 68.90 | 8 | | | 20 | 48 | 8 | | | | | | | | |
| 68.50 | | | | | | | | 8 | | | 20 | 48 | 8 | |
| 68.30 | | | | | | | | | | 67 | 20 | 136 | 133 | 25 |
| 67.90 | | | | | | | | 13 | | | 20 | 56 | 13 | |
| 67.89 | | | | | | | | 8 | | | 20 | 48 | 8 | |
| 67.80 | | | | | | | | 8 | | | 20 | 48 | 8 | |
| 65.70 | | | 40 | 20 | 96 | 80 | 15 | | | 40 | 20 | 96 | 80 | 15 |
| 65.60 | | | | | | | | 13 | | | 20 | 56 | 13 | |
| 65.50 | | | | | | | | | | 67 | 20 | 136 | 133 | 25 |
| 64.95 | | | 27 | 20 | 76 | 53 | 10 | | | | | | | |
| 64.90 | | | | | | | | 13 | | | 20 | 56 | 13 | |
| 64.89 | | 20 | | 20 | 66 | 40 | | | | | | | | |
| 64.00 | CH 19 (2750E ROAD) SN 006-0132 | | | | | | | | | | | | | |
| 63.98 | | | | | | | | | | 53 | 20 | 116 | 53 | 20 |
| WB TOTALS | 40 | 20 | 67 | 140 | 442 | 213 | 25 | 74 | | 227 | 220 | 848 | 473 | 85 |

| | | | |
|--|-------------------------|---------------------|-----------|
| FILE NAME = c:\projects\cmain09\cm308\details.dgn | USER NAME = carpenterdj | DESIGNED <i>RLW</i> | REVISED - |
| | | DRAWN <i>RLW</i> | REVISED - |
| PLOT SCALE = 1/8" = 1' / IN. | CHECKED - | REVISED - | REVISED - |
| PLOT DATE = Mar 08, 2008 - 08:53:14 AM | DATE - | REVISED - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES - PROJECT 1

SCALE: SHEET NO. 3 OF 5 SHEETS STA. TO STA.

| | | | | |
|------------------------------|----------------------|--------|--------------------|--------------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 80 | D3 PAVEMENT PATCHING | BUREAU | 13 | 6 |
| FED. ROAD DIST. NO. ILLINOIS | | | CONTRACT NO. 66778 | |