

SUMMARY OF QUANTITIES			80% FED. 20% STATE	
CODE NO.	ITEM	CONSTRUCTION CODE		
		UNIT	I000	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD		920
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD		67
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD		67
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON		6
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		3061
40600300	AGGREGATE (PRIME COAT)	TON		78
40600535	LEVELING BINDER (HAND METHOD), N70	TON		16.7
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON		858.5
40600895	CONSTRUCTING TEST STRIP	EACH		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD		474.4
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD		283.6
40600990	TEMPORARY RAMP	SQ YD		16.7
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON		3170.6
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON		94.8
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD		15330.5
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD		18052.7
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD		336.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON		392.8
66700095	PERMANENT SURVEY MARKERS	EACH		10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		3
67100100	MOBILIZATION	L SUM		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM		1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM		1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT		2980

FILE NAME =	USER NAME = Fergusonso	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\projects\66804\66804-shr-cover.dgn		DRAWN -	REVISED -			317	26 RS-5	LIVINGSTON	13	3	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 66804					
	PLOT DATE = Mar 31, 2008 - 04:57:49 PM	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.