

**MAINLINE SCHEDULE**

LOCATION	LENGTH FEET	WIDTH FEET	WIDTH WITH PAVED SHLDR	PAVED SHLDR WIDTH	AGG SHLDR WIDTH	AREA	AREA WITH SHLDR	HOT-MIX ASPHALT SURF. CSE. MIX D N 70	LEVEL BIND (MACH.METH) N 70	LEVEL BINDER (HAND METH.)	AGG. PRIME COAT	BIT. PRIME COAT	AGG. SHLDRS. TY B	HOT-MIX ASPHALT SURF.REM BUTT JT	TEMP. RAMP	HOT-MIX ASPHALT SURF.REM 1"	HOT-MIX ASPHALT SURF.REM 1 1/2"
			FEET	FEET	FEET	FEET	FEET	SQ YD	SQ YD	TONS	TONS	TONS	TONS	GAL.	TONS	SQ YD	SQ YD
STA. 491+67 TO 537+66.15	4599.15	24	30	6	6	12264.4	15330.5	1287.76	858.51	7.67	30.66	1226.44	393	200	16.67	15330.5	
STA. 537+66.15 TO STA. 541+94.80	428.65	24	26	2	0	1143.07	1238.32	104.02		0.62	2.48	99.07					1238.32
STA. 541+94.80 TO STA. 547+01	506.2	24	30	6	0	1349.87	1687.33	141.74		0.84	3.37	134.99					1687.33
STA. 547+01 TO STA. 555+30	829	26-38	26-38	0	0	3694.86	3694.86	310.37		1.85	7.39	295.59					3694.86
STA. 555+30 TO 576+77	2147	24	30	6	0	5725.33	7156.67	601.16		3.58	14.31	572.53					7156.67
STA. 576+77 TO STA. 591+57	1480	24	26	2	0	3946.67	4275.56	359.15		2.14	8.55	342.04					4275.56
<b>LINE TOTAL</b>	<b>9990</b>					<b>28124.2</b>	<b>33383</b>	<b>2804.2</b>	<b>858.51</b>	<b>16.7</b>	<b>66.76</b>	<b>2670.66</b>	<b>392.84</b>	<b>200</b>	<b>16.67</b>	<b>15330.5</b>	<b>18052.74</b>

**THERMOPLASTIC PAVEMENT MARKING**

LOCATION		4"		6"		8"	12"	12"	24"	LETTERS & SYMBOLS	SHORT TERM PVMT MK	WORK ZONE PVMT MK REM
		WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	SO FT	LIN FT	SQ FT
		LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT			
<b>KANKAKEE COUNTY</b>												
STA. 491+67 TO 537+66.15	4599.15	9198.3			1149.8						1380	153.1
STA. 537+66.15 TO STA. 541+94.80	428.65	857.3			107.2						86	14.3
STA. 541+94.80 TO STA. 547+01	506.2	1012.4			126.6						101	16.8
STA. 547+01 TO STA. 555+30	829		2287	420		226	210	200	95	62.4	688	114.5
STA. 555+30 TO 576+77	2147	4294			536.8						429	71.5
STA. 576+77 TO STA. 591+57	1480	2960			370.0						296	49.3
<b>PROJECT TOTAL</b>	<b>9990</b>	<b>18322</b>	<b>2287</b>	<b>420</b>	<b>2290</b>	<b>226</b>	<b>210</b>	<b>200</b>	<b>95</b>	<b>62</b>	<b>2980</b>	<b>420</b>

**TEMPORARY PAVEMENT MARKING**

LOCATION		4"		6"		8"	12"	12"	24"
		WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE
		LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT
<b>KANKAKEE COUNTY</b>									
STA. 491+67 TO 537+66.15	4599.15	9198.3			1149.8				
STA. 537+66.15 TO STA. 541+94.80	428.65	857.3			107.2				
STA. 541+94.80 TO STA. 547+01	506.2	1012.4			126.6				
STA. 547+01 TO STA. 555+30	829		2287	420		226	210	200	95
STA. 555+30 TO 576+77	2147	4294			536.8				
STA. 576+77 TO STA. 591+57	1480	2960			370.0				
<b>PROJECT TOTAL</b>	<b>9990</b>	<b>18322</b>	<b>2287</b>	<b>420</b>	<b>2290</b>	<b>226</b>	<b>210</b>	<b>200</b>	<b>95</b>

**RAISED REFLECTIVE MARKERS**

LOCATION		1 WAY CRYSTAL	1 WAY AMBER	2 WAY AMBER	REMOVAL
		EACH	EACH	EACH	EACH
STA. 491+67 TO 537+66.15	4599.15			57	57
STA. 537+66.15 TO STA. 541+94.80	428.65			5	5
STA. 541+94.80 TO STA. 547+01	506.2			6	6
STA. 547+01 TO STA. 555+30	829	6	26	8	23
STA. 555+30 TO 576+77	2147			27	27
STA. 576+77 TO STA. 591+57	1480			19	19
<b>TOTAL</b>		<b>6</b>	<b>26</b>	<b>122</b>	<b>137</b>