



ELECTRICAL SCHEDULE OF QUANTITIES (FIRST STREET)

DESCRIPTION	UNIT	QUANTITY
INDUCTIVE LOOP DETECTOR	EACH	12
DETECTOR LOOP, TYPE I	FOOT	1200
LOOP DETECTOR TESTING	EACH	1
MODIFY EXISTING CONTROLLER CABINET	EACH	1

1. SAW CUT EXISTING DETECTOR LOOPS TO BE ABANDONED
2. THE CONTRACTOR SHALL USE THE EXISTING DRILLED HOLE AND CONDUIT WHENEVER PRACTICAL.
3. FOUR (4) TURNS ARE REQUIRED FOR EACH DETECTOR LOOP
4. DETECTOR LOOPS SHALL BE CUT INTO THE PAVEMENT AFTER MILLING HAS BEEN PERFORMED AND BEFORE BINDER AND SURFACE LIFTS HAVE BEEN ADDED.