

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

LOCATION OF WORK:

DEWITT COUNTY RURAL ROADWAY/STRUCTURE IMPROVEMENTS FAI-74 STA 633+65 TO STA 909+40.45 90% FEDERAL 10% STATE I000-2A QUANTITY	DEWITT COUNTY RURAL ROADWAY/STRUCTURE IMPROVEMENTS FAI-74 STA 638+50.61 S.N. 010-0024 90% FEDERAL 10% STATE SFTY-2A QUANTITY
--	--

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	DEWITT COUNTY QUANTITY	DEWITT COUNTY QUANTITY
20200100	EARTH EXCAVATION	CU YD	46.0	46.0	
20400800	FURNISHED EXCAVATION	CU YD	1,390.0	1,390.0	
25000210	SEEDING, CLASS 2A	ACRE	2.0	2.0	
25000350	SEEDING, CLASS 7	ACRE	2.0	2.0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	157.0	157.0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	157.0	157.0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	157.0	157.0	
25100115	MULCH, METHOD 2	ACRE	2.0	2.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	174.0	174.0	
28000300	TEMPORARY DITCH CHECKS	EACH	7.0	7.0	
28000500	INLET AND PIPE PROTECTION	EACH	4.0	4.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27,113.0	27,113.0	
40600300	AGGREGATE (PRIME COAT)	TON	543.0	543.0	
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	442.0	442.0	
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,047.0	4,047.0	
40600990	TEMPORARY RAMP	SQ YD	2,012.0	2,012.0	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	19,036.0	19,036.0	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	13,622.0	13,622.0	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41.0	41.0	
40800030	AGGREGATE (PRIME COAT)	TON	1.0	1.0	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	87.0	87.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,544.0	1,544.0	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	151,586.0	151,586.0	

SHEET 1 OF 3

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A DRAWN BY: CADD
 DATE: 02-25-08 CHECKED BY:

PLOT DATE = 2/25/2008
 FILE NAME = c:\pwork\1582285\68170475cover.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = callierb