

SUMMARY OF QUANTITIES

LOCATION OF WORK:

DEWITT COUNTY RURAL ROADWAY/STRUCTURE IMPROVEMENTS FAI-74 STA 633+65 TO STA 909+40.45 90% FEDERAL 10% STATE I000-2A QUANTITY	DEWITT COUNTY RURAL ROADWAY/STRUCTURE IMPROVEMENTS FAI-74 STA 638+50.61 S.N. 010-0024 90% FEDERAL 10% STATE SFTY-2A QUANTITY
--	--

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	DEWITT COUNTY QUANTITY	DEWITT COUNTY QUANTITY
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1,571.0	1,571.0	
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	110.0	110.0	
44200629	CLASS A PATCHES, TYPE I, 15 INCH	SQ YD	36.0	36.0	
44200630	CLASS A PATCHES, TYPE II, 15 INCH	SQ YD	86.0	86.0	
44200631	CLASS A PATCHES, TYPE III, 15 INCH	SQ YD	210.0	210.0	
44200632	CLASS A PATCHES, TYPE IV, 15 INCH	SQ YD	1,402.0	1,402.0	
44213000	PATCHING REINFORCEMENT	SQ YD	1,734.0	1,734.0	
44213200	SAW CUTS	FOOT	2,955.0	2,955.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,795.0	2,795.0	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	10,129.0	10,129.0	
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	7.0	7.0	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3,857.0	3,857.0	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.0	1.0	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	22.0	22.0	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0	2.0	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	16.0	16.0	
63200310	GUARDRAIL REMOVAL	FOOT	3,622.0	3,622.0	
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	4,913.0	4,913.0	
* 63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1.0	1.0	
* 63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.0	2.0	
63400105	GUARD POSTS	EACH	62.0	62.0	
63400205	GUARD POSTS REMOVAL	EACH	35.0	35.0	
64200105	SHOULDER RUMBLE STRIP	FOOT	106,597.0	106,597.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7.0	7.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	

* SPECIALTY ITEM

SHEET 2 OF 3

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A
 DATE: 02-25-08

DRAWN BY: CADD
 CHECKED BY:

PLOT DATE = 2/20/08
 FILE NAME = c:\pwork\1105\1105.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = onitmbv