

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULES OF QUANTITIES

CROSSOVERS

STATION	AREA (SQ YD)	40800010 BIT MATLS PR CT (GALLON)	40800030 AGG PR CT (TON)	40800050 INCID HMA SURFACE (TONS)
699+35	206.1	20.6	0.4	43.3
788+62	206.1	20.6	0.4	43.3
TOTAL =		41.2	0.8	86.6
USE =		41.0	1.0	87.0

44000155 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"

* STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
RT EB 844+30.80		RT EB 848+15.40	384.6	10	427.3
LT EB 844+30.80		LT EB 848+15.40	384.6	6	256.4
RT WB 843+08.70		RT EB 847+92.67	484.0	10	537.7
LT WB 843+08.70		LT WB 847+92.67	484.0	6	322.6
* SHOULDER AREAS			TOTAL =	1,544.1	
			USE =	1,544.0	

44000158 HOT MIX-ASPHALT SURFACE REMOVAL, 2 1/4"

	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
	EB 608+76.00		EB 610+00.00 (BK)	124.0	24	330.7
	WB 608+90.00		WB 610+00.00 (BK)	110.0	24	293.3
	EB 633+68.77 (AH)		EB 655+70.00	2201.2	24	5,869.9
	WB 633+68.77 (AH)		WB 666+29.87	3261.1	24	8,696.3
	EB 655+70.00		EB 659+74.37	404.4	24	1,078.3
REST AREA	EB 655+70.00		EB 662+33.70	663.7	VAR	943.1
	WB 666+29.87		WB 675+79.87	950.0	24	2,533.3
REST AREA	WB 666+29.87		WB 679+10.15	1280.3	VAR	1663.6
	EB 659+74.37		EB 662+33.70	259.3	24	691.5
	WB 675+79.87		WB 679+10.15	330.3	24	880.7
	EB 662+33.70		EB 694+54.78	3221.1	24	8,589.5
	WB 679+10.15		WB 711+31.23	3221.1	24	8,589.5
REST AREA	WB 711+31.23		WB 717+94.93	663.7	VAR	944.9
	EB 694+54.78		EB 697+85.06	330.3	24	880.7
REST AREA	EB 694+54.78		EB 707+35.06	1280.3	VAR	1,663.8
	WB 711+31.23		WB 713+90.56	259.3	24	691.5
	EB 697+85.06		EB 707+35.06	950.0	24	2,533.3
	WB 713+90.56		WB 717+94.93	404.4	24	1,078.3
	EB 707+35.06		EB 745+73.01	3838.0	24	10,234.5
	WB 717+94.93		WB 744+75.17	2680.2	24	7,147.3
	EB 749+39.68		EB 775+06.98	2567.3	24	6,846.1
	WB 748+41.84		WB 774+92.42	2650.6	24	7,068.2
	EB 776+13.99		EB 807+27.60	3113.6	24	8,303.0
	WB 776+01.37		WB 807+37.98	3136.6	24	8,364.3
	EB 808+76.60		EB 816+05.17	728.6	24	1,942.9
	WB 808+86.98		WB 816+05.17	718.2	24	1,915.2
	EB 817+66.75		EB 844+75.80	2709.1	24	7,224.1
	WB 817+66.75		WB 844+53.07	2686.3	24	7,163.5
	WB 847+47.67		WB 910+00.00	6252.3	24	16,672.9
	EB 847+70.40		EB 909+40.50	6170.1	24	16,453.6
RAMP "C"	EB 829+63.00		EB 836+25.23	662.2	VAR	942.1
RAMP "D"	EB 857+10.70		EB 864+93.00	782.3	VAR	1,119.7
RAMP "B"	WB 824+85.00		WB 835+74.53	1089.5	VAR	1,260.0
RAMP "A"	WB 856+24.80		WB 863+06.00	681.2	VAR	976.1
TOTAL =						151,586.1
USE =						151,586.0

44000161 HOT-MIX ASPHALT SURFACE REMOVAL, 3"

	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
	EB 844+75.80		EB 847+70.40	294.6	24	785.6
	WB 844+53.07		WB 847+47.67	294.6	24	785.6
TOTAL =						1,571.2
USE =						1,571.0

PLOT DATE = 3/28/2008
 FILE NAME = c:\projects\4592295 (8)\70475cover.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A
 DATE: 02-25-08
 DRAWN BY: CADD
 CHECKED BY: