

SCHEDULES OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(20-1)RS-2	DEWITT	97	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** ③ 63301210 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A**

	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>FOOT</u>
<u>REST AREA</u>							
EASTBOUND	RT 656+24.00		RT 657+36.50	RT 656+43.90		RT 657+56.40	112.5
WESTBOUND	LT 716+65.50		LT 717+78.00	LT 716+08.50		LT 717+21.05	112.5
<u>S. N. 020-0026</u>							
EASTBOUND	RT 743+87.08		RT 745+62.08	RT 743+38.85		RT 745+13.85	175.0
<u>S. N. 020-0027</u>							
WESTBOUND	LT 748+62.40		LT 750+24.90	LT 748+73.15		LT 750+35.65	162.5
<u>S. N. 020-0028</u>							
EASTBOUND	RT 773+04.08		RT 774+79.08	RT 772+55.85		RT 774+30.85	175.0
<u>S. N. 020-0029</u>							
WESTBOUND	LT 776+39.42		LT 778+01.92	LT 776+50.15		LT 778+12.65	162.5
<u>S. N. 020-0030</u>							
EASTBOUND	RT 790+07.31		RT 806+93.11	RT 789+94.85		RT 806+69.85	1,675.0
<u>S. N. 020-0031</u>							
WESTBOUND	LT 788+40.25		LT 807+15.75	LT 788+10.35		LT 806+85.85	1,875.5
<u>S. N. 020-0033</u>							
WESTBOUND	LT 818+11.31		LT 819+73.81	LT 818+22.15		LT 819+84.65	162.5
<u>S. N. 020-0036</u>							
EASTBOUND	RT 863+55.32		RT 865+17.82	RT 863+32.05		RT 864+94.55	162.5
<u>S. N. 020-0037</u>							
WESTBOUND	LT 867+68.19		LT 869+05.69	LT 867+78.95		LT 869+16.45	137.5
<u>TOTAL =</u>							<u>4,913.0</u>
<u>USE =</u>							<u>4,913.0</u>

*** ④ 63301990 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1**

	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>EACH</u>
<u>SN 020-0037</u>							
WESTBOUND	LT 869+06.99		LT 869+56.99	LT 869+78.95		LT 870+28.95	1.0
<u>TOTAL =</u>							<u>1.0</u>

*** ⑤ 63302000 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2**

	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>EACH</u>
<u>REST AREA</u>							
EASTBOUND	RT 657+36.5		RT 657+49	RT 657+56.4		RT 657+71.2	1.0
WESTBOUND	LT 716+53		RT 716+65.5	RT 715+93.75		RT 716+08.55	1.0
<u>TOTAL =</u>							<u>2.0</u>

63400105 GUARD POSTS

<u>STATION/LOCATION</u>	<u>EACH</u>	
655+86.93	6.0	
669+18.28	6.0	
699+27.84	6.0	
711+12.44	6.0	
733+67.81	6.0	
760+24.09	6.0	
850+66.46	6.0	
IMPACT ATTENUATORS SN 020-0024	10.0	
IMPACT ATTENUATORS SN 020-0034	10.0	
<u>TOTAL =</u>		<u>62.0</u>

* SEE "DETAIL FOR GUARDRAIL LOCATIONS"

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (20-1)RS-2
 DEWITT COUNTY

SCALE: N/A DRAWN BY: CADD
 DATE: 02-25-08 CHECKED BY: