

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	D5 PATCHING	CHAMPAIGN	17	10

# SCHEDULES OF QUANTITIES

## TABULATION OF CLASS A PAVEMENT PATCH, 13 INCH (EASTBOUND)

STATION	LANE	LENGTH ( FT )	WIDTH ( FT )	TYPE 1 X0325338 ( SQ. YD. )	TYPE 2 X4420046 ( SQ. YD. )	TYPE 3 X4420064 ( SQ. YD. )	TYPE 4 X4420066 ( SQ. YD. )	SAWCUTS 44213200 ( FT )	TIE BARS Z0075300 ( EACH )	PATCHING REINFORCEMENT 44213000 ( SQ. YD. )
1898+33.00	EBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1821+20.00	EBDL	12.0	12.0	-	-	16.0	-	72.0	-	16.0
1803+87.00	EBDL	8.0	12.0	-	10.7	-	-	64.0	-	10.7
1781+22.00	EBDL	8.0	12.0	-	10.7	-	-	64.0	-	10.7
1781+03.00	EBDL	10.0	6.0	-	6.7	-	-	44.0	-	6.7
1780+70.00	EBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1779+84.00	EBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1779+27.00	EBDL	8.0	12.0	-	10.7	-	-	64.0	-	10.7
1762+36.00	EBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1743+88.00	EBDL	15.0	12.0	-	-	20.0	-	78.0	-	20.0
1732+55.00	EBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1710+80.00	EBDL	10.0	12.0	-	13.3	-	-	68.0	-	13.3
1674+48.00	EBDL	10.0	12.0	-	13.3	-	-	68.0	-	13.3
1674+04.00	EBDL	10.0	12.0	-	13.3	-	-	68.0	-	13.3
1673+00.00	EBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
CLASS A PATCH 13 INCH - PAGE SUBTOTALS				12.0	102.7	36.0	0.0	878.0	0.0	150.7

PLOT DATE : 3/13/2008  
 FILE NAME : c:\projects\70646\70646cover.dgn  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES OF QUANTITIES**  
 F.A.I. ROUTE 72  
 SECTION D5 PATCHING  
 CHAMPAIGN COUNTY

SCALE: NONE  
 DATE: 03-07-2008  
 DRAWN BY: CADD  
 CHECKED BY: