

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	D5 PATCHING	CHAMPAIGN	17	13

SCHEDULES OF QUANTITIES

TABULATION OF CLASS A PAVEMENT PATCH, 13 INCH (WESTBOUND)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 1 X0325338 (SQ. YD.)	TYPE 2 X4420046 (SQ. YD.)	TYPE 3 X4420064 (SQ. YD.)	TYPE 4 X4420066 (SQ. YD.)	SAWCUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ. YD.)
1991+33.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1991+33.00	•WBPL•	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1988+36.00	WBDL	80.0	6.0	-	-	-	53.3	184.0	40.0	53.3
1985+28.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1985+28.00	•WBPL•	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1934+72.00	•WBPL•	12.0	25.0	-	-	-	33.3	124.0	-	33.3
1920+61.00	WBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1920+29.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1905+78.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1905+78.00	•WBPL•	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1898+65.00	WBDL	10.0	6.0	-	6.7	-	-	44.0	-	6.7
1897+78.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
CLASS A PATCH 13 INCH - PAGE SUBTOTALS				4.0	70.7	0.0	86.6	868.0	40.0	161.3

PLOT DATE : 3/13/2008
 FILE NAME : c:\projects\70646\70646cover.dgn
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 72
 SECTION D5 PATCHING
 CHAMPAIGN COUNTY

SCALE: NONE
 DATE: 03-07-2008
 DRAWN BY: CADD
 CHECKED BY: