

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	D5 PATCHING	CHAMPAIGN	17	14

SCHEDULES OF QUANTITIES

TABULATION OF CLASS A PAVEMENT PATCH, 14 INCH (EASTBOUND & WESTBOUND)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 1 44200616 (SQ. YD.)	TYPE 2 44200620 (SQ. YD.)	TYPE 3 44200624 (SQ. YD.)	TYPE 4 44200628 (SQ. YD.)	SAWCUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ. YD.)
1624+93.00	EBDL	10.0	12.0	-	13.3	-	-	68.0	-	13.3
1611+62.00	EBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1611+30.00	EBDL	6.0	6.0	4.0	-	-	-	36.0	-	4.0
1611+21.00	EBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1611+21.00	•EBPL•	6.0	12.0	-	8.0	-	-	60.0	-	8.0
1610+84.00	EBDL	15.0	12.0	-	-	20.0	-	78.0	-	20.0
1585+40.00	EBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
EASTBOUND										
CLASS A PATCH 14 INCH - PAGE SUBTOTALS				8.0	37.3	20.0	0.0	398.0	0.0	65.3

STATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE 1 44200616 (SQ. YD.)	TYPE 2 44200620 (SQ. YD.)	TYPE 3 44200624 (SQ. YD.)	TYPE 4 44200628 (SQ. YD.)	SAWCUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQ. YD.)
1595+49.00	WBDL	6.0	12.0	-	8.0	-	-	60.0	-	8.0
WESTBOUND										
CLASS A PATCH 14 INCH - PAGE SUBTOTALS				0.0	8.0	0.0	0.0	60.0	0.0	8.0

EASTBOUND AND WESTBOUND										
CLASS A PATCH 14 INCH - PAGE SUBTOTALS				8.0	45.3	20.0	0.0	458.0	0.0	73.3

PLOT DATE : 3/13/2008
 FILE NAME : c:\projects\70646\70646cover.dgn
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : collierb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 F.A.I. ROUTE 72
 SECTION D5 PATCHING
 CHAMPAIGN COUNTY

SCALE: NONE
 DATE: 03-07-2008
 DRAWN BY: CADD
 CHECKED BY: