

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		100% STATE	Y007
28100207	STONE DUMPED RIPRAP, CLASS A4	TON	182	182
28200200	FILTER FABRIC	SQ YD	312	312
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1,739	1,739
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	846	846
50105200	REMOVE EXISTING CULVERTS	EACH	3	3
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	557	557
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	634	634
54200661	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 36"	FOOT	100	100
54215550	METAL END SECTIONS 15"	EACH	26	26
54215553	METAL END SECTIONS 18"	EACH	20	20
54215571	METAL END SECTIONS 36"	EACH	4	4
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	8,000	8,000
63500105	DELINEATORS	EACH	14	14
63600105	CABLE ROAD GUARD, SINGLE STRAND	FOOT	3,260	3,260
67100100	MOBILIZATION	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1

• LAGRANGE WETLAND BANK
 ** D6 WETLAND MITIGATION 3

FILE NAME =	USER NAME = loughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\Projects\4650305\contract 03\shscoq		DRAWN -	REVISED -					•	**	BROWN	174	4
PLOT SCALE = 100.0000' / IN.	CHECKED - JCN	REVISIONS -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 72968				
PLOT DATE = Mar-17-2008 12:03:05PM	DATE -	REVISIONS -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							