

CULVERT & FOUNDATION REMOVAL SCHEDULE		
LOCATION	FOUND. REMOVAL	REMOVE EXISTING CULVERTS
	(EACH)	(EACH)
ALIGNMENT A001a STA 38+20.00 STA 62+35.00		1 1
ALIGNMENT B001 STA 331+50.00		1
ALIGNMENT Z001 RT STA 5013+00.00 TO RT STA 5014+00.00	3	
TOTAL =	3	3

AGGREGATE SUB-BASE / SURFACE SCHEDULE		
LOCATION	SUB-BASE GRAN. T-B 4" THICK	AGG. SURF. T-A 2" THICK
	(TON)	(TON)
ALIGNMENT A001 STA 500+06.13 TO STA 510+00.00	1162.7	564.6
ALIGNMENT A001b STA 7+00.00 TO STA 9+50.00	225.4	110.5
ALIGNMENT A001a STA 26+70.15 TO STA 27+50.00	33.7	16.3
RT STA 26+70.15 TO RT STA 26+80.15 - PARKING LOT	7.9	3.8
ALIGNMENT B001 STA 348+00.00 TO STA 350+00.00	84.4	40.9
RT STA 349+10.00 TO RT STA 350+00.00 - PARKING LOT	69.3	34.3
ALIGNMENT Z001 RT STA 5013+00.00 TO RT STA 5014+00.00 - PARKING LOT & FIELD ENTRANCE	158.2	77.5
TOTAL =	1741.6	848.0

ACCESS CONTROL FENCE / GATES			
LOCATION	CABLE A/C FENCE	CABLE A/C GATE	ACCESS GATE DBL, 30'
	(FOOT)	(EACH)	(EACH)
ALIGNMENT Z001 RT STA 5003+87.79 TO RT STA 5004+17.44		1	
RT STA 5004+17.44 TO RT STA 5013+33.00	931		
RT STA 5013+33.00 TO RT STA 5014+37.00	183	1	
RT STA 5014+37.00 TO RT STA 5018+89.68	453		
RT STA 5018+89.68 TO RT STA 5019+31.74	46		
RT STA 5056+34.33 TO RT STA 5056+64.54		1	
RT STA 5056+64.54 TO RT STA 5062+62.94	600		
RT STA 5062+62.94 TO RT STA 500+87.65 (A001)	89		
STA 500+87.65 (A001)			1
LT STA 500+87.65 (A001) TO RT STA 5064+43.15	94		
RT STA 5064+43.15 TO RT STA 5066+53.68	211		
RT STA 5066+53.68 TO RT STA 5066+86.79	39		
RT STA 5066+86.79 TO LT STA 101+00.00 (C001)	532		
TOTAL =	3,178	3	1

PIPE CULVERT SCHEDULE							
LOCATION	PIPE CULV T-1, CS/A	PIPE CULV T-1, CS/A	PIPE CULV T-1, CS/A	METAL END SEC	METAL END SEC	METAL END SEC	DELIN. S - WHITE CRYSTAL
	15" (FOOT)	18" (FOOT)	36" (FOOT)	15" (EACH)	18" (EACH)	36" (EACH)	(EACH)
ALIGNMENT A001b STA 9+75.00	60			2			2
ALIGNMENT A001 LT STA 509+40.00	32			2			
RT STA 509+60.00	70			2			
LT STA 525+00.00	32			2			
ALIGNMENT A001a RT STA 37+00.00	58			2			
STA 38+20.00			100			4	2
STA 45+50.00		80			4		2
LT STA 56+00.00	34			2			
RT STA 56+00.00	34			2			
STA 62+35.00		108			4		2
LT STA 74+00.00	40			2			
RT STA 74+00.00	40			2			
STA 75+50.00		32*					
STA 90+00.00		32*					
STA 101+80.00		32*					
STA 110+00.00		32*					
LT STA 117+00.00	40			2			
ALIGNMENT B001 RT STA 330+00.00	36			2			
STA 331+50.00		126			4		2
RT STA 333+50.00	35			2			
STA 341+00.00		96			4		2
STA 347+50.00		96			4		2
ALIGNMENT Z001 RT STA 5014+25.00	46			2			
TOTAL =	557	634	100	26	20	4	14

NOTE: * COST OF REMOVING AND RE-INSTALLING EXISTING END SECTIONS, FURNISHING AND INSTALLING AN APPROVED METAL EXTENSION BANDS, AND REMOVING AND REINSTALLING EXISTING DELINEATORS WILL BE CONSIDERED PART OF CONTRACT UNIT BID PRICE FOR THE PIPE CULVERTS.

• LAGRANGE WETLAND BANK
•• D6 WETLAND MITIGATION 3