

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
723		MONTGOMERY	4	3
STA. 5+09		TO STA. 374+69		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

(16R)RS-6; (17R)RS-6

Application Rates
 Bituminous Materials (Prime Coat)
 Aggregate Materials (Prime Coat)

0.00038 Tons / Sq Yd (0.10 Gal / Sq Yd)
 0.002 Tons / Sq Yd

Station Range	Width (FT)	Length (FT)	Area (SY)	CAPE Seal (SY)
5+09 TO 266+45	22	26,136	63,888	63,888
Totals		26,136	63,888	63,888

Raised Reflective Markers Removal (EACH)	Raised Reflective Markers Installation (EACH)
327	327
327	327

Paint Pavement Marking Line, 5" Location	Length (FT)	Edge Line (FT)	Skip/No Passing (FT)	Total
No Passing Zones	26,136	52,272	13,068	65,340

Notes:
 The Aggregate used with the A-1 treatment for the CAPE seal shall be CA-16

DISTRICT SIX	
EXAMINED <u>Feb 22</u> 20 <u>08</u>	
<i>[Signature]</i>	
OPERATIONS ENGINEER	
EXAMINED <u>2-20-</u> 20 <u>08</u>	
<i>[Signature]</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED <u>FEB 24</u> 20 <u>08</u>	
<i>[Signature]</i>	
PROGRAM DEVELOPMENT ENGINEER	

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAS 723
 SECTION (16R)RS-6; (17R)RS-6
 MONTGOMERY COUNTY
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY