SUMMARY OF QUANTITIES

S. N. 084-0046
80% STATE
20% FED

CODE X080-2A

CODE NO	PAY ITEM	UNITS	QUANTITY
X0326089	ERECTING PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1927
X0326090	ERECTING STRUCTURAL STEEL	POUND	26060
X0301424	SILICONE JOINT SEALER	FOOT	33
X0320887	POLYMER CONCRETE	CU FT	1.2
X7200201	WIDTH RESTRICTION SIGNAGE	L SUM	1
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECIVE), TEST LEVEL 3	EACH	2
20200100	EARTH EXCAVATION	CU YD	100
25000200	SEEDING, CLASS 2	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9
25100115	MULCH, METHOD 2	ACRE	0.1
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	345
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	10.0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5
40600300	AGGREGATE (PRIME COAT)	TON	1
40600990	TEMPORARY RAMP	SQ YD	29
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 70	TON	83

* Specialty Items