

INDEX OF SHEETS

GENERAL NOTES

- ① WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSES OR OTHERWISE REFERENCED THEIR LOCATION.
- ② ANY REFERENCE TO A STANDARD IN THE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION, AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS, OR THE COPY OF THE STANDARD INCLUDED IN THE PLANS.
- ③ EXCESS MATERIAL COLLECTED FROM EXCAVATING AND GRADING EXISTING SHOULDERS SHALL BE USED TO GRADE AND PREPARE THE SUB-BASE FOR PROPOSED AGGREGATE SHOULDERS, TYPE B TO THE SATISFACTION OF THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER TON FOR AGGREGATE SHOULDERS, TYPE B.
- ④ AN AVERAGE THICKNESS OF 2" WAS USED TO CALCULATE THE QUANTITY FOR AGGREGATE SHOULDERS, TYPE B.
- ⑤ THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE:

LOCATION(S):	IL 10
MIXTURE USE(S):	HMA SHOULDERS 8
AC/PG:	PG 58-22
R.A.P. % (MAX.):	50 %
DESIGN AIR Voids	2.0 @ N design = 30
MIXTURE COMPOSITION (Gradation Mixture)	BAM MIX
FRICTION AGGREGATE	N/A

RATES OF APPLICATION TABLES

THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES.

HOT-MIX ASPHALT MATERIALS (PRIME COAT): 0.00038 TON / SQ YD (ON PAVEMENT)
 0.001425 TON / SQ YD (ON AGGREGATE)
 AGGREGATE MATERIALS (PRIME COAT): 0.002 TON / SQ YD
 HOT-MIX ASPHALT SURFACE MIX C / BINDER (112 LBS): 0.056 TON / SQ YD • in
 AGGREGATE MATERIALS: 2.05 TON / CU YD

COMMITMENTS

(NONE)

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTIONS
- 5 SCHEDULE OF QUANTITIES
- 6 - 8 PLAN VIEW (3)
- 9 - 11 PAVEMENT MARKING DETAILS (3)
- 12 SHOULDER RUMBLE STRIP DETAIL

STANDARDS

- | | |
|-----------|--|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS |
| 482001-02 | HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT |
| 701011-01 | OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY (RUMBLE STRIP, MOVING OPS) |
| 701301-02 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS (CLEAN UP DEBRIS ON SHOULDER) |
| 701306-01 | LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45MPH (SHLD OPS) |
| 701311-02 | LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY (PAVEMENT MARKING) |
| 701326-02 | LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH (SHLD EXCAV & HMA SHLD) |
| 701901 | TRAFFIC CONTROL DEVICES |
| 780001-01 | TYPICAL PAVEMENT MARKING |

DISTRICT SIX	
EXAMINED <u>March 14</u>	20 <u>08</u>
<i>Simon J. Hoopes</i>	
OPERATIONS ENGINEER	
EXAMINED <u>MAR 7</u>	20 <u>08</u>
<i>W.R. J...</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED <u>Mar 17</u>	20 <u>08</u>
<i>W.R. J...</i>	
PROGRAM DEVELOPMENT ENGINEER	