

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	122,R	WABASH	31	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

GUARDRAIL SCHEDULE

	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER, DIRECT APPLIED
	FT	EACH	EACH	EACH	EACH
LT STA 1019+86 TO STA 1020+36	87.5	1		2	1
LT STA 1020+36 TO STA 1021+24			1		
LT STA 1021+24 TO STA 1021+68					
RT STA 1019+61 TO STA 1020+11	112.5	1		3	1
RT STA 1020+11 TO STA 1021+24			1		
RT STA 1021+24 TO STA 1021+68					
TOTALS	200	2	2	5	2

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD) NTO	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NTO	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL " "	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 14"	HOT-MIX ASPHALT SHOULDERS 8"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY RAMP	AGGREGATE SHOULDERS, TYPE B 8"
	FT	FT	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ FT	SQ YD	SQ YD
STA 2+45.00 TO STA 2+75.00	30.00	25.6	85.3	8.5	0.2		7.2	85.3			53.3	12.0	1.0	14.2	13.3
STA 2+75.00 TO STA 6+65.00	390.00	25.6	1109.3	110.9	2.2	46.6	93.2		1109.3		693.3	156.0	13.0		173.3
STA 6+65.00 TO STA 9+84.00	319.00	38.6	1368.2	136.8	2.7	57.5	114.9		1368.2		309.0	127.6	10.6		68.0
STA 9+84.00 TO STA 12+20.00	236.00	25.6	671.3	67.1	1.3	28.2	56.4		671.3		370.0	94.4	7.9		102.0
STA 12+20.00 TO STA 12+21.58	1.58	24	4.2	0.4						4.2	2.8		0.1		0.7
STATION EQUATION															
STA 1012+15.28 TO STA 1021+36.34	921.06	24	2456.2	360.0	14.7					2456.2	1957.0	190.0	31.0		327.0
TOTAL QUANTITIES	1897.64		5694.5	684	21	132	272	85	3149	2460	3385	580	64	14	684

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) SHORTAGE(-)	TOPSOIL EXCAVATION AND PLACEMENT
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	SQ. YD.
IL 15 MAINLINE	12272	9204	52354	-43150	2868
SOUTHGATE DRIVE	163	122	3764	-3642	174
TOTALS	12435	9326	56118	-46792	3042

DRAINAGE

	TYPE D INLET BOX, STANDARD 609006	PIPE DRAINS 12"	CONCRETE THRUST BLOCKS	METAL END SECTIONS 12"
	EACH	FOOT	EACH	EACH
LT STA 1021+52	1	44	1	1
RT STA 1021+52	1	80	1	1
TOTALS	2	124	2	2

FURNISHING AND ERECTING ROW MARKERS

95.00'	RT	STA	3+06.47	1	EACH
100.00'	LT	STA	3+44.39	1	EACH
95.00'	RT	STA	4+00.00	1	EACH
100.00'	LT	STA	7+30.71	1	EACH
130.00'	RT	STA	8+00.00	1	EACH
100.00'	LT	STA	8+26.45	1	EACH
100.00'	LT	STA	12+21.58	1	EACH
130.00'	RT	STA	1013+93.86	1	EACH
223.08'	RT	STA	1013+94.30	1	EACH
130.00'	LT	STA	1014+01.04	1	EACH
256.62'	RT	STA	1015+48.89	1	EACH
232.50'	RT	STA	1015+51.01	1	EACH
130.00'	LT	STA	1018+00.00	1	EACH
148.81'	LT	STA	1018+97.72	1	EACH
198.90'	LT	STA	1020+00.77	1	EACH
417.65'	RT	STA	1020+12.23	1	EACH
202.64'	LT	STA	1020+53.13	1	EACH
192.66'	LT	STA	1020+53.88	1	EACH
238.34'	RT	STA	1020+84.43	1	EACH
155.02'	RT	STA	1021+24.47	1	EACH
485.14'	RT	STA	1026+82.06	1	EACH
194.06'	LT	STA	1027+23.26	1	EACH
TOTAL				22	EACH

PAVEMENT MARKING

	POLYUREA PAVEMENT MARKING TYPE 2 - LINE 4"	POLYUREA PAVEMENT MARKING TYPE 2 - LINE 6"	POLYUREA PAVEMENT MARKING TYPE 2 - LINE 24"	POLYUREA PAVEMENT MARKING TYPE 2 - LTRS & SYMB	RAISED REFLECTIVE PAVEMENT MARKERS (AMBER 2 - WAY)	WHITE	YELLOW
	FOOT	FOOT	FOOT	SQ FT	EACH		
LT STA 2+65			12			X	
LT STA 4+25			12			X	
LT STA 4+50				61.2		X	
LT STA 4+75			12			X	
LT STA 8+50				15.6		X	
LT STA 9+40				15.6		X	
LT STA 8+50 TO 9+50		100				X	
WB NPZ 2+45 TO 1021+66	1927						X
EB SKIPS 2+45 TO 1021+66	482				25		X
EDGE 2+45 TO 1021+66	3854					X	
TOTALS	6263	100	36	92.4	25		

SURVEY MARKERS

PERMANENT SURVEY MARKERS, TYPE 1	
PC STA 1014+01.04	1 EACH
PT STA 1021+46.06	1 EACH
TOTAL	2 EACH
PERMANENT SURVEY MARKERS, TYPE 2	
PI STA 1017+82.61	1 EACH

TREE REMOVAL

TREE REMOVAL (OVER 15 UNIT DIA)	
LT STA 5+65	24 UNITS
TREE REMOVAL, ACRES	
LT STA 10+60 TO 12+21	0.13 ACRES
LT STA 1012+15 TO 1021+66	0.76 ACRES
RT STA 3+05 TO 12+21	0.88 ACRES
RT STA 1012+15 TO 1015+47	0.32 ACRES
RT STA 1015+83 TO 1017+96	0.21 ACRES
RT STA 1018+48 TO 1021+66	0.31 ACRES
TOTAL	2.6 ACRES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY