

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SFTY-3N		
20200100	EARTH EXCAVATION	CU YD	10	10		
20400800	FURNISHED EXCAVATION	CU YD	6773	6773		
25000200	SEEDING, CLASS 2	ACRE	5.3	5.3		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	477	477		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	477	477		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	477	477		
25100115	MULCH, METHOD 2	ACRE	5.3	5.3		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	530	530		
28000300	TEMPORARY DITCH CHECKS	EACH	15	15		
28000500	INLET AND PIPE PROTECTION	EACH	6	6		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1178	1178		
50105220	PIPE CULVERT REMOVAL	FOOT	93	93		
50300225	CONCRETE STRUCTURES	CU YD	42.9	42.9		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4010	4010		
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	145	145		
54246405	INLET BOX, STANDARD 542531	EACH	2	2		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	25	25		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	22	22		
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1500	1500		
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5		
63200310	GUARDRAIL REMOVAL	FOOT	164	164		
63400105	GUARD POSTS	EACH	70	70		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	30	30		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5		
X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	EACH	3	3		
X6050700	REMOVE INLET BOX	EACH	3	3		
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14	14		

FILE NAME =
c:\projects\74250d\shs0q_74250.dgn

USER NAME = teasleyck

DESIGNED -

DRAWN -

CHECKED -

DATE -

REVISED -

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	D7 SAFETY 2008-3	MACON	70	3
CONTRACT NO. 74250				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

Rev.