

| F.A.P. RTE.         | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
|---------------------|----------|------------------|--------------|-----------|
| 304                 | 5BR-2    | CALHOUN          | 68           | 2         |
| STA.                |          | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |              |           |

## INDEX OF SHEETS

- 1. COVER PAGE
- 2. INDEX OF SHEETS/HIGHWAY STANDARDS/GENERAL NOTES & COMMITMENTS
- 3. - 4. SUMMARY OF QUANTITIES
- 5. TYPICAL SECTIONS & MIXTURE REQUIREMENTS
- 6. - 7. SCHEDULE OF QUANTITIES
- 8. TIE POINTS & BENCHMARKS
- 9. WIDE LOAD SIGNING
- 10. -12 MAINLINE PLAN AND PROFILE SHEET
- 13. - 18. SUGGESTED STAGES OF CONSTRUCTION & TRAFFIC CONTROL
- 19. - 20A. PLAT OF HIGHWAYS
- 21. - 23. PAVEMENT MARKING SHEETS
- 24. SIDE ROAD AND JOINT DETAILS
- 24A. REPAIR DETAILS
- 25. - 52. STRUCTURE PLANS
- 53. - 64. EXISTING STRUCTURE PLANS
- 65. - 68. MAINLINE CROSS SECTIONS

## HIGHWAY STANDARDS

|           |  |
|-----------|--|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS                             |
| 001001-01 | AREAS OF REINFORCEMENT BARS  |
| 001006    | DECIMAL OF AN INCH OF A FOOT   |
| 280001-04 | TEMPORARY EROSION CONTROL SYSTEMS  |
| 420401-06 | BRIDGE APPROACH PAVEMENT   |
| 515001-02 | NAME PLATE FOR BRIDGES   |
| 630001-07 | STEEL PLATE BEAM GUARDRAIL   |
| 630301-04 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS               |
| 631032-03 | TRAFFIC CONTROL BARRIER TERMINAL, TYPE 6A                                |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT                                  |
| 635011-01 | REFLECTOR MARKER AND MOUNTING DETAILS                                    |
| 664001-01 | CHAIN LINK FENCE   |
| 701006-02 | OFF-ROAD OPERATIONS, 2L, 2W, 4.5m (15') TO 600m (24') FROM PAVEMENT EDGE |
| 701011-01 | OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY                             |
| 701311-02 | LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY                       |
| 701321-09 | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER                         |
| 701326-02 | LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS >= 45 MPH            |
| 701901    | TRAFFIC CONTROL DEVICES  |
| 704001-04 | TEMPORARY CONCRETE BARRIER   |
| 780001-01 | TYPICAL PAVEMENT MARKINGS  |
| 781001-02 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS                  |

## GENERAL NOTES

- THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- THE THICKNESS OF THE HMA MIXTURES SHOWN ON THE PLANS IS THE NORMAL THICKNESS. DEVIATIONS MAY OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA MIXTURE IS PLACED.
- ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- \* AMEREN CIPS (ELECTRICAL)
- \* AMEREN CIPS (GAS)
- \* FRONTIER COMMUNICATIONS CO. (COMMUNICATIONS)

MEMBERS OF J.U.L.I.E (800) 892-0123 ARE INDICATED BY \*. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR SEEDING, FERTILIZING, AND MULCHING ANY AREAS DISTURBED OUTSIDE THE LIMITS OF CONSTRUCTION. THIS WORK WILL NOT BE MEASURED FOR PAYMENT. THE SEEDING SHALL BE CLASS 2. THE APPLICATION OF THE SEEDING, FERTILIZER, AND MULCH SHALL BE TO THE SATISFACTION OF THE ENGINEER. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
- IF THE CONTRACTOR, FOR HIS CONSTRUCTION ACTIVITY, REMOVES TREES WITHIN THE RIGHT-OF-WAY LIMITS WHICH ARE NOT DESIGNATED ON THE PLANS FOR REMOVAL, I.E. IN ORDER TO GAIN ACCESS TO THE PROJECT SITE; IT WILL BE HIS RESPONSIBILITY TO REPLACE THE TREES AT A 1:1 RATIO. THE TREES WILL BE REPLACED WITH A 1 GALLON NATIVE ILLINOIS TREE SPECIES AND SHALL BE APPROVED BY THE ENGINEER. THE TREE REMOVAL AND TREE REPLACEMENT WILL BE AT THE CONTRACTOR'S EXPENSE, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND ENDING OF THE PROJECT AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE.
- NO TRENCHES OR OPEN PITS WILL BE PERMITTED ADJACENT TO A TRAFFIC LANE DURING NON-WORKING HOURS. ALL WIDENING TRENCHES SHALL BE BACKFILLED DURING THE SAME WORKING DAY IT WAS EXCAVATED.
- THE COST OF GRADING AND SHAPING ALONG THE PROPOSED BASE COURSE SHALL BE INCLUDED IN THE COST OF "EARTH EXCAVATION".
- THE COST TO REMOVE ALL EXISTING TRAFFIC BARRIER TERMINALS SHALL BE INCLUDED IN THE COST OF "GUARDRAIL REMOVAL".

## EROSION CONTROL PLAN

ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO APPROVAL AND USE OF THE PRODUCT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER RECOMMENDED INSTALLATION PROCEDURES TO FACILITATE THE ENGINEER IN CONSTRUCTION INSPECTION.

STRAW BALES, HAY BALES, PERIMETER EROSION BARRIER, AND SILT FENCES WILL NOT BE PERMITTED FOR TEMPORARY OR PERMANENT DITCH CHECKS. DITCH CHECKS SHALL BE COMPOSED OF AGGREGATE, SILT PANELS, ROLLED EXCELSIOR, URETHANE FOAM/GEOTEXTILE (SILT WEDGES), EARTH MEDIAN AND/OR OTHER MATERIAL APPROVED BY THE EROSION AND SEDIMENT CONTROL COORDINATOR.

TEMPORARY DITCH CHECK, GEOTEXTILES, ROLLED EXCELSIOR, SILT WEDGES, AND PANELS SHALL BE LOCATED AT EVERY 1.5 FT FALL/RISE IN DITCH GRADE.

TEMPORARY DITCH CHECKS, AGGREGATE USES GRADING NO. 3 - REMOVE AT END OF CONSTRUCTION.

TEMPORARY SEEDING SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE PAID FOR AS "TEMPORARY EROSION CONTROL SEEDING" AND NO OTHER PAYMENT WILL BE PERMITTED. FOR CALCULATION PURPOSES, THREE APPLICATIONS OF TEMPORARY SEEDING WERE ASSUMED.

ALL AREAS DISTURBED FOR ANY REASON SHALL BE SEEDED WITH CLASS 2 SEEDING AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04 EXCEPT FERTILIZER NUTRIENTS WILL NOT BE PAID FOR SEPARATELY AS INCLUDED IN THE COST OF CLASS 2 SEEDING.

CLASS 2 SEEDING AND EROSION CONTROL BLANKET IS TO BE PLACED AS SOON AS EARTHWORK IS COMPLETED.

EROSION CONTROL BLANKET IS TO BE PLACED ON ALL SLOPE 1:2 OR STEEPER.

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.

## COMMITMENTS

THE CONTRACTOR SHALL COMPLETE THE SHORING OF BEAM 3 IN SPAN 1 WITH A SUPPORT BEAM AND HAVE THE WEIGHT LIMIT RESTRICTION REMOVED BY NO LATER THAN SEPTEMBER 1, 2008.

| REVISIONS |      | ILLINOIS DEPARTMENT OF TRANSPORTATION<br>INDEX OF SHEETS/HIGHWAY SATNDARDS<br>GENERAL NOTES/COMMITMENTS                |
|-----------|------|--|
| NAME      | DATE |  |
|           |      | FAP ROUTE 304<br>SECTION 5BR-2<br>CALHOUN COUNTY<br><br>SCALE: VERT.      DRAWN BY<br>DATE      HORIZ.      CHECKED BY |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |
|           |      |  |