

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	5BR-2	CALHOUN	68	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

RESURFACING SCHEDULE

STATION	RT/LT	HOT-MIX ASPHALT BS WIDENING 9" (SQ YD)	AGG. PRIME COAT (TON)	BIT. MAT'L PRIME COAT (TON)	INCIDENTAL HMA SURF. (TON)	BIT. CONC. BINDER SUPER. MIX "B" (TON)	BIT. CONC. SURF. CSE. SUPER. MIX "C", N70 (TON)	HMA SHOULDERS 8" (SQ YD)	AGG. SHLD TYPE B 6" (SQ YD)
463+70.00 TO 466+71.50	LT	150.75							
464+15.00 TO 466+71.39	RT/LT		1.03	0.21			57.43	170.93	170.93
464+15.00 TO 465+04.86	RT/LT					10.06			
465+04.86 TO 466+71.39	RT/LT					156.67			
468+11.50 TO 471+21.00	LT	154.75							103.17
468+42.80 TO 471+19.00	LT							92.07	
468+47.42 TO 471+15.00	RT/LT		1.07	0.22			59.94		
468+47.42 TO 470+11.81	RT/LT					191.48			
470+11.81 TO 471+15.00	RT/LT					11.56			
468+47.42 TO 471+65.00	RT								105.86
468+59.78 TO 471+65.00	RT							101.74	
471+44.97	SIDE RD LT				10.33				
TOTAL		305.50	2.10	0.43	10.33	369.77	117.37	364.74	379.96

RIPRAP SCHEDULE

LOCATION					RIPRAP A4 (SQ YD)	STONE DUMPED RIPRAP A4 (TON)	RIPRAP A5 (SQ YD)	FILTER FABRIC (SQ YD)
STA	463+58.00	TO	STA	466+81.00	LT	945.12		
STA	465+15.00	TO	STA	466+99.00	RT	711.12		
BRIDGE							1479	1479
STA	468+19.00	TO	STA	471+25.00	LT	1894.90		
STA	468+38.90	TO	STA	471+05.00	RT	469.06		
STA	469+75.00	TO	STA	471+10.00	LT	255.00		255.00
TOTAL					255.00	4020.19	1479.00	1734.00

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION	RT/LT	STOP BARS	PAVEMENT MARKING			WORK ZONE PVMT REMOVAL (SQ FT)	PVMT MRKG REMOVAL (SQ FT)
			LINE 4" PAVEMENT (FT)	LINE 6" (TEMP. BARR.) (FT)	LINE 24" PAVEMENT (FT)		
462+30.00	RT	STOP BARS			12	24.0	
462+30.00	TO 473+48.00	STAGE 1	2236.00			745.3	
462+30.00	TO 473+50.00	RT/LT					746.7
462+30.00	TO 473+50.00	CL					93.3
463+30.00	TO 472+00.00	STAGE 1		870			
463+57.50	TO 471+17.50	STAGE 2		750			
473+48.00	LT	STOP BARS			12.0	24.0	
462+47.00	RT	STOP BARS			12	24.0	
462+47.00	TO 473+50.00	STAGE 2	2206.00			735.3	
473+50.00	LT	STOP BARS			12.0	24.0	
471+44.97	SIDE ROAD	LT STOP BARS			24.0	48.0	
SUB-TOTAL							
TOTAL			4442.0	1620.0	72.0	1624.7	840.0

GUARDRAIL SCHEDULE

STATION	RT/LT	SPBGR (FT)	TBT - T1 (SPECIAL) (EA)	TBT-T6 (EA)	GUARDRAIL MRKS TY-A (EA)	PRISMATIC BAR. REFLEC. (EA)
463+75.25	TO 466+94.00	LT	225.0	1	1	4
466+94.00	TO 468+09.50	LT				2
468+09.50	TO 471+03.25	LT	200.0	1	1	4
465+02.25	TO 467+08.50	RT	112.5	1	1	3
467+08.50	TO 468+26.00	RT				2
468+26.00	TO 470+32.25	RT	112.5	1	1	3
TOTAL			650.0	4	4	14

PAVEMENT MARKING SCHEDULE

STATION	RT/LT	PAVEMENT					BRIDGE		
		4" WHITE LINE (FT)	4" YELLOW LINE (FT)	YELLOW SKIP DASH LINE 4" (FT)	4" DBL YELLOW LINE (FT)	DOUBLE AMBER RSD REFL PMK (EA)	4" WHITE LINE (FT)	4" DBL YELLOW LINE (FT)	DOUBLE AMBER RSD REFL PMK (EA)
462+30.00	TO 466+71.39	RT/LT	882.78					6	
462+30.00	TO 465+00.00	CL		270.00	67.50				
465+00.00	TO 466+71.39	CL				342.78			
466+71.39	TO 468+47.42	RT/LT					352.06	352.06	2
468+47.42	TO 473+50.00	RT/LT	1005.16						
468+47.42	TO 473+50.00	CL				1005.16		6	
SUB-TOTAL			1887.94	270.00	67.50	1347.94	12	352.06	352.06
TOTAL							12	704.12	2

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAP ROUTE 304 SECTION 5BR-2 CALHOUN COUNTY
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____

Rev. Sheet 4-3-08