

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00334-00-SW	MCLEAN	14	C3.0
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT

LOCATION	UNIT
STA. 10+63, 30' RT	8
STA. 12+69, 28' RT	6
STA. 12+78, 28' RT	8
TOTAL	22

LOCATION	CU YD
STA. 9+84 TO STA. 10+52 LT	21
STA. 10+44 TO STA. 12+12.7 LT	32
STA. 10+53 LT & RT	13
STA. 10+53.8 LT	35
STA. 10+67 RT	54
STA. 10+74 TO STA. 12+45 RT	34
CONTINGENCY	31
TOTAL	220

LOCATION	EACH
STA. 10+48.7, 17' LT	1
STA. 10+74, 34' RT	1
STA. 12+61.8, 28.5' RT	1
STA. 12+66.8, 18' LT	1
TOTAL	4

LOCATION	CLASS A	CLASS B
	TYPE 2, 12"	TYPE 1, 10"
	FOOT	FOOT
STA. 10+53.8 LT	23	
STA. 10+66 TO STA. 10+73 RT		8
STA. 10+67 RT	35	
CONTINGENCY	2	2
TOTAL	60	10

LOCATION	MANHOLE, SPECIAL	INLET TYPE A WITH TYPE 3 FRAME AND GRATE	INLET TYPE A1, SPECIAL
	EACH	EACH	EACH
STA. 10+48.7, 18' LT		1	
STA. 10+61.6	1		
STA. 10+65.5, 36' RT			1
STA. 10+73, 34' RT		1	
TOTAL	1	2	1

LOCATION	SIDEWALK REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CONCRETE FOUNDATION REMOVAL
	SO FT	SO YD	EACH
STA. 9+69.5 TO STA. 9+84 LT	78		
STA. 10+34 TO STA. 11+18 RT	1,272		
STA. 10+36.5 TO STA. 11+64.6 LT	1,345		
STA. 10+45.8, 26' RT			1
STA. 10+58, 26' RT			
STA. 11+27, 38' RT	25		
STA. 11+59.6 TO STA. 11+95.6 RT	452		
STA. 11+64.6 TO STA. 11+94.2 LT		38	
STA. 11+94, 35.5' RT			1
STA. 11+94.2 TO STA. 12+12.7 LT	216		
STA. 11+95.2 TO STA. 12+25.2 RT		41	
STA. 12+25 TO STA. 13+03.8 RT	1,332		
STA. 12+77, 21' LT			
CONTINGENCY	30	6	
TOTAL	4,750	85	2

LOCATION	EACH
STA 10+38.65, LT 37.31	ORNAMENTAL PLANTER 30"
STA 10+39.03, LT 34.20	ORNAMENTAL PLANTER 42"
STA 10+41.15, LT 31.94	ORNAMENTAL PLANTER 30"
STA 10+62.58, RT 36.90	ORNAMENTAL PLANTER 30"
STA 11+09.93, LT 21.17	ORNAMENTAL PLANTER 30"
STA. 11+12.07, RT 38.95	ORNAMENTAL PLANTER 30"
STA. 11+59.58, LT 21.29	ORNAMENTAL PLANTER 30"
STA. 11+70.12, RT 37.29	ORNAMENTAL PLANTER 30"
STA. 12+26.90, LT 21.88	ORNAMENTAL PLANTER 30"
STA. 12+31.09, RT 38.08	ORNAMENTAL PLANTER 30"
STA. 12+67.03, RT 32.79	ORNAMENTAL PLANTER 30"
STA. 12+68.51, LT 21.15	ORNAMENTAL PLANTER 30"
STA. 12+71.60, LT 21.19	ORNAMENTAL PLANTER 42"
STA. 12+99.10, RT 28.93	ORNAMENTAL PLANTER 30"
STA. 13+01.08, RT 31.21	ORNAMENTAL PLANTER 42"
STA. 13+02.63, RT 34.16	ORNAMENTAL PLANTER 30"
STA. 10+56.11, RT 36.22	METAL BENCH, 8'
STA. 10+61.55, RT 30.93	METAL BENCH, 8'
STA. 10+82.99, LT 27.23	METAL BENCH, 8'
STA. 11+04.23, RT 45.19	METAL BENCH, 8'
STA. 12+67.83, RT 26.67	METAL BENCH, 8'
STA. 12+73.30, RT 32.20	METAL BENCH, 8'
STA. 12+77.56, LT 20.21	METAL BENCH, 8'
STA. 12+82.85, RT 21.24	BIKE RACK
STA. 10+66.55, RT 30.67	BIKE RACK

LOCATION	SIDEWALK, SPECIAL	P.C.C. DRIVEWAY PAVEMENT, 6"	P.C.C. BASE COURSE 7"	HOT-MIX ASPHALT SURFACE COURSE MIX C, N50
	SO FT	SO YD	SO YD	TON
STA. 9+69.5 TO STA. 9+84 LT	78			
STA. 9+84 TO STA. 10+52 LT			45	8
STA. 10+32 TO STA. 10+74 RT			28	5
STA. 10+34 TO STA. 11+18 RT	1,272			
STA. 10+36.5 TO STA. 11+64.6 LT	1,320			
STA. 10+40 LT			14	3
STA. 10+44 TO STA. 12+12.7 LT			57	10
STA. 10+53 LT & RT			12	2
STA. 10+53.8 LT			3	1
STA. 10+67 RT			10	2
STA. 10+74 TO STA. 12+88 RT			71	13
STA. 11+59.6 TO STA. 11+95.6 RT	452			
STA. 11+64.6 TO STA. 11+94.2 LT		31		
STA. 11+94.2 TO STA. 12+12.7 LT	280			
STA. 11+95.2 TO STA. 12+25.2 RT		41		
STA. 12+25 TO STA. 13+03.8 RT	1,332			
CONTINGENCY	11	8	20	6
TOTAL	4,750	80	260	50

LOCATION	EACH
STA. 10+72.32, LT 21.42	CHANTICLEER CALLERY PEAR, 2 1/2" B.B.
STA. 11+27.38, RT 38.16	CHANTICLEER CALLERY PEAR, 2 1/2" B.B.
STA. 12+76.23, RT 24.26	FRONTIER ELM, 2 1/2" B.B.
STA. 10+49.02 TO STA. 10+56.02, RT 26.49 TO RT 31.99	STRAWBERRY CANDY DAYLILY - GROUPING OF 10
STA. 10+69.84 TO 10+74.84, LT 18.91 TO LT 23.91	STRAWBERRY CANDY DAYLILY - GROUPING OF 8
STA. 11+24.89 TO 11+29.89, RT 35.66 TO RT 40.66	STRAWBERRY CANDY DAYLILY - GROUPING OF 8
STA. 12+72.85 TO 12+79.85, RT 21.21 TO RT 27.21	STRAWBERRY CANDY DAYLILY - GROUPING OF 10

NOTE: FOR ELECTRICAL SCHEDULES SEE E1.3

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
		CITY OF BLOOMINGTON DOWNTOWN MAIN STREET BEAUTIFICATION FRONT STREET TO WASHINGTON STREET
		SCALE: VERT. HORIZ. DATE: 01-31-08
		DRAWN BY: DVH CHECKED BY: JCB