

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	06-00009-01-FP	ST. CLAIR	69	4
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT--				
SCHEDULE OF QUANTITIES				
CONTRACT NO. 97312				

FENCE GUARDRAIL SCHEDULE													
STA	RT/LT	CHAIN LINK FENCE REMOVAL 66410300 (FOOT)	CHAINLINK FENCE 6' (SPECIAL) 66400560 (FOOT)	CHAINLINK FENCE 4' 66400105 (FOOT)	CHAIN LINK FENCE 4' ATTACHED TO STRUCTURE 66400525 (FOOT)	STEEL PLATE BEAM GUARD RAIL, TYPE B 63000005 (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT) 63100167 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 2 63100045 (EACH)	STEEL PLATE BEAM GUARD RAIL, TYPE B 63000005 (FOOT)	STEEL PLATE BEAM GUARD RAIL, TYPE A 63000000 (FOOT)	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES (SPECIAL) 63000155 (FOOT)	STEEL RAILING, TYPE 2399 X0325701 (FOOT)	TRAFFIC BARRIER, TYPE SA 63100075 (EACH)
SAUGET BUSINESS BOULEVARD													
79+40	RT			117	33		1		63				
79+40	LT			127	33			1		25			
80+00	RT								25				
80+29	LT							1		63		37	2
80+29	RT						1					37	2
98+50	RT	60	50										
101+95	RT						1						
102+52	LT							1					
102+20	RT									100	25		
103+00	LT						1			125	25		
103+45	RT					43		1		50			
104+13	RT					43				50			
103+82	RT												
104+45	RT												
103+12	RT			45	35								
103+12	LT			80									
MOUSETTE LANE (EAST)													
46+75	LT			60			1	1	50	75	16		
TOTAL		60	50	429	101	86	5	5	236	366	66	74	4

EROSION SCHEDULE				
STATION	STATION	EROSION CONTROL BLANKET 25100630 (SQ YD)	AGGREGATE DITCH CHECKS 28000310 (EACH)	PERIMETER EROSION CONTROL BARRIER 28000400 (FOOT)
SAUGET BUSINESS BLVD.				
46+50	80+00	0		10
46+92		64		0
53+55		64		
56+00		64		
83+00		64		2765
80+00	95+00	64	6	
95+00	103+00	0	3	560
103+00	107+50	128	2	1255
107+50	109+00	64	2	1585
SAUGET INDUSTRIAL PARKWAY				
156+88	162+00.5	64	2	925
MOUSETTE LANE (EAST)				
44+00	49+25	64	1	
GOOSE LAKE ROAD				
43+00	44+00	0	1	530
43+10		211		
TOTAL		851	27	7620

PIPE CULVERT REMOVAL SCHEDULE			
STATION		PIPE CULVERT REMOVAL 50105220 (FOOT)	CULVERTS TO BE GROUTED X0325561" (CU YD)
SAUGET BUSINESS BLVD.			
76+81	RT 20" STL		36
99+50	LT 24" RCP		70
INDUSTRIAL PARKWAY			
159+52	RCP 24"		54
MOUSETTE LANE (EAST)			
46+92	RT LT 4 42" FES		32
GOOSE LAKE ROAD			
43+11	RT LT 2 FES 48"		16
RAMP 3			
30+40	RT FES		8

T:\clients\BUSEY\131317-1.phd\dwg\02-06 Summary of Quantities.dwg, 03 Fence culvert removal, 4/12/2008 5:57:35 PM, Jpg, 1/1/2008 5:57:35 PM, 11, PHHW07.PHW03