

**SUMMARY OF QUANTITIES**

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL PROJECT QUANTITY	BASE BID QUANTITY	ADD. ALT. #1 QUANTITY	UTILITIES QUANTITY	BUILDING QUANTITY
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	1	0	0	0
AR152455	EMBANKMENT IN PLACE	C.Y.	7950	6650	0	0	1300
AR156510	SILT FENCE	L.F.	1815	1815	0	0	0
AR156520	INLET PROTECTION	EACH	12	12	0	0	0
AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	9050	9050	0	0	0
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	365	365	0	0	0
AR501508	8" PCC PAVEMENT	S.Y.	8685	8685	0	0	0
AR501530	PCC TEST BATCH	EACH	1	1	0	0	0
AR501604	4" PCC SIDEWALK	S.F.	72	0	0	72	0
AR501690	PCC SIDEWALK REMOVAL	S.F.	72	0	0	72	0
AR620510	PAVEMENT MARKING	S.F.	5325	5325	0	0	0
AR162324	CLASS E GATE 24' - VINYL	EACH	1	1	0	0	0
AR162410	CLASS E FENCE, VINYL-10'	L.F.	680	680	0	0	0
AR162730	ELECTRIC GATE - 30'	EACH	1	1	0	0	0
AR162900	REMOVE CLASS E FENCE	L.F.	320	320	0	0	0
AR163510	TEMPORARY FENCE	L.F.	1315	1315	0	0	0
AR800280	CLASS E FENCE W/SCREEN	L.F.	55	55	0	0	0
AR800353	ACCESS CONTROLS	L.S.	1	1	0	0	0
AR701008	8" PVC STORM SEWER	L.F.	110	110	0	0	0
AR701512	12" RCP, CLASS IV	L.F.	690	690	0	0	0
AR701515	15" RCP, CLASS IV	L.F.	605	605	0	0	0
AR751410	INLET	EACH	9	9	0	0	0
AR751530	MANHOLE	EACH	2	2	0	0	0
AR754410	COMB CONCRETE CURB & GUTTER	L.F.	330	330	0	0	0
AR760302	2" WATER MAIN	L.F.	165	0	0	165	0
AR760308	8" WATER MAIN	L.F.	925	0	0	925	0
AR760720	20" STEEL CASING	L.F.	20	0	0	20	0
AR760800	FIRE HYDRANT	EACH	4	0	0	4	0
AR760830	WATER VALVE	EACH	7	0	0	7	0
AR760840	IRON FITTINGS	LB.	2630	0	0	2630	0
AR800271	PRESSURE TESTING OF WATERMAIN	L.S.	1	0	0	1	0
AR800272	DISINFECTION OF WATERMAIN	L.S.	1	0	0	1	0
AR800325	CONTROLLED LOW STRENGTH MATERIAL	C.Y.	14	0	0	14	0
AR800382	PAVEMENT REMOVAL AND REPLACEMENT	S.Y.	23	0	0	23	0
AR770506	6" SANITARY SEWER	L.F.	270	0	0	270	0
AR770945	ADJUST SANITARY MANHOLE	EACH	1	0	0	1	0
AR800276	LEAKAGE TESTING	L.F.	270	0	0	270	0
AR800383	SANITARY SEWER FITTINGS	LB.	450	0	0	450	0
AR901510	SEEDING	ACRE	6	0	0	0	0
AR904510	SODDING	S.Y.	615	615	0	0	0
AR908510	MULCHING	ACRE	6	6	0	0	0
AR908520	EXCELSIOR BLANKET	S.Y.	7475	7475	0	0	0
AR910101	ROADWAY LIGHT POLE, TYPE A	EACH	3	3	0	0	0
AR910102	ROADWAY LIGHT POLE, TYPE B	EACH	1	1	0	0	0
AR800306	LIGHTING CONTROLS	L.S.	1	1	0	0	0
AR910200	ROADWAY SIGN	EACH	6	6	0	0	0
AR910230	HANDICAP SIGN	EACH	1	1	0	0	0
AR910420	BOLLARD	EACH	12	12	0	0	0
AR910915	REMOVE ROADWAY SIGN	EACH	3	3	0	0	0
AR800304	FLAG POLE	EACH	1	1	0	0	0
AR108108	1/C #8 5 KV UG CABLE	L.F.	195	195	0	0	0
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	410	410	0	0	0
AR108812	12 PAIR CONTROL CABLE	L.F.	1140	1140	0	0	0
AR800349	2 - #8 USE, 1 - #10 GROUND	L.F.	250	250	0	0	0
AR800350	2 - #10 USE, 1 - #10 GROUND	L.F.	400	400	0	0	0
AR800351	6/C #18 SHIELDED CABLE	L.F.	400	400	0	0	0
AR800352	2/C #14 SHIELDED CABLE	L.F.	200	200	0	0	0
AR800219	30-FIBER OPTIC CABLE IN UD	L.F.	4140	4140	0	0	0
AR110201	1" PVC DUCT, DIRECT BURY	L.F.	1020	1020	0	0	0
AR110202	2" PVC DUCT, DIRECT BURY	L.F.	460	460	0	0	0
AR110204	4" PVC DUCT, DIRECT BURY	L.F.	1055	0	0	1055	0
AR110212	2" STEEL DUCT, DIRECT BURY	L.F.	20	20	0	0	0
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	1090	1090	0	0	0
AR110550	SPLIT DUCT	L.F.	100	100	0	0	0
AR110900	REMOVE DUCT	L.F.	1215	1215	0	0	0
AR800231	INSTALL UTILITY PAD	EACH	1	0	0	1	0
AR800254	ELECTRICAL HANDHOLE - 4'	EACH	4	3	0	1	0
AR800307	POLYMER CONCRETE HANDHOLE	EACH	3	3	0	0	0
AR125441	TAXI GUIDANCE SIGN, 1 CHARACTER	EACH	1	1	0	0	0
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1	1	0	0	0
AR125585	SPLICE CAN	EACH	1	1	0	0	0
AR125965	RELOCATE RWY DISTANCE REMAIN SIGN	EACH	1	1	0	0	0
AR800294	REPLACE SIGN FACE	EACH	1	1	0	0	0
AS209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	880	0	880	0	0
AS501508	8" PCC PAVEMENT	S.Y.	840	0	840	0	0
AS620510	PAVEMENT MARKING	S.F.	30	0	30	0	0


**INDEX TO SHEETS**

NUMBER	TITLE
01	COVER SHEET
02	INDEX TO SHEETS AND SUMMARY OF QUANTITIES
03	AIRPORT SITE PLAN
04	CONSTRUCTION ACTIVITY PLAN
05	CONSTRUCTION ACTIVITY PLAN DETAILS 1
06	CONSTRUCTION ACTIVITY PLAN DETAILS 2
07	EXISTING CONDITIONS & REMOVALS 1
08	EXISTING CONDITIONS & REMOVALS 2
09	PROPOSED IMPROVEMENTS SITE PLAN
10	PROPOSED IMPROVEMENTS 1
11	PROPOSED IMPROVEMENTS 2
12	PROPOSED IMPROVEMENTS 3
13	TYPICAL SECTIONS
14	ARFF RESPONSE ROAD PLAN & PROFILE
15	ARFF RESPONSE & SERVICE ROAD PLAN & PROFILE
16	SERVICE ROAD PLAN & PROFILE
17	GRADING PLAN
18	STAKING PLAN 1
19	STAKING PLAN 2
20	JOINTING PLAN 1
21	JOINTING PLAN 2
22	JOINTING DETAILS 1
23	JOINTING DETAILS 2
24	PAVING AND MISCELLANEOUS DETAILS 1
25	PAVING AND MISCELLANEOUS DETAILS 2
26	DRAINAGE PLAN 1
27	DRAINAGE PLAN 2
28	STORM SEWER PROFILES 1
29	STORM SEWER PROFILES 2
30	INLET DETAILS
31	DRAINAGE DETAILS
32	MARKING AND SIGNAGE PLAN 1
33	MARKING AND SIGNAGE PLAN 2
34	MARKING AND SIGNAGE DETAILS 1
35	MARKING AND SIGNAGE DETAILS 2
36	UTILITY PLAN 1
37	UTILITY PLAN 2
38	SANITARY SEWER PLAN & PROFILE 1
39	SANITARY SEWER PLAN & PROFILE 2
40	WATER MAIN DETAILS
41	SANITARY SEWER DETAILS
42	ELECTRICAL PLAN 1
43	ELECTRICAL PLAN 2
44	LIGHTING DETAILS
45	ELECTRICAL DETAILS 1
46	ELECTRICAL DETAILS 2
47	AIRFIELD SIGNAGE DETAILS
48	FENCING PLAN
49	FENCE DETAILS 1
50	FENCE DETAILS 2
51	ELECTRIC GATE DETAILS 1
52	ELECTRIC GATE DETAILS 2
53	ELECTRIC GATE DETAILS 3
54	ELECTRIC GATE DETAILS 4
55	ONE-LINE DIAGRAM
56	EROSION CONTROL & TURFING PLAN 1
57	EROSION CONTROL & TURFING PLAN 2
58	EROSION CONTROL DETAILS
59	INDEX TO CROSS SECTIONS
60	EARTHWORK SUMMARY
61	BASELINE A CROSS SECTIONS 1 STA. 37+00 TO STA. 39+00
62	BASELINE A CROSS SECTIONS 2 STA. 39+50 TO STA. 43+50
63	BASELINE A CROSS SECTIONS 3 STA. 44+00 TO STA. 45+18
64	BASELINE A CROSS SECTIONS 4 STA. 45+61.37 TO STA. 46+77.86
65	BASELINE B CROSS SECTIONS STA. 142+50 TO STA. 145+50
66	BASELINE C CROSS SECTIONS STA. 0+11.91 TO STA. 4+24.89

K:\Bloomington\0508508\_BMI\_ARFF\Draw\Sheets  
 FILE: INDEX-SUM.dwg  
 UPDATE BY: Kristy Brod  
 PLOT DATE: 4/21/2008 3:34 PM


**BL064**

REVISIONS		
NUMBER	BY	DATE



**BLOOMINGTON-NORMAL AIRPORT AUTHORITY**  
**CENTRAL ILLINOIS REGIONAL AIRPORT**  
**BLOOMINGTON, ILLINOIS**

**CONSTRUCT NEW ARFF FACILITY**  
**INDEX TO SHEETS AND SUMMARY OF QUANTITIES**


**CMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 164-000616

DESIGN BY:	KLB
DRAWN BY:	CMT
CHECKED BY:	<i>RW</i>
APPROVED BY:	<i>RW</i>
DATE:	04/01/2008
JOB No:	0508509
IL PROJ. NO.	BMI-3797
AIP PROJ. NO.	3-17-0006-46 & 48
SHEET	02 OF 66 SHEETS