


EARTHWORK QUANTITIES:

UNCLASSIFIED EXCAVATION	10,050 C.Y.
ON-SITE BORROW	6,650 C.Y.
TOPSOILING (FROM ON-SITE)	6,050 C.Y.

NOTE: FOR ON-SITE BORROW LOCATION, SEE SITE PLAN, SHEET 3.



- NOTES:**
1. FOR PROPOSED ELEVATIONS AND OFFSETS, SEE STAKING PLAN SHEETS.
 2. FOR TYPICAL SECTIONS, SEE SHEET 9.
 3. MEET EXISTING = M.E.
 4. FILL QUANTITIES INCLUDE TOPSOIL.

LE039

HANSON

HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801

Illinois Professional Design Firm
Registration No. 184-001084

© Copyright Hanson Professional Service Inc. 2008

Chicago-Romeoville Airport

JOLIET REGIONAL PORT DISTRICT

1 George Michas Drive
Romeoville, Illinois 60446
Telephone: 815.838.9497
Fax: 815.838.9524

EXTEND RUNWAY 2-20; CONSTRUCT TAXIWAY TURNAROUND

AIP PROJECT NO. 3-17-0140-B42
IDA PROJECT NO. LOT-3792

No.	Drawing Issue Description	Date	By

Date

APRIL 18, 2008

Sheet Title

**CROSS SECTIONS
RUNWAY 2-20
STA. 151+00 THRU
STA. 152+50**

07A0166
Project Number

LDH 03/12/08
Layout By Date

LDH 03/12/08
Designed By Date

RMH 03/20/08
Reviewed By Date

LDH
Drawn By

Sheet No.

I:\07A0166\07A0166\DRAWINGS\SHEETS\2-CROSS SECTIONS\DWG APR 18, 2008 10:17AM HAUSMOR02