

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)

UNLESS OTHERWISE SHOWN.

REVISIONS
NAME DATE
R. MIRS 9-15-97
R. MIRS 12-11-97
T. RAMMACHER 12-2-99
T. RAMMACHER 12-2-99
SCALE: DRAWN BY: BUR. OF DESIGN DATE 3/18/2005 CHECKED BY
TC22

TC22 REVISION DATE:02/02/99

3/18/2005 w:BdiststdBtc22.dgn VI=TC22