F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-5	LAKE	562	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

D-91-552-99 60881

IDOT CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 100% STATE J000-2A	ROADWAY 50% STATE 50% BUFFALO GROVE SFTY-1B	ROADWAY 50% STATE 50% LONG GROVE SFTY-1B	ROADWAY 50% STATE 50% LINCOLN-SHIRE SFTY-1B	ROADWAY 50% STATE 50% CHARLES FIORE CO. I000-1A	ROADWAY 100% BUFFALO GROVE Y007	ROADWAY 100% LINCOLN-SHIRE Y007	UTILITY ADJUSTMENT Y060 100% BUFFALO GROVE	UTILITY ADJUSTMENT Y060 100% LINCOLN-SHIRE	STRUCTURES X928-2A IL 22 OVER PEDESTRIAN TUNNEL 100% STATE	STRUCTURES X928-2A IL 22 OVER PED. TUNNEL EXTENSION 100% STATE	STRUCTURES X028-1A IL 22 OVER KILDEER CREEK 100% STATE	STRUCTURES X028-1A IL 22 OVER INDIAN CREEK 100% STATE	LIGHTING Y030-1E 100% BUFFALO GROVE	SIGNING Y002-1C 100% STATE
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	30	30														
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	16	16														
M6021640	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 8 GRATE	EACH	2	2														
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6														
M6022005	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1														
M6022010	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11														
MX602420	MANHOLES, TYPE A, 1.8M DIAMETER, 2-TYPE 1 FRAMES, CLOSED LID, RESTRICTOR PLATE	EACH	6	6														
MX602455	MANHOLES, TYPE A, 2.1M DIAMETER, 2-TYPE 1 FRAMES&CLOSED LIDS WITH RESTRICTOR PLATE	EACH	1	1														
MX602089	MANHOLES, TYPE A, SPECIAL, 2.1M DIAMETER, 2-TYPE 1 FRAMES & CLOSED LIDS	EACH	1	1														
M6023515	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (600MM DEPTH)	EACH	1	1														
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	44	44														
M6023705	INLETS, TYPE A, TYPE 3 FRAME AND GRATE (600MM DEPTH)	EACH	31	31														
M6023810	INLETS, TYPE A, TYPE 8 GRATE (600 MM DEPTH)	EACH	1	1														
• M6024310	VALVE VAULTS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7									7						
• M6024410	VALVE VAULTS, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7									7						
60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	1	1														
60248000	JUNCTION CHAMBER, NO. 1	EACH	1	1														
60248100	JUNCTION CHAMBER, NO. 2	EACH	1	1														
60248200	JUNCTION CHAMBER, NO. 3	EACH	1	1														
60248300	JUNCTION CHAMBER, NO. 4	EACH	1	1														
60248400	JUNCTION CHAMBER, NO. 5	EACH	1	1														
60250200	CATCH BASINS TO BE ADJUSTED	EACH	12	12														
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	14	13							1							
60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1														
60255500	MANHOLES TO BE ADJUSTED	EACH	9	9														
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	9	9														
• 60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	28								9	19						
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	16									16						
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2									2						
• XX001047	VALVE VAULTS TO BE ABANDONED	EACH	9									9						
• X0324635	ADJUST EXISTING WATER MAIN UNDER STORM SEWER	EACH	1									1						
• X0324636	WATER VALVE BOXES TO BE ABANDONED	EACH	4									4						
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	4								2	2						
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	10								10							
60500040	REMOVING MANHOLES	EACH	21	21														
60500050	REMOVING CATCH BASINS	EACH	82	82														
X0322719	TEMPORARY DRAINAGE CONNECTION	EACH	26	26														
X0323236	TEMPORARY INLET	EACH	26	26														
X6040200	FRAMES AND LIDS, TYPE 1, OPEN LID, TEMPORARY	EACH	1	1														
M6060070	CONCRETE CURB, TYPE B	METER	402	402														
M6060500	COMBINATION CONCRETE CURB AND GUTTER TYPE B-15.30	METER	133	133														

• INDICATES SPECIALTY ITEMS

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK	TEMPLATE	
	AREAS	
NO.	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK	TEMPLATE	
	AREAS	
NO.	AREAS CHECKED	

REVISIONS NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SUMMARY OF QUANTITIES
SHEET 5 OF 8

SCALE: NONE DRAWN BY: JSM
DATE: 03-22-2004 CHECKED BY: JNR