

IDOT CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY								UTILITY ADJUSTMENT Y060		STRUCTURES				LIGHTING Y030-1E	SIGNING Y002-1C
				100% STATE	50% STATE 50% BUFFALO GROVE	50% STATE 50% LONG GROVE	50% STATE 50% LINCOLN-SHIRE	50% STATE 50% CHARLES FIORE CO.	100% BUFFALO GROVE	100% LINCOLN-SHIRE	X928-2A		X028-2A						
											100% STATE	100% STATE	IL 22 OVER PEDESTRIAN TUNNEL	IL 22 OVER PED. TUNNEL EXTENSION	IL 22 OVER KILDEER CREEK	IL 22 OVER INDIAN CREEK			
• MX830110	LIGHT POLE, STEEL, 10.5M M.H., 2-1.8M MAST ARMS	EACH	4														4		
• MX830111	LIGHT POLE, STEEL, 12.2M M.H., 2-1.8M MAST ARMS	EACH	4														4		
• M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	240														240		
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	57														57		
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	20														20		
• XX004047	LIGHTING CONTROLLER SPECIAL	EACH	2														2		
• 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2														2		
• 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1														1		
• M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	9939	5177													4762		
• 84200700	LIGHTING FOUNDATION REMOVAL	EACH	22														22		
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	18														18		
• 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4														4		
• X0324637	BASE COVER, LIGHT POLE	EACH	18														18		
• X0324723	MAINTENANCE OF LIGHTING SYSTEM	L SUM	1														1		
• X8380083	BREAKAWAY DEVICE	EACH	18														18		
MX030114	TRENCH DRAIN	METER	8																
MX030242	SLEEPER SLAB	METER	1422	1422															
MX032134	BRACED EXCAVATION	CU M	80																
MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	313	126						187									
MX033518	SEGMENTAL CONCRETE BLOCK WALL (SPECIAL)	SQ M	178								178								
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	23	23															
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	220	220															
X0323782	VORTEX MANHOLE, LOCATION NO. 1	EACH	1	1															
X0323783	VORTEX MANHOLE, LOCATION NO. 2	EACH	1	1															
X0323784	VORTEX MANHOLE, LOCATION NO. 3	EACH	1	1															
MX030199	TEMPORARY PAVEMENT	SQ M	11615	11615															
MX033519	TEMPORARY PATCHING	M TON	140	140															
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9	9															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	23	23															
X4023000	TEMPORARY ACCESS (ROAD)	EACH	28	28															
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	191	191															
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	120,004	119,643						361									
Z0002600	BAR SPLICERS	EACH	195										64			55	76		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1															
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	12	12															
Z0024478	FLEXIBLE DELINEATORS	EACH	35	35															
MZ050100	REMOVE AND RE-ERECT EXISTING HANDRAIL	METER	25														25		
MZ067300	STEEL CASING, 300MM	METER	14																
MZ067900	STEEL CASING, 600MM	METER	19																

FINAL SURVEY PLOTTED NOTE BOOK NO. _____

DATE _____

BY _____

ORIGINAL SURVEY PLOTTED NOTE BOOK NO. _____

DATE _____

BY _____

AREAS CHECKED _____

FINAL SURVEY PLOTTED NOTE BOOK NO. _____

DATE _____

BY _____

ORIGINAL SURVEY PLOTTED NOTE BOOK NO. _____

DATE _____

BY _____

AREAS CHECKED _____

• INDICATES SPECIALTY ITEMS

☐ INCLUDES Y031 IF TOTALS FROM PAGE 13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL RTE 22 (FAP 337)
 IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)
SUMMARY OF QUANTITIES
 SHEET 8 OF 8

SCALE: NONE DRAWN BY: JSM
 DATE: 03-22-2004 CHECKED BY: JNR

REV.