| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 337 | 20R-5 | LAKE | 562 | 25 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

D-91-552-99 60881

## PAVEMENT REMOVAL

| DESCRIPTION | FROM | | | TO | | | APPROX. LENGTH (METERS) | AVERAGE WIDTH (METERS) | PAVEMENT REMOVAL (SQ M) M4402000 |
|---|---|---|---|---|---|---|---|---|---|
| | ALIGNMENT | STATION | OFFSET | ALIGNMENT | STATION | OFFSET | | | |
| ILLINOIS 22 (ADJACENT TO MEDIAN) | IL 21 | 99+815 | LT/RT | IL 21 | 99+848 | LT/RT | 33 | 2 | 69 |
| ILLINOIS 22 (ADJACENT TO MEDIAN) | IL 22 | 99+962 | LT/RT | IL 22 | 99+976 | LT/RT | 14 | 2 | 34 |
| ILLINOIS 83 (RADII RETURN) | IL 22 | 99+969 | RT | IL 22 | 99+987 | RT | 18 | 5 | 88 |
| ILLINOIS 83 (RADII RETURN) | IL 22 | 100+013 | LT | IL 22 | 100+031 | LT | 18 | 5 | 95 |
| WESTBOUND ILLINOIS 22 | IL 22 | 100+025 | LT | IL 22 | 100+125 | LT | 100 | 11 | 1,077 |
| EASTBOUND ILLINOIS 22 | IL 22 | 100+015 | RT | IL 22 | 100+158 | RT | 143 | 8 | 1,132 |
| WESTBOUND ILLINOIS 22 | IL 22 | 100+125 | LT | IL 22 | 100+475 | LT | 350 | 7 | 2,608 |
| EASTBOUND ILLINOIS 22 | IL 22 | 100+158 | RT | IL 22 | 100+475 | RT | 317 | 9 | 2,762 |
| TALL OAKS DRIVE | IL 22 | 100+382 | LT | IL 22 | 100+426 | LT | 44 | 8 | 336 |
| WESTBOUND ILLINOIS 22 | IL 22 | 100+475 | LT | IL 22 | 100+835 | LT | 360 | 6 | 2,339 |
| EASTBOUND ILLINOIS 22 | IL 22 | 100+475 | RT | IL 22 | 100+835 | RT | 360 | 6 | 2,225 |
| HAMPTON DRIVE | IL 22 | 100+721 | LT | IL 22 | 100+746 | LT | 25 | 19 | 480 |
| WESTBOUND ILLINOIS 22 | IL 22 | 100+835 | LT | IL 22 | 101+180 | LT | 345 | 4 | 1,483 |
| EASTBOUND ILLINOIS 22 | IL 22 | 100+835 | RT | IL 22 | 101+180 | RT | 345 | 5 | 1,584 |
| ACACIA TERRACE | IL 22 | 101+244 | LT | IL 22 | 101+269 | LT | 25 | 8 | 198 |
| OAK GROVE DRIVE | IL 22 | 101+241 | RT | IL 22 | 101+268 | RT | 27 | 12 | 334 |
| WESTBOUND ILLINOIS 22 | IL 22 | 101+180 | LT | IL 22 | 101+510 | LT | 330 | 7 | 2,330 |
| EASTBOUND ILLINOIS 22 | IL 22 | 101+180 | RT | IL 22 | 101+510 | RT | 330 | 8 | 2,672 |
| WESTBOUND ILLINOIS 22 | IL 22 | 101+510 | LT | IL 22 | 101+800 | LT | 290 | 9 | 2,544 |
| EASTBOUND ILLINOIS 22 | IL 22 | 101+510 | RT | IL 22 | 101+800 | RT | 290 | 10 | 2,957 |
| BUFFALO GROVE RD (NORTH OF IL 22) | BUFFALO | 10+209 | LT/RT | BUFFALO | 10+332 | LT/RT | 123 | 20 | 2,455 |
| BUFFALO GROVE RD (SOUTH OF IL 22) | BUFFALO | 10+014 | LT/RT | BUFFALO | 10+189 | LT/RT | 175 | 11 | 1,982 |
| WESTBOUND ILLINOIS 22 | IL 22 | 101+800 | LT | IL 22 | 102+050 | LT | 250 | 9 | 2,321 |
| EASTBOUND ILLINOIS 22 | IL 22 | 101+800 | RT | IL 22 | 102+050 | RT | 250 | 10 | 2,530 |
| ARBORETUM WAY (NORTH OF IL 22) | IL 22 | 101+843 | LT | IL 22 | 101+898 | LT | 55 | 7 | 375 |
| ARBORETUM WAY (SOUTH OF IL 22) | IL 22 | 101+841 | RT | IL 22 | 101+883 | RT | 42 | 8 | 344 |
| WESTBOUND ILLINOIS 22 | IL 22 | 102+050 | LT | IL 22 | 102+395 | LT | 345 | 9 | 3,129 |
| EASTBOUND ILLINOIS 22 | IL 22 | 102+050 | RT | IL 22 | 102+395 | RT | 345 | 9 | 3,115 |
| WILLOW PARKWAY (NORTH OF IL 22) | IL 22 | 102+053 | LT | IL 22 | 102+122 | LT | 69 | 8 | 565 |
| WILLOW PARKWAY (SOUTH OF IL 22) | IL 22 | 102+067 | RT | IL 22 | 102+114 | RT | 47 | 7 | 316 |
| WESTBOUND ILLINOIS 22 | IL 22 | 102+395 | LT | IL 22 | 102+720 | LT | 325 | 6 | 1,874 |
| EASTBOUND ILLINOIS 22 | IL 22 | 102+395 | RT | IL 22 | 102+720 | RT | 325 | 6 | 1,942 |
| EASTON AVENUE | IL 22 | 102+437 | LT | IL 22 | 102+462 | LT | 25 | 13 | 324 |
| WESTBOUND ILLINOIS 22 | IL 22 | 102+720 | LT | IL 22 | 102+915 | LT | 195 | 6 | 1,110 |
| EASTBOUND ILLINOIS 22 | IL 22 | 102+720 | RT | IL 22 | 102+917 | RT | 197 | 6 | 1,264 |
| MAIN STREET (NORTH OF IL 22) | PRAIRIE | 10+005 | LT/RT | PRAIRIE | 10+140 | LT/RT | 135 | 12 | 1,617 |
| PRAIRIE ROAD (SOUTH OF IL 22) | PRAIRIE | 9+959 | LT/RT | PRAIRIE | 9+990 | LT/RT | 31 | 15 | 471 |
| WESTBOUND ILLINOIS 22 | IL 22 | 102+922 | LT | IL 22 | 103+060 | LT | 138 | 5 | 650 |
| EASTBOUND ILLINOIS 22 | IL 22 | 102+925 | RT | IL 22 | 103+060 | RT | 135 | 5 | 610 |
| PRAIRIE ROAD (NORTH OF IL 22) | IL 22 | 102+945 | LT | IL 22 | 102+967 | LT | 22 | 12 | 261 |
| WESTBOUND ILLINOIS 22 | IL 22 | 103+060 | LT | IL 22 | 103+400 | LT | 340 | 5 | 1,823 |
| EASTBOUND ILLINOIS 22 | IL 22 | 103+060 | RT | IL 22 | 103+400 | RT | 340 | 6 | 1,888 |
| PRAIRIE LANE | IL 22 | 103+194 | LT | IL 22 | 103+225 | LT | 31 | 10 | 324 |
| APPLE HILL LANE (NORTH OF IL 22) | IL 22 | 103+332 | LT | IL 22 | 103+379 | LT | 47 | 8 | 381 |
| APPLE HILL LANE (SOUTH OF IL 22) | IL 22 | 103+339 | RT | IL 22 | 103+373 | RT | 34 | 11 | 377 |

## PAVEMENT REMOVAL, CONTINUED

| DESCRIPTION | FROM | | | TO | | | APPROX. LENGTH (METERS) | AVERAGE WIDTH (METERS) | PAVEMENT REMOVAL (SQ M) M4402000 |
|---|---|---|---|---|---|---|---|---|---|
| | ALIGNMENT | STATION | OFFSET | ALIGNMENT | STATION | OFFSET | | | |
| WESTBOUND ILLINOIS 22 | IL 22 | 103+400 | LT | IL 22 | 103+750 | LT | 350 | 6 | 2,236 |
| EASTBOUND ILLINOIS 22 | IL 22 | 103+400 | RT | IL 22 | 103+750 | RT | 350 | 7 | 2,391 |
| STEVENSON DRIVE | IL 22 | 103+635 | LT | IL 22 | 103+673 | LT | 38 | 10 | 397 |
| PALLAZO DRIVE | IL 22 | 103+632 | RT | IL 22 | 103+666 | RT | 34 | 11 | 363 |
| WESTBOUND ILLINOIS 22 | IL 22 | 103+750 | LT | IL 22 | 104+090 | LT | 340 | 7 | 2,485 |
| EASTBOUND ILLINOIS 22 | IL 22 | 103+750 | RT | IL 22 | 104+090 | RT | 340 | 8 | 2,749 |
| HOTZ ROAD | IL 22 | 103+865 | LT | IL 22 | 103+892 | LT | 27 | 11 | 305 |
| MILLBROOK LANE | IL 22 | 103+847 | RT | IL 22 | 103+884 | RT | 37 | 12 | 428 |
| WESTBOUND ILLINOIS 22 | IL 22 | 104+090 | LT | IL 22 | 104+410 | LT | 320 | 6 | 1,976 |
| EASTBOUND ILLINOIS 22 | IL 22 | 104+090 | RT | IL 22 | 104+410 | RT | 320 | 8 | 2,584 |
| SCHELTER ROAD (SOUTH OF IL 22) | IL 22 | 104+138 | RT | IL 22 | 104+180 | RT | 42 | 27 | 1,135 |
| SCHELTER ROAD (NORTH OF IL 22) | IL 22 | 104+126 | RT | IL 22 | 104+255 | RT | 129 | 5 | 634 |
| WESTBOUND ILLINOIS 22 | IL 22 | 104+410 | LT | IL 22 | 104+600 | LT | 190 | 5 | 1,027 |
| EASTBOUND ILLINOIS 22 | IL 22 | 104+410 | RT | IL 22 | 104+600 | RT | 190 | 7 | 1,389 |
| OLD HALF DAY ROAD | HALFDAY | 10+003 | LT/RT | HALFDAY | 10+237 | LT/RT | 234 | 8 | 1,916 |
| BARCLAY BOULEVARD | IL 22 | 104+357 | RT | IL 22 | 104+396 | RT | 39 | 10 | 406 |
| TOTAL | | | | | | | | | 81,816 |

## GUARDRAIL REMOVAL

| DESCRIPTION | FROM | | | TO | | | GUARD RAIL REMOVAL (METERS) M6320030 |
|---|---|---|---|---|---|---|---|
| | ALIGNMENT | STATION | OFFSET | ALIGNMENT | STATION | OFFSET | |
| ILLINOIS 22 AT KILDEER CREEK | ILLINOIS 22 | 100+931 | RT | ILLINOIS 22 | 101+015 | RT | 84 |
| ILLINOIS 22 AT KILDEER CREEK | ILLINOIS 22 | 100+948 | LT | ILLINOIS 22 | 101+025 | LT | 77 |
| TOTAL | | | | | | | 161 |

| FINAL SURVEY | BY | DATE |
|---|---|---|
| SURVEYED | | |
| PLOTTED | | |
| TEMPLATE | | |
| AREAS | | |
| AREAS CHECKED | | |
| NOTE BOOK | | |
| NO. | | |

| ORIGINAL SURVEY | BY | DATE |
|---|---|---|
| SURVEYED | | |
| PLOTTED | | |
| TEMPLATE | | |
| AREAS | | |
| AREAS CHECKED | | |
| NOTE BOOK | | |
| NO. | | |

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SCHEDULE OF QUANTITIES

SHEET 1 OF 14

SCALE: NONE DRAWN BY: JSM

DATE: 03-22-2004 CHECKED BY: JNR

P:\6033P\Road\sc22rsh01.dgn 03/25/2004 06:02:01 PM