F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-5	LAKE	562	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

D-91-552-99 60881

PROPOSED PAVEMENT

DESCRIPTION	FROM			TO			PCC PVT 250 JOINTED (SQ M) M4202255	AGG SUBGRADE 300 (SQ M) MZ001050	BC SC SUPER "C" N50 (M TON) MX406012	BC BC SUPER "D" N70 (M TON) MX406024	BC BC SUPER IL-19.0 N70 (SQ M) MX406216	BIT BC SUPER 250 (SQ M) MX355250	BC BC WIDE SUPER 250 (SQ M) M3560250	PAVEMENT FABRIC (SQ M) M4205100	POLY BC SC SUPER "F" N90 (M TON)
	ALIGNMENT	STATION	OFFSET	ALIGNMENT	STATION	OFFSET									
ILLINOIS 22 MEDIAN	IL 22	102+110	-	IL 22	102+181	-		97							
EASTON AVENUE	IL 22	102+434	LT	IL 22	102+463	LT	136	354	15		15		45		
ILLINOIS 22 MEDIAN	IL 22	102+388	-	IL 22	102+433	-		68							
WESTBOUND ILLINOIS 22	IL 22	102+448	LT	IL 22	102+913	LT	3778	4256							
ILLINOIS 22 MEDIAN	IL 22	102+592	-	IL 22	102+661	-		93							
ILLINOIS 22 MEDIAN	IL 22	102+778	-	IL 22	102+832	-		157							
EASTBOUND ILLINOIS 22	IL 22	102+448	RT	IL 22	102+918	RT	4245	4734							
ILLINOIS 22 MEDIAN	IL 22	102+869	-	IL 22	102+917	-		109							
MAIN STREET (NORTH OF IL 22)	PRAIRIE	10+012	LT/RT	PRAIRIE	10+140	LT/RT	1622	1860							
PRAIRIE ROAD (SOUTH OF IL 22)	PRAIRIE	9+800	LT/RT	PRAIRIE	9+959	LT/RT		550		213	218	550			
PRAIRIE ROAD (SOUTH OF IL 22)	PRAIRIE	9+959	LT/RT	PRAIRIE	9+990	LT/RT	773	860							
ILLINOIS 22/RR XING (NW)	IL 22	102+909	LT	IL 22	102+916	LT		28		3	3			65	
ILLINOIS 22/RR XING (SW)	IL 22	102+915	RT	IL 22	102+920	RT		19		2	2			43	
ILLINOIS 22/RR XING (NE)	IL 22	102+922	LT	IL 22	102+929	LT		28		3	3			65	
ILLINOIS 22/RR XING (SE)	IL 22	102+928	RT	IL 22	102+933	RT		19		2	2			43	
ILLINOIS 22 MEDIAN	IL 22	102+927	-	IL 22	102+967	-		87							
PRAIRIE ROAD (NORTH OF IL 22)	IL 22	102+929	LT	IL 22	102+979	LT	337	400							
WESTBOUND ILLINOIS 22	IL 22	102+924	LT	IL 22	103+355	LT	3719	3897							
ILLINOIS 22 MEDIAN	IL 22	103+122	-	IL 22	103+198	-		102							
EASTBOUND ILLINOIS 22	IL 22	102+930	RT	IL 22	103+355	RT	3742	4365							
ILLINOIS 22 MEDIAN	IL 22	103+223	-	IL 22	103+340	-		217							
PRAIRIE LANE	IL 22	103+178	LT	IL 22	103+229	LT	271	479	13		13		30		
APPLE HILL LANE (NORTH OF IL 22)	IL 22	103+289	LT	IL 22	103+371	LT	414	601	9		9		15		
APPLE HILL LANE (SOUTH OF IL 22)	IL 22	103+336	RT	IL 22	103+425	RT	532	611							
WESTBOUND ILLINOIS 22	IL 22	103+355	LT	IL 22	103+653	LT	2592	2873							
ILLINOIS 22 MEDIAN	IL 22	103+371	-	IL 22	103+634	-		423							
EASTBOUND ILLINOIS 22	IL 22	103+355	RT	IL 22	103+653	RT	2802	3033							
STEVENSON DRIVE	IL 22	103+642	LT	IL 22	103+678	LT	446	496							
PALLAZO DRIVE	IL 22	103+632	RT	IL 22	103+698	RT	303	349							
WESTBOUND ILLINOIS 22	IL 22	103+653	LT	IL 22	103+874	LT	2677	2878							
ILLINOIS 22 MEDIAN	IL 22	103+672	-	IL 22	103+851	-		238							
EASTBOUND ILLINOIS 22	IL 22	103+653	RT	IL 22	103+873	RT	2056	2243							
HOTZ ROAD	IL 22	103+863	LT	IL 22	103+893	LT	168	442	19		20		43		
MILLBROOK LANE	IL 22	103+845	RT	IL 22	103+890	RT	359	394							
WESTBOUND ILLINOIS 22	IL 22	103+874	LT	IL 22	104+167	LT	2521	2799							
ILLINOIS 22 MEDIAN	IL 22	103+893	-	IL 22	103+963	-		96							
EASTBOUND ILLINOIS 22	IL 22	103+873	RT	IL 22	104+167	RT	3045	3340							
ILLINOIS 22 MEDIAN	IL 22	104+082	-	IL 22	104+137	-		82							
SCHELTER ROAD (NORTH OF IL 22)	IL 22	104+116	LT	IL 22	104+189	LT	468	563							
SCHELTER ROAD (SOUTH OF IL 22)	IL 22	104+128	RT	IL 22	104+172	RT	1219	1364							
WESTBOUND ILLINOIS 22	IL 22	104+167	LT	IL 22	104+374	LT	2075	2205							
EASTBOUND ILLINOIS 22	IL 22	104+167	RT	IL 22	104+374	RT	2407	2542							
ILLINOIS 22 MEDIAN	IL 22	104+178	-	IL 22	104+356	-		307							
WESTBOUND ILLINOIS 22	IL 22	104+374	LT	IL 22	104+600	LT	2098	2353							
EASTBOUND ILLINOIS 22	IL 22	104+374	RT	IL 22	104+522	RT	1122	1901							

FINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED — BY — DATE — NOTE BOOK NO.

ORIGINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED — BY — DATE — NOTE BOOK NO.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

SCHEDULE OF QUANTITIES

SHEET 8 OF 14

SCALE: NONE — DRAWN BY: JSM

DATE: 03-22-2004 — CHECKED BY: JNR